

6/2/84



JCFE RHH: 10/1/84  
137830  
Darius

1c

PROJECT FOR  
PERFORMANCE OF  
REMEDIAL RESPONSE ACTIVITIES AT  
UNCONTROLLED HAZARDOUS  
SUBSTANCE FACILITIES—ZONE 1

NUS CORPORATION  
SUPERFUND DIVISION

AR100144

ORIGINAL  
(ked)

R-585-4-4-32  
DESK-TOP PRELIMINARY ASSESSMENT AND SITE INSPECTION OF  
RHINEHART TIRE DUMP  
PREPARED UNDER

TDD NO. F3-8403-07  
EPA NO. VA-278  
CONTRACT NO. 68-01-6699

FOR THE  
HAZARDOUS SITE CONTROL DIVISION  
U.S. ENVIRONMENTAL PROTECTION AGENCY

SEPTEMBER 28, 1984

NUS CORPORATION  
SUPERFUND DIVISION

SUBMITTED BY

REVIEWED BY

APPROVED BY

Richard Gorrell  
RICHARD GORRELL  
ENVIRON. ENGINEER

William Wentworth  
WILLIAM WENTWORTH  
ASST. MANAGER, REPORTS

Garth Glenn  
GARTH GLENN  
MANAGER, FIT III

AR100145

TABLE OF CONTENTS

<u>SECTION</u>		<u>PAGE</u>
1.0	INTRODUCTION	1-1
1.1	AUTHORIZATION	1-1
1.2	SCOPE OF WORK	1-1
1.3	SUMMARY	1-1
2.0	THE SITE	2-1
2.1	LOCATION	2-1
2.2	SITE LAYOUT	2-1
2.3	OWNERSHIP HISTORY	2-1
2.4	SITE USE HISTORY	2-2
2.5	PERMIT AND REGULATORY ACTION HISTORY	2-2
2.6	REMEDIAL ACTION TO DATE	2-2
3.0	ENVIRONMENTAL SETTING	3-1
3.1	SURFACE WATERS	3-1
3.2	GEOLOGY AND SOILS	3-1
3.3	GROUNDWATERS	3-3
3.4	CLIMATE AND METEOROLOGY	3-4
3.5	LAND USE	3-4
3.6	POPULATION DISTRIBUTION	3-4
3.7	WATER SUPPLY	3-5
3.8	CRITICAL ENVIRONMENTS	3-5
4.0	WASTE TYPES AND QUANTITIES	4-1
5.0	EPA ASSESSMENT FORMS	5-1
5.1	EPA PRELIMINARY ASSESSMENT FORM	
5.2	EPA SITE INSPECTION FORM	

ORIGINAL  
(Red)

Site Name: Rhinehart Tire Dump  
TDD No.: F3-8403-07

APPENDICES

A	1.0	COPY OF TDD	A-1
B	1.0	MAPS AND SKETCHES	B-1
	1.1	SITE LOCATION MAP	
	1.2	SITE SKETCH	
C	1.0	VIRGINIA STATE WATER CONTROL BOARD; LABORATORY DATA ON WATER SAMPLES TAKEN AT RHINEHART TIRE DUMP	C-1
D	1.0	U.S. EPA ERT; TECHNOLOGICAL CONSIDERATIONS AND APPROACH REGARDING RHINEHART TIRE DUMP FIRE	D-1
E	1.0	HYDROGEOLOGICAL AND GEOLOGIC BACKGROUND INFORMATION FOR THE RHINEHART TIRE DUMP	E-1
F	1.0	TELECON NOTES DOCUMENTING BACKGROUND INFORMATION PERTAINING TO THE RHINEHART TIRE DUMP	F-1
G	1.0	U.S. EPA, <u>PRELIMINARY ENVIRONMENTAL ASSESSMENT REPORT FOR THE RHINEHART TIRE FIRE</u>	G-1



SECTION 1

AR100148

ORIGINAL  
(Red)

Site Name: Rhinehart Tire Dump  
TDD No.: F3-8403-07

## 1.0 INTRODUCTION

### 1.1 Authorization

NUS Corporation performed this work under Environmental Protection Agency Contract No. 68-01-6699. This specific report was prepared in accordance with Technical Directive Document No. F3-8403-07 for the Rhinehart Tire Dump located in Frederick County, Winchester, Virginia.

### 1.2 Scope of Work

NUS Corporation was tasked to complete a desk-top Preliminary Assessment, Site Inspection, and Hazard Ranking report for the subject project, based upon sample analyses data and other information provided by the U.S. EPA and the Virginia State Water Control Board (VA SWCB). The Hazard Ranking report has been submitted under separate cover.

### 1.3 Summary

After reviewing data and reports supplied by EPA and the VA SWCB, as well as discussing the site with Virginia officials, NUS FIT III completed a desk-top Preliminary Assessment and Site Inspection report.

The Rhinehart Tire Dump is approximately 5 acres and is located in a ravine on private property adjacent to an unnamed tributary to Hogue Run. In 1972, Mr. Paul Rhinehart, the site owner, began a tire disposal operation which consisted of transporting rubber tires from various locations to the ravine for ultimate disposal.

On October 31, 1983, the tire dump caught fire. Although the fire was brought under control within a short period, the dump continued to smolder for several months. The exact date at which the fire was declared entirely extinguished is unavailable. Combustion processes resulted in the contamination of air and the by products of the fire contaminated surface water and groundwater within the site vicinity.

Site Name: Rhinehart Tire Dump  
TDD No.: F3-8403-07

Several containment basins were constructed in an effort to mitigate surface water contamination. In addition to the containment basins, several groundwater monitoring wells were also constructed in and around the disposal area. Sampling from the test wells and residential supply wells has shown contamination in the test wells only. On February 13, 1984, the site owner consented to a C.E.R.C.L.A. Section 106 Order issued by EPA requiring control of on-site drainage.

SECTION 2

AR100151

## 2.0 THE SITE

### 2.1 Location

The Rhinehart Tire Dump is located in Western Frederick County, Virginia, in a sparsely populated area approximately 3/4 miles northwest of the town of Mount Pleasant. The nearest major road in the area is County Road 608, which passes through the town of Mount Pleasant. The town of Winchester is approximately 6 miles east of the site.

### 2.2 Site Layout

The site consists of a ravine which was filled with waste rubber tires. Although a fire at the site in 1983 reduced the volume of materials in the ravine, the original area of fill was estimated at 600 feet long by 375 feet wide with depths ranging from 20 to 40 feet.

An unnamed tributary to Hogue Run is located approximately 100 feet north of the site. Topography is such that drainage from the ravine area flows toward this stream. The general area slopes 20 to 35 percent in a north westerly direction and elevations range from 920 feet to 1,000 feet mean sea level (MSL).

Following the 1983 fire at the subject site, EPA authorized the construction of several containment structures down slope from the ravine. Currently, there are 3 of these structures on the site. The primary containment lagoon, an unlined 50,000 gallon capacity pond, is located immediately down slope from the burn area. The second lagoon, a lined 400,000 gallon capacity pond, is located adjacent to the primary lagoon. The third containment lagoon, its capacity is estimated at 1/4 of that of the second lagoon, is located adjacent to the unnamed tributary. This lagoon functions as a safety valve to ensure that oils from the second lagoon do not enter the unnamed tributary.

### 2.3 Ownership History

Previous owners of the property are not known. Mr. Paul Rhinehart has owned the property for at least the past 12 years.

Site Name: Rhinehart Tire Dump  
TDD No.: F3-8403-07

#### 2.4 Site Use History

Although records are not available, the Frederick County Administration reports that the site had been used to raise horses in the past. In 1972, Mr. Rhinehart began accepting old tires for disposal on his property. Mr. Rhinehart owns several trucks that had delivered discarded tires to the site from locations up to 200 miles away. In addition to operating this business, Mr. Rhinehart had built an incinerator that was to be used to test a process that would recover carbon black and oils from the discarded tires. The incinerator was never put into operation.

#### 2.5 Permit and Regulatory Action History

As of the this time, there have been no permit or regulatory actions associated with the subject site. However, due to complaints by local residents, activities on site were halted pursuant to a circuit court action.

#### 2.6 Remedial Action To Date

With the exception of the construction of containment structures to prevent the discharge of oils from entering adjacent surface waters and the removal of by-product oils from containment structures at the site, there have been no remedial actions to remove or properly dispose of the materials remaining on site. Approximately 800,000 gallons of oils produced by the fire have been removed from the containment structures and it is understood that they will be used as blending agents in fuel oils. It has been estimated that approximately 20 percent of the volume of materials originally placed on site remained as of April 2, 1984. On February 13, 1984, the site owner consented to a C.E.R.C.L.A. Section 106 Order issued by EPA requiring control of on-site drainage.

SECTION 3

AR100154

### 3.0 ENVIRONMENTAL SETTING

#### 3.1 Surface Waters

The site is drained by a small unnamed tributary along its western edge. This stream joins another unnamed tributary which drains a facing valley. The 2 streams confluence to form Massy Run. Massy Run flows about 1/2 mile west to Hogue Creek. Massy Run is not labeled on the U.S.G.S. Topographic 7.5' quadrangle shown in figure 1 of appendix B. The nearest public water supply intake on Hogue Creek is 22 miles downstream. Most of the on-site activities performed by EPA Emergency Response Team (ERT) were directed toward preventing oily discharges from the fire from entering Massy Run and contaminating Hogue Creek.

#### 3.2 Geology and Soils

The majority of geologic information for this site was obtained from Mr. Thomas Stone, Hydrogeologist for IT Corporation (ERT consultant). The Rhinehart Tire Dump is located on the west side of Hunting Mountain in the Appalachian section of the Ridge and Valley Province. The site is underlain by the Chemung Formation, which is defined on the Virginia Division of Mineral Resources map (by James L. Calver) as consisting of chiefly gray shale and sandstone with thin conglomerates and a few red zones (appendix D). According to Mr. Stone, the monitoring well drill logs for the site show a highly cemented, very hard, mostly fine grained sandstone with some shale and some weathered zones composed of 0.5 to 2.0 inches of clay. The formation is very massive in this area and supports near vertical fractures with a northwest-southeast trend. This alignment concides with the strike of the beds and the strike of Hunting Mountain ridge top to the immediate east of the site. The dip of the beds range from 35 to 50 degrees to the east-southeast.



As shown on the geologic map and cross section (see appendix D), the site is located on the western side of Hunting Mountain. Hunting Mountain is entirely within the Chemung Formation and is on the western limb of the Pleasant Mountain Syncline, which plunges to the south. Within a few thousand feet, east of the site, is the overlying Hampshire Formation which is comprised of red shale, mudrock, and sandstone. To the west is the underlying Braillier Formation which consists of greenish to brown micaceous shale with thin intercalated layers of fine-grained gray sandstone. Mr. Stone estimates that the actual thickness of the Chemung Formation in the site area is approximately 1,500 feet; however, since the beds are dipping, the apparent (vertical) thickness of the formation is roughly 2,000 feet. The entire thickness of the Chemung Formation is exposed at the surface with the site situated in the mid to lower strata.

The overburden in the immediate site area ranges in thickness from 20 to 30 feet on the average, but can be completely missing in the stream valleys as is the case along Massy Run. In general, the overburden is thickest on the side slopes of Hunting Mountain and thins toward the valley. The overburden is composed of weathered Chemung and, as such, consists of sandstones, shales, and clays. The sequence is gradational to bedrock with alternating layers of relatively competent material. The extent to which Mr. Rhinehart reworked the soils in the site area has not been determined. According to Mark Davis (Frederick County District Conservationist), the soils in the site area were mapped as belonging to the Wiekurt Berkes Channery silt loam 25 to 65 percent series.

### 3.3 Groundwaters

Information on groundwater in the vicinity of the site was obtained from a telephone conversation with Mr. Stone. IT Corporation installed 7 monitoring wells at the site and is in the process of finalizing a hydrogeologic assessment. According to Mr. Stone, there is no definable aquifer under the site. This is due to the presence of near vertical joints and steeply dipping beds which intersect the overburden allowing surface water to be communicated into the bedrock readily. However, there are essentially 2 flow regimes within the site area. The upper regime mainly occupies the overburden and mimics topography at an average depth of 10 feet. Flow in the overburden is generally toward the unnamed tributary and Massy Run. Deep flow in the bedrock follows a more regional path believed to be in a southeastern direction toward the axis of the synclines in the direction of plunge. Mr. Stone stated that the near surface flow is complicated by a positive vertical flow component (artesian) which impedes the infiltration of surface waters into the ground. As a result, most contaminants probably flow to the nearest downgradient stream. Some lateral flow has been observed in the overburden. Lateral flow is produced by the combined effects of the positive vertical flow component, the presence of alternating layers of relatively competent and highly weathered material in the overburden, and near vertical joints and fractures. Hydraulic conductivity rates, as determined by Mr. Stone, were  $5.4 \times 10^{-6}$  feet/sec. ( $1.6 \times 10^{-4}$  cm/sec) for the overburden and  $1.4 \times 10^{-4}$  ft./sec ( $4.2 \times 10^{-3}$  cm/sec) for the bedrock as noted in appendix E. Flow in the bedrock ranged from 0.1 gpm to 15 gpm and intersected. Reduced flow in the overburden is due to the presence of weathered material which collapses and clogs the secondary porosity near the surface.

Three (3) of the monitoring wells were installed into bedrock and 4 were installed into overburden. The maximum range in elevation monitored by the wells is 168 feet from the base of the highest well to the base of the lowest well. Little correlation can be drawn from this, which will be discussed in IT Corporation's final report. The range or extent of contamination has not been completely determined. The state of Virginia conducted a survey of the homes in the area; the results of contamination found in these wells, in conjunction with the geology, will be presented in IT Corporation's report.

Site Name: Rhinehart Tire Dump  
TDD No.: F3-8403-07

According to Mr. Stone, Mr. Rhinehart draws his drinking water from an artesian spring above the site. Analysis of his water has shown no contamination to date. The next closest residential well is approximately 1/4 mile away, according to Mr. Stone. Mr. Stone stated that local drillers told him that people on Hunting Mountain ridge have wells drilled to 300 feet or more. Mr. Stone does not know of any contamination in these bedrock wells. He said that some wastes have entered the bedrock on site, but that these wastes will probably leave through the streams. Contamination is not expected to move downward to much extent.

### 3.4 Climate and Meteorology

The climate of the Frederick County area is characteristic of a humid continental-type marked by extreme seasonal temperature changes. The mean annual air temperature is about 53°F. Annual precipitation is about 38 inches. The distribution of rainfall, which is nearly uniform throughout the year, reaches a maximum in August. The climate is modified by the higher humidity of the Atlantic Coastal area.

### 3.5 Land Use

The land usage in the site vicinity is largely rural. There are, however, some agricultural and pasture lands as well as a few small residential villages within a 3-mile radius of the site.

### 3.6 Population Distribution

There are approximately 20 homes or about 76 people residing within a 1-mile radius of the site. Most of these homes are located approximately 3/4 of a mile southeast of the site in the village of Mount Pleasant. Based on a U.S.G.S. topographic map house count, an estimated 40 residences, or 152 persons, are located within a 3-mile radius of the site.

Site Name: Rhinehart Tire Dump  
TDD No.: F3-8403-07

### 3.7 Water Supply

Water supplies in the area of the site, which draw water from the aquifer of concern (Chemung Formation), are provided by private domestic wells. There are no other sources of drinking water currently available. Local residential wells and test wells have been sampled. Although the test wells have shown contamination, no domestic wells have been found to be contaminated (see appendix C).

### 3.8 Critical Environments

Hogue Creek is a state designated "put and take" trout stream.

SECTION 4

AR100160

#### 4.0 WASTE TYPES AND QUANTITIES

Records of the materials deposited on site prior to the fire were not kept or required, since there were no permits issued to the site. The tires, as deposited on site, were not considered hazardous materials. An unknown quantity of hazardous substances, including benzene, phenol, chloroform, and styrene were released to the air as a result of the fire. An unknown quantity of hazardous materials, including benzene, phenol, methylene chloride and toluene, have been released to surface and groundwaters adjacent to the site as byproducts of the fire. These oils were partially contained within the previously described lagoons and eventually removed from the site.

SECTION 5

AR100162

ORIGINAL  
(Red)

Site Name: Rhinehart Tire Dump  
TDD No.: F3-8403-07

5.0 EPA ASSESSMENT FORMS

5.1 EPA Preliminary Assessment Form

5.2 EPA Site Inspection Form



ORIGINAL  
(Red)

TDD No. F3-8403-07

EPA		POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT PART 1 - SITE LOCATION AND INSPECTION INFORMATION		I. IDENTIFICATION	
01 SITE NAME (Legal, common, or descriptive name of site)		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER		01 STATE	02 SITE NUMBER
Rhinehart Tire Dump		Mt. Falls		VA	278
03 CITY	04 STATE	05 ZIP CODE	06 COUNTY	07 COUNTY CODE	08 CENSUS DIS.
Winchester	VA	22601	Frederick	069	VA07
09 COORDINATES LATITUDE 39° 10' 50" N LONGITUDE 78° 18' 10" W		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN			
III. INSPECTION INFORMATION					
01 DATE OF INSPECTION None by FIT III MONTH DAY YEAR		02 SITE STATUS <input type="checkbox"/> ACTIVE <input checked="" type="checkbox"/> INACTIVE		03 YEARS OF OPERATION 1972 1983 UNKNOWN BEGINNING YEAR ENDING YEAR	
04 AGENCY PERFORMING INSPECTION (Check all that apply)					
<input checked="" type="checkbox"/> A. EPA <input checked="" type="checkbox"/> B. EPA CONTRACTOR NUS Corporation <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR <input type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR <input type="checkbox"/> G. OTHER					
05 CHIEF INSPECTOR		06 TITLE		07 ORGANIZATION	08 TELEPHONE NO.
Inspection initiated by EPA, OSC, and ERT					( )
09 OTHER INSPECTORS		10 TITLE		11 ORGANIZATION	12 TELEPHONE NO.
					( )
					( )
					( )
					( )
					( )
					( )
13 SITE REPRESENTATIVES INTERVIEWED		14 TITLE	15 ADDRESS	16 TELEPHONE NO.	
N/A				( )	
				( )	
				( )	
				( )	
				( )	
				( )	
				( )	
				( )	
17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT		18 TIME OF INSPECTION Inspection initiated by fire on property by EPA Emergency Response Team. No site inspection conducted by FIT III.			
19 WEATHER CONDITIONS					
IV. INFORMATION AVAILABLE FROM					
01 CONTACT		02 OF (Agency/Organization)		03 TELEPHONE NO.	
Darius Ostrauskas		EPA Region III		(215) 597-1391	
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM		05 AGENCY	06 ORGANIZATION	07 TELEPHONE NO.	08 DATE
David R. Kindig		----	NUS Corp.	(215) 687-9510	4/13/84 MONTH DAY YEAR

AR100164



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 2 - WASTE INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
VA 278

II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 PHYSICAL STATES (Check all that apply)

☐ A SOLID ☐ E SLURRY  
☐ B POWDER/FINES ☒ F LIQUID  
☐ C SLUDGE ☒ G GAS

☒ D OTHER oils  
(Specify)

02 WASTE QUANTITY AT SITE

(Measures of waste quantities must be independent)

TONS 3,336

CUBIC YARDS --

NO OF DRUMS 14,550

03 WASTE CHARACTERISTICS (Check all that apply)

☒ A TOXIC ☐ E SOLUBLE ☐ I HIGHLY VOLATILE  
☐ B CORROSIVE ☐ F INFECTIOUS ☐ J EXPLOSIVE  
☐ C RADIOACTIVE ☒ G FLAMMABLE ☐ K REACTIVE  
☒ D PERSISTENT ☒ H IGNITABLE ☐ L INCOMPATIBLE  
☐ M NOT APPLICABLE

III. WASTE TYPE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE			
OLW	ONLY WASTE	800,000	gallons	produced as a result of fire
SOL	SOLVENTS			
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

01 CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/ DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION
SOL	Benzene	71432	all wastes were produced as a result of a fire		
OCL	Phenol	108952	on site and released to air, surface water		
SOL	Chloroform	67663	and groundwater. Results of sampling/		
SOL	Methylene Chloride	75009	monitoring conducted by EPA ERT and		
SOL	Methyl Ethyl Ketone	78933	Virginia Water Control Board are located		
SOL	Ethylene Dichloride	107062	in Appendix 3 and 4 of the Site Inspection		
SOL	1,1,1-trichloroethane	71556	Report.		
SOL	Toluene	108883			
SOL	Acetone	67641			
SOL	Xylenes	1330207			
SOL	Styrene	100425			
SOL	Ethyl Benzene	100414			
PSD	Caprolactam	--			

\*\*The above lists major organic hazardous and priority pollutants found in samples and is not a complete listing. See Appendix 3 and 4 of the Site Inspection Report for complete results.

V. FEEDSTOCKS (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS	N/A		FDS		
FDS			FDS		
FDS			FDS		

VI. SOURCES OF INFORMATION (Cite specific references e.g. State Ins. Sample Analysis Report)

EPA Environmental Response Branch Preliminary Environmental Assessment Report, 2/15/84

Virginia Water Control Board results of quantitative analyses (See Appendix C of the Site Inspection Report)

ORIGINAL  
(Red)

<b>POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT</b>		<b>I. IDENTIFICATION</b> 01 STATE   02 SITE NUMBER VA   278	
<b>PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS</b>			
<b>II. HAZARDOUS CONDITIONS AND INCIDENTS</b>			
01 <input checked="" type="checkbox"/> A. GROUNDWATER CONTAMINATION 03 POPULATION POTENTIALLY AFFECTED: <u>152</u>	02 <input checked="" type="checkbox"/> OBSERVED (DATE: <u>3/26/84</u> ) <input type="checkbox"/> POTENTIAL <input type="checkbox"/> ALLEGED 04 NARRATIVE DESCRIPTION Report of 3/26/84 by Virginia Water Control Board indicates quantitative evidence of groundwater contamination (See Appendix C of the Site Inspection Report).		
01 <input checked="" type="checkbox"/> B. SURFACE WATER CONTAMINATION 03 POPULATION POTENTIALLY AFFECTED: <u>0</u>	02 <input checked="" type="checkbox"/> OBSERVED (DATE: <u>2/15/84</u> ) <input type="checkbox"/> POTENTIAL <input type="checkbox"/> ALLEGED 04 NARRATIVE DESCRIPTION Report of 2/15/84 by EPA ERT indicates quantitative evidence of surface water contamination.		
01 <input checked="" type="checkbox"/> C. CONTAMINATION OF AIR 03 POPULATION POTENTIALLY AFFECTED: <u>152</u>	02 <input checked="" type="checkbox"/> OBSERVED (DATE: <u>2/15/84</u> ) <input type="checkbox"/> POTENTIAL <input type="checkbox"/> ALLEGED 04 NARRATIVE DESCRIPTION Report of 2/15/84 by EPA ERT indicates quantitative evidence of air contamination.		
01 <input type="checkbox"/> D. FIRE/EXPLOSIVE CONDITIONS 03 POPULATION POTENTIALLY AFFECTED: _____	02 <input type="checkbox"/> OBSERVED (DATE: _____) <input type="checkbox"/> POTENTIAL <input type="checkbox"/> ALLEGED 04 NARRATIVE DESCRIPTION None - Site has not been designated a potential fire/explosion threat.		
01 <input checked="" type="checkbox"/> E. DIRECT CONTACT 03 POPULATION POTENTIALLY AFFECTED: <u>76 (1 mi.)</u>	02 <input type="checkbox"/> OBSERVED (DATE: _____) <input checked="" type="checkbox"/> POTENTIAL <input type="checkbox"/> ALLEGED 04 NARRATIVE DESCRIPTION By-products of combustion of tires are on site in liquid and solid (residue) form.		
01 <input checked="" type="checkbox"/> F. CONTAMINATION OF SOIL 03 AREA POTENTIALLY AFFECTED: <u>5 to 10</u> <small>(Acres)</small>	02 <input checked="" type="checkbox"/> OBSERVED (DATE: <u>2/15/84</u> ) <input type="checkbox"/> POTENTIAL <input type="checkbox"/> ALLEGED 04 NARRATIVE DESCRIPTION Report of 2/15/84 by EPA ERT indicates quantitative evidence of soil contamination adjacent to the unnamed tributary to Hogue Creek.		
01 <input checked="" type="checkbox"/> G. DRINKING WATER CONTAMINATION 03 POPULATION POTENTIALLY AFFECTED: <u>2,014 (3 mi.)</u>	02 <input checked="" type="checkbox"/> OBSERVED (DATE: <u>3/16/84</u> ) <input checked="" type="checkbox"/> POTENTIAL <input type="checkbox"/> ALLEGED 04 NARRATIVE DESCRIPTION Potential exists for groundwater contamination of drinking water supplies based on preliminary results of groundwater sampling program.		
01 <input type="checkbox"/> H. WORKER EXPOSURE/INJURY 03 WORKERS POTENTIALLY AFFECTED: _____	02 <input type="checkbox"/> OBSERVED (DATE: _____) <input type="checkbox"/> POTENTIAL <input type="checkbox"/> ALLEGED 04 NARRATIVE DESCRIPTION None known.		
01 <input type="checkbox"/> I. POPULATION EXPOSURE/INJURY 03 POPULATION POTENTIALLY AFFECTED: _____	02 <input type="checkbox"/> OBSERVED (DATE: _____) <input type="checkbox"/> POTENTIAL <input type="checkbox"/> ALLEGED 04 NARRATIVE DESCRIPTION None known.		



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
VA 278

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☒ J. DAMAGE TO FLORA  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☒ POTENTIAL ☐ ALLEGED

Potential due to release of toxic/hazardous substances into air, surface waters and soils.

01 ☒ K. DAMAGE TO FAUNA  
04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☒ POTENTIAL ☐ ALLEGED

Potential due to release of toxic/hazardous substances into air, surface waters and soils.

01 ☒ L. CONTAMINATION OF FOOD CHAIN  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☒ POTENTIAL ☐ ALLEGED

Hogue Creek is a state designated "put and take" trout stream.

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES  
(Spills, Runoff, Standing liquids, Leaking drums)

02 ☒ OBSERVED (DATE: 2/13/84)

☐ POTENTIAL ☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED 152

04 NARRATIVE DESCRIPTION

On February 13, 1984, the site owner consented to a C.E.R.C.L.A. Section 106 Order issued by EPA requiring control of runoff on site.

01 ☐ N. DAMAGE TO OFFSITE PROPERTY  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL ☐ ALLEGED

None known.

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL ☐ ALLEGED

None

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL ☐ ALLEGED

None known.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

None

III. TOTAL POPULATION POTENTIALLY AFFECTED: 3,154 (4-mile radius)

IV. COMMENTS

N/A

V. SOURCES OF INFORMATION (Cite specific references, e.g., State files, sample analysis reports)

EPA ERT report of 2/15/84

Virginia Water Control Board analytical findings on analyses of surface waters, groundwaters and soils. (included with Site Inspection Report, Appendix C)

ORIGINAL  
(Red)

		<b>POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION</b> <b>PART 4 - PERMIT AND DESCRIPTIVE INFORMATION</b>		<b>I. IDENTIFICATION</b> 01 STATE: VA    02 SITE NUMBER: 278	
<b>II. PERMIT INFORMATION</b> <u>No known permits exist for the site</u>					
01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS	
<input type="checkbox"/> A. NPDOS					
<input type="checkbox"/> B. UNC					
<input type="checkbox"/> C. AIR					
<input type="checkbox"/> D. RCRA					
<input type="checkbox"/> E. RCRA INTERIM STATUS					
<input type="checkbox"/> F. SPCC PLAN					
<input type="checkbox"/> G. STATE (Specify)					
<input type="checkbox"/> H. LOCAL (Specify)					
<input type="checkbox"/> I. OTHER (Specify)					
<input checked="" type="checkbox"/> J. NONE					
<b>III. SITE DESCRIPTION</b>					
01 STORAGE/DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER	
<input type="checkbox"/> A. SURFACE IMPOUNDMENT <input type="checkbox"/> B. PILES <input type="checkbox"/> C. DRUMS, ABOVE GROUND <input type="checkbox"/> D. TANK, ABOVE GROUND <input type="checkbox"/> E. TANK, BELOW GROUND <input type="checkbox"/> F. LANDFILL <input type="checkbox"/> G. LANDFARM <input type="checkbox"/> H. OPEN DUMP <input type="checkbox"/> I. OTHER (Specify)	<u>Before the fire, an unknown quantity of tires existed on site. After the fire, 3 surface impoundments totalling an estimated 450,000 gallons were constructed to contain contaminated runoff from fire area.</u>		<input type="checkbox"/> A. INCINERATION <input type="checkbox"/> B. UNDERGROUND INJECTION <input type="checkbox"/> C. CHEMICAL/PHYSICAL <input type="checkbox"/> D. BIOLOGICAL <input type="checkbox"/> E. WASTE OIL PROCESSING <input type="checkbox"/> F. SOLVENT RECOVERY <input type="checkbox"/> G. OTHER RECYCLING/RECOVERY <input checked="" type="checkbox"/> H. OTHER <u>none</u> (Specify)	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE  2  06 AREA OF SITE  <u>4.5</u> (Acres)	
07 COMMENTS <p>The site was used for storage of old tires. The tires were simply piled on the ground. No permits exist for the site because the old tires were placed on private property and were not considered to be of a hazardous nature. No precautions were taken by the owner to contain the tires or to prevent access to the site.</p>					
<b>IV. CONTAINMENT</b>					
01 CONTAINMENT OF WASTES (Check one)					
<input type="checkbox"/> A. ADEQUATE, SECURE <input type="checkbox"/> B. MODERATE <input checked="" type="checkbox"/> C. INADEQUATE, POOR <input type="checkbox"/> D. INSECURE, UNSOUND, DANGEROUS					
02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC. <p>Surface impoundments were constructed by EPA after the fire was started in an effort to contain waste oils produced due to the fire on site. Three containment impoundments were constructed. Primary containment was an unlined lagoon with a 50,000 gallon capacity. Secondary containment was a lined lagoon with a capacity of approximately 400,000 gallons. The third lagoon was a back up to the secondary impoundment and was not used.</p>					
<b>V. ACCESSIBILITY</b>					
01 WASTE EASILY ACCESSIBLE: <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO					
02 COMMENTS <p>Old tires were placed in a ravine on site. No barriers or other precautions exist.</p>					
<b>VI. SOURCES OF INFORMATION</b> (Cite specific references, e.g. data files, sample analyses, reports)					
<p>Telecon - M. Sterrett, VA WCB; John Riley, Frederick County Virginia Administrator; S. Jarvella, EPA ERT. (See Appendix F of the Site Inspection Report.)</p>					



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
VA 278

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY (Check as applicable)		02 STATUS			03 DISTANCE TO SITE
SURFACE WELL		ENDANGERED	AFFECTED	MONITORED	
COMMUNITY	A. <input type="checkbox"/>	B. <input type="checkbox"/>	A. <input type="checkbox"/>	B. <input type="checkbox"/>	C. <input type="checkbox"/>
NON-COMMUNITY	C. <input type="checkbox"/>	D. <input checked="" type="checkbox"/>	D. <input checked="" type="checkbox"/>	E. <input type="checkbox"/>	F. <input type="checkbox"/>
					A. _____ (mi)
					B. 0.01 (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)				
<input checked="" type="checkbox"/> A. ONLY SOURCE FOR DRINKING <input type="checkbox"/> B. DRINKING (Other sources available) COMMERCIAL, INDUSTRIAL, IRRIGATION (No other water sources available) <input type="checkbox"/> C. COMMERCIAL, INDUSTRIAL, IRRIGATION (Limited other sources available) <input type="checkbox"/> D. NOT USED, UNUSEABLE				
02 POPULATION SERVED BY GROUND WATER 152		03 DISTANCE TO NEAREST DRINKING WATER WELL 0.1 (mi)		
04 DEPTH TO GROUNDWATER 10 to 20 (ft)	05 DIRECTION OF GROUNDWATER FLOW northwest	06 DEPTH TO AQUIFER OF CONCERN 10 to 20 (ft)	07 POTENTIAL YIELD OF AQUIFER 0.1 to 15 (gpd)	08 SOLE SOURCE AQUIFER <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO

09 DESCRIPTION OF WELLS (including location, depth, and location relative to population and buildings)

A majority of the wells used for domestic drinking water are located southeast of the site at a distance of more than 1,000 feet, draw water from a deeper location in the aquifer, and are upgradient of the direction of contaminated shallow groundwater movement.

10 RECHARGE AREA		11 DISCHARGE AREA	
<input type="checkbox"/> YES	COMMENTS	<input type="checkbox"/> YES	COMMENTS
<input type="checkbox"/> NO	unknown	<input type="checkbox"/> NO	unknown

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)			
<input checked="" type="checkbox"/> A. RESERVOIR, RECREATION, DRINKING WATER SOURCE <input type="checkbox"/> B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCES <input type="checkbox"/> C. COMMERCIAL, INDUSTRIAL <input type="checkbox"/> D. NOT CURRENTLY USED			
02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER			
NAME:		AFFECTED	DISTANCE TO SITE
Hogue Creek		<input checked="" type="checkbox"/>	0.75 (mi)
unnamed tributary to Hogue Creek		<input checked="" type="checkbox"/>	0.01 (mi)
		<input type="checkbox"/>	(mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN			02 DISTANCE TO NEAREST POPULATION
ONE (1) MILE OF SITE A. 76 NO. OF PERSONS	TWO (2) MILES OF SITE B. 570 NO. OF PERSONS	THREE (3) MILES OF SITE C. 2,014 NO. OF PERSONS	0.1 (mi)
03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE 150			04 DISTANCE TO NEAREST OFF-SITE BUILDING 0.67 (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)

Population is largely rural within 1 mile of the site and includes the small village of Mt. Pleasant southeast of the site. A major residential subdivision is located approximately 2 miles northwest of the site (Shawnee - Land).



I. IDENTIFICATION	
01 STATE	02 SITE NUM
VA	278

## P1 PERMEABILITY OF UNSATURATED ZONE (See 800)

☐ A.  $10^{-6} - 10^{-5}$  cm/sec    ☐ B.  $10^{-4} - 10^{-5}$  cm/sec    ☒ C.  $10^{-4} - 10^{-3}$  cm/sec    ☐ D. GREATER THAN  $10^{-3}$  cm/sec

## 02 PERMEABILITY OF BEDROCK (CNS-11 2102)

☐ A. IMPERMEABLE (Less than  $10^{-6}$  cm/sec)    ☐ B. RELATIVELY IMPERMEABLE ( $10^{-6} - 10^{-8}$  cm/sec)    ☒ C. RELATIVELY PERMEABLE ( $10^{-2} - 10^{-4}$  cm/sec)    ☐ D. VERY PERMEABLE (Greater than  $10^{-2}$  cm/sec)

Q3 DEPTH TO BEDROCK

20 to 30 (m)

04 DEPTH OF CONTAMINATED SOIL ZONE

unknown (R)

105 304L PM

unknown

06 NET PRECIPITATION

8

07 ONE YEAR 24 HOUR RAINFALL

## 2.5

**04 SLOPE**

SITE SLOPE

30 to 50 \*

**DIRECTION OF SITE SLOPE**

northwest

TERRAIN AVERAGE SLOPE

18

### 08 FLOOD POTENTIAL

SITE IS IN 200 YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

## 11 DISTANCE TO WETLANDS (1 acre minimum)

ESTUARINE

**OTHER**

A unknown (mi)

8. unknown (m)

## 12 DISTANCE TO CRITICAL HABITAT IN COMPOSITE MILES

\_\_\_\_\_ (m)

**ENDANGERED SPECIES: N/A**

### 1.3 LAND USE IN VICINITY

**DISTANCE TO:****COMMERCIAL/INDUSTRIAL**

**RESIDENTIAL AREAS; NATIONAL/STATE PARKS,  
FORESTS, OR WILDLIFE RESERVES**

AGRICULTURAL LANDS  
PRIME AG LAND AG LAND

A. 6 (mi)

B. 0.01 (ml)

c. unknown (mi) o. unknown (mi)

## 14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

The site is located near the summit of Hunting Ridge in the ridge and valley province of the Blue Ridge Mountains. As a result, the surrounding topography consists of wooded hills and valleys with rather steep grades.

**VII. SOURCES OF INFORMATION** (Cite specific references, e.g., newspaper, article, analysis, reports)

EPA ERT Preliminary Report (2/15/84) and files from Virginia WCB reports.  
U.S.G.S 7.5 Minute Winchester, Virginia Topographic Quad. (1973)  
Hydrogeologic and geologic background information for the Rhinehart Tire Dump as determined by Mr. Thomas Stone, Hydrogeologist of IT Corporation, subcontractor for the EPA OSC.

AR100170



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
VA 278

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN **	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	14	Virginia State WCB, Bridgewater, Virginia	See
SURFACE WATER	38	EPA Emergency Response Branch, Edison, NJ	Appendices
WASTE			
AIR	79	Clayton Environmental Consultants, Inc., (74) Weston, Inc. - SPER Division (5)	
RUNOFF		included with surface water sampling	
SPILL	4	EPA Emergency Response Branch, Edison, NJ	
SOIL			
VEGETATION			
OTHER	**Data received as of 2/15/84 - See Appendix C		

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
	None performed by FIT III

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input checked="" type="checkbox"/> AERIAL	02 IN CUSTODY OF <u>I.L.S. EPA ERT, VA WCB</u> <small>(Name of organization or individual)</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS <u>EPA ERT, Edison, NJ; IT Corporation, Edison, NJ</u>

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

No data collected by FIT III.

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

EPA ERT report of 2/15/84  
VA WCB results of quantitative analyses (See Appendix C of the Site Inspection Report)



ORIGINAL  
(led)

EPA		POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT PART 7 - OWNER INFORMATION		I. IDENTIFICATION	
				01 STATE	02 SITE NUMBER
				VA	278
II. CURRENT OWNER(S)			PARENT COMPANY (If applicable)		
01 NAME	02 D+B NUMBER	03 NAME	04 D+B NUMBER		
Paul Rhinehart		N/A			
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD #, etc.)	11 SIC CODE		
Mt. Falls	N/A				
05 CITY	06 STATE	07 ZIP CODE	12 CITY	13 STATE	14 ZIP CODE
Winchester	VA	22601			
01 NAME	02 D+B NUMBER	03 NAME	04 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD #, etc.)	11 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	12 CITY	13 STATE	14 ZIP CODE
01 NAME	02 D+B NUMBER	03 NAME	04 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD #, etc.)	11 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	12 CITY	13 STATE	14 ZIP CODE
01 NAME	02 D+B NUMBER	03 NAME	04 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD #, etc.)	11 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	12 CITY	13 STATE	14 ZIP CODE
III. PREVIOUS OWNER(S) (List most recent first)			IV. REALTY OWNER(S) (If applicable, list most recent first)		
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
unknown		unknown			
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
V. SOURCES OF INFORMATION (Cite specific references, e.g., 2000 Reg. permit analysis, reports)					
U.S. EPA files					



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
VA 278

II. CURRENT OPERATOR (Provide if different from owner)				OPERATOR'S PARENT COMPANY (if applicable)			
01 NAME N/A		02 D+B NUMBER		10 NAME N/A		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
06 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					
III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)				PREVIOUS OPERATORS' PARENT COMPANIES (if applicable)			
01 NAME N/A		02 D+B NUMBER		10 NAME N/A		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
06 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
06 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
06 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
06 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)							
N/A							

ORIGINAL  
(Red)

		<b>POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT</b>		<b>I. IDENTIFICATION</b>			
		<b>PART 5 - GENERATOR/TRANSPORTER INFORMATION</b>		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">01 STATE</td> <td style="width: 50%;">02 SITE NUMBER</td> </tr> <tr> <td>VA</td> <td>278</td> </tr> </table>		01 STATE	02 SITE NUMBER
01 STATE	02 SITE NUMBER						
VA	278						

<b>II. ON-SITE GENERATOR</b>					
01 NAME N/A		02 D+B NUMBER			
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE			
05 CITY	06 STATE	07 ZIP CODE			
<b>III. OFF-SITE GENERATOR(S)</b>					
01 NAME N/A		02 D+B NUMBER		01 NAME	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE
01 NAME		02 D+B NUMBER		01 NAME	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE
01 NAME		02 D+B NUMBER		01 NAME	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE
01 NAME		02 D+B NUMBER		01 NAME	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE
<b>IV. TRANSPORTER(S)</b>					
01 NAME N/A		02 D+B NUMBER		01 NAME	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE
01 NAME		02 D+B NUMBER		01 NAME	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE
<b>V. SOURCES OF INFORMATION</b> (See specific references, e.g., state Reg. sample analysis reports)					
N/A					



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
VA 278

II. PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ D. SPILLED MATERIAL REMOVED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ E. CONTAMINATED SOIL REMOVED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ F. WASTE REPACKAGED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☒ G. WASTE DISPOSED ELSEWHERE  
04 DESCRIPTION

02 DATE 11/83

03 AGENCY \_\_\_\_\_

Seeping from the fire (800,000 gallons) was pumped out of lagoons for use as a blending agent in heating fuels. Company unknown.

01 ☐ H. ON SITE BURIAL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ I. IN SITU CHEMICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ J. IN SITU BIOLOGICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ K. IN SITU PHYSICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ L. ENCAPSULATION  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ M. EMERGENCY WASTE TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ N. CUTOFF WALLS  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☒ O. EMERGENCY DIKING/SURFACE WATER DIVERSION  
04 DESCRIPTION

02 DATE 11/83

03 AGENCY EPA ERT

Three containment lagoons constructed to capture oily waste seeping into adjacent unnamed tributary to Hogue Creek.

01 ☐ P. CUTOFF TRENCHES/SUMP  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

01 ☐ Q. SUBSURFACE CUTOFF WALL  
04 DESCRIPTION


02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

N/A

AR100175

ORIGINAL  
(Red)

		<b>POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT PART 10 - PAST RESPONSE ACTIVITIES</b>		<b>I. IDENTIFICATION</b>	
				01 STATE	02 SITE NUMBER
				VA	278
<b>II. PAST RESPONSE ACTIVITIES (Continued)</b>					
01 <input type="checkbox"/> R. BARRIER WALLS CONSTRUCTED 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> S. CAPPING/COVERING 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> T. BULK TANKAGE REPAIRED 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> U. GROUT CURTAIN CONSTRUCTED 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> V. BOTTOM SEALED 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> W. GAS CONTROL 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> X. FIRE CONTROL 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> Y. LEACHATE TREATMENT 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> Z. AREA EVACUATED 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> 1. ACCESS TO SITE RESTRICTED 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> 2. POPULATION RELOCATED 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
01 <input type="checkbox"/> 3. OTHER REMEDIAL ACTIVITIES 04 DESCRIPTION		02 DATE _____	03 AGENCY _____		
N/A					
<b>III. SOURCES OF INFORMATION</b> (Cite specific references, e.g., state files, sample analysis reports)					
Telecon communication previously noted.					



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
VA	278

II. ENFORCEMENT INFORMATION

01 PART REGULATORY/ENFORCEMENT ACTION ☒ YES ☐ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

Circuit court closed the site in response to complaints from neighbors as of 10/7/83.

III. SOURCES OF INFORMATION (Cite specific references e.g. state files, surface analysis, reports)

Telecon communication previously noted.



POTENTIAL HAZARDOUS WASTE SITE  
IDENTIFICATION AND PRELIMINARY ASSESSMENT

TDD. No. F3-8403-07

REGION III SITE NUMBER (to be assigned by HQ)  
VA-278

NOTE: This form is completed for each potential hazardous waste site to help set priorities for site inspection. The information submitted on this form is based on available records and may be updated on subsequent forms as a result of additional inquiries and on-site inspections.

GENERAL INSTRUCTIONS: Complete Sections I and III through X as completely as possible before Section II (Preliminary Assessment). File this form in the Regional Hazardous Waste Log File and submit a copy to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION

A. SITE NAME Rhinehart Tire Dump		B. STREET (or other identifier) Mt. Falls	
C. CITY Winchester	D. STATE VA	E. ZIP CODE 22601	F. COUNTY NAME Frederick
G. OWNER/OPERATOR (if known) 1. NAME Mr. Paul Rhinehart		2. TELEPHONE NUMBER unknown	
H. TYPE OF OWNERSHIP <input type="checkbox"/> 1. FEDERAL <input type="checkbox"/> 2. STATE <input type="checkbox"/> 3. COUNTY <input type="checkbox"/> 4. MUNICIPAL <input checked="" type="checkbox"/> 5. PRIVATE <input type="checkbox"/> 6. UNKNOWN			

I. SITE DESCRIPTION

Approximately 5 acre site in a ravine which is used for storage of discarded tires. The site is adjacent to an unnamed tributary of Hogue Creek.

J. HOW IDENTIFIED (i.e., citizen's complaints, OSHA citations, etc.) Ms. Eve Thorsen - Virginia Emergency Services	K. DATE IDENTIFIED (mo., day, & yr.) 10/31/83	
L. PRINCIPAL STATE CONTACT 1. NAME Mr. Ray Tesh - Virginia State Water Control Board - Director - Division of Surveillance and Field Studies		2. TELEPHONE NUMBER (703) 828-2595

II. PRELIMINARY ASSESSMENT (complete this section last)

A. APPARENT SERIOUSNESS OF PROBLEM <input checked="" type="checkbox"/> 1. HIGH <input type="checkbox"/> 2. MEDIUM <input type="checkbox"/> 3. LOW <input type="checkbox"/> 4. NONE <input type="checkbox"/> 5. UNKNOWN	
B. RECOMMENDATION <input type="checkbox"/> 1. NO ACTION NEEDED (no hazard) <input type="checkbox"/> 2. IMMEDIATE SITE INSPECTION NEEDED a. TENTATIVELY SCHEDULED FOR: b. WILL BE PERFORMED BY: <input type="checkbox"/> 3. SITE INSPECTION NEEDED a. TENTATIVELY SCHEDULED FOR: b. WILL BE PERFORMED BY: <input checked="" type="checkbox"/> 4. SITE INSPECTION NEEDED (low priority) Groundwater and surface water is and should be monitored periodically.	

C. PREPARER INFORMATION 1. NAME David R. Kindig, NUS FIT III	2. TELEPHONE NUMBER (215) 687-9510	3. DATE (mo., day, & yr.) 3/26/84
--	---------------------------------------	--------------------------------------

III. SITE INFORMATION

A. SITE STATUS <input type="checkbox"/> 1. ACTIVE (Those industrial or municipal sites which are being used for waste treatment, storage, or disposal on a continuing basis, even if infrequently.) <input checked="" type="checkbox"/> 2. INACTIVE (Those sites which no longer receive wastes.) <input type="checkbox"/> 3. OTHER (specify):	
B. IS GENERATOR ON SITE? <input checked="" type="checkbox"/> 1. NO <input type="checkbox"/> 2. YES (specify generator's four-digit SIC Code):	
C. AREA OF SITE (in acres) approximately 5	D. IF APPARENT SERIOUSNESS OF SITE IS HIGH, SPECIFY COORDINATES 1. LATITUDE (deg.-min.-sec.) 39° 10' 50" 2. LONGITUDE (deg.-min.-sec.) 78° 18' 10"
E. ARE THERE BUILDINGS ON THE SITE? <input type="checkbox"/> 1. NO <input checked="" type="checkbox"/> 2. YES (specify): a small shed is located adjacent to the site.	

## IV. CHARACTERIZATION OF SITE ACTIVITY

Indicate the major site activity(ies) and details relating to each activity by marking 'X' in the appropriate boxes.

<input checked="" type="checkbox"/> A. TRANSPORTER	<input checked="" type="checkbox"/> B. STORER	<input checked="" type="checkbox"/> C. TREATER	<input checked="" type="checkbox"/> D. DISPOSER
1. RAIL	<input checked="" type="checkbox"/> 1. PILE	1. FILTRATION	1. LANDFILL
2. SHIP	2. SURFACE IMPOUNDMENT	2. INCINERATION	2. LANDFARM
3. BARGE	3. DRUMS	3. VOLUME REDUCTION	3. OPEN DUMP
4. TRUCK	4. TANK, ABOVE GROUND	4. RECYCLING/RECOVERY	4. SURFACE IMPOUNDMENT
5. PIPELINE	5. TANK, BELOW GROUND	5. CHEM./PHYS. TREATMENT	5. MIGNIGHT DUMPING
6. OTHER (specify):	6. OTHER (specify):	6. BIOLOGICAL TREATMENT	6. INCINERATION
		7. WASTE OIL REPROCESSING	7. UNDERGROUND INJECTION
		8. SOLVENT RECOVERY	8. OTHER (specify):
		9. OTHER (specify):	

## E. SPECIFY DETAILS OF SITE ACTIVITIES AS NEEDED

Site was used for storage of discarded tires. Stated purpose of the site was for eventual reclamation/recycling.

## V. WASTE RELATED INFORMATION

## A. WASTE TYPE

☐ 1. UNKNOWN ☐ 2. LIQUID ☐ 3. SOLID ☐ 4. SLUDGE

☒ 5. GAS \*Tire burned therefore releasing gas and liquid to the environments

## B. WASTE CHARACTERISTICS

☐ 1. UNKNOWN ☐ 2. CORROSIVE ☐ 3. IGNITABLE ☐ 4. RADIOACTIVE ☐ 5. HIGHLY VOLATILE  
☒ 6. TOXIC ☐ 7. REACTIVE ☐ 8. INERT ☒ 9. FLAMMABLE

☐ 10. OTHER (specify):

## C. WASTE CATEGORIES

1. Are records of wastes available? Specify items such as manifests, inventories, etc. below.

None known

2. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which wastes are present.

a. SLUDGE	b. OIL	c. SOLVENTS	d. CHEMICALS	e. SOLIDS	f. OTHER
AMOUNT	800,000	AMOUNT	AMOUNT	unknown	AMOUNT
UNIT OF MEASURE	gallon	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE
<input checked="" type="checkbox"/> (1) PAINT, PIGMENTS	<input checked="" type="checkbox"/> (1) OILY WASTES	<input checked="" type="checkbox"/> (1) HALOGENATED SOLVENTS	<input checked="" type="checkbox"/> (1) ACIDS	<input checked="" type="checkbox"/> (1) FLYASH	<input checked="" type="checkbox"/> (1) LABORATORY PHARMACEUT.
(2) METALS SLUDGES	<input checked="" type="checkbox"/> (2) OTHER (specify): byproduct oils from combustion	(2) NON-HALOGENATED SOLVENTS	(2) PICKLING LIQUORS	(2) ASBESTOS	(2) HOSPITAL
(3) POTW		(3) OTHER (specify):	(3) CAUSTICS	(3) MILLING/ MINE TAILINGS	(3) RADIOACTIVE
(4) ALUMINUM SLUDGE			(4) PESTICIDES	(4) FERROUS SMLTG. WASTES	(4) MUNICIPAL
(5) OTHER (specify):			(5) DYES/INKS	(5) NON-FERROUS SMLTG. WASTES	(5) OTHER (specify):
			(6) CYANIDE	<input checked="" type="checkbox"/> (6) OTHER (specify): solid remains of tires are on site	
			(7) PHENOLS		
			(8) HALOGENS		
			(9) PCB		
			(10) METALS		
			(11) OTHER (specify):		

BR100179



ORIGINAL  
(Red)

Continued From Page 2

V. WASTE RELATED INFORMATION (continued)

3. LIST SUBSTANCES OF GREATEST CONCERN WHICH MAY BE ON THE SITE (place in descending order of hazard).

Benzene	Methyl ethyl ketone	Acetone
Phenol	Ethylene dichloride	Xylenes
Chloroform	1,1,1-trichloroethane	Styrene
Methylene chloride		Toluene

4. ADDITIONAL COMMENTS OR NARRATIVE DESCRIPTION OF SITUATION KNOWN OR REPORTED TO EXIST AT THE SITE.

VI. HAZARD DESCRIPTION

A. TYPE OF HAZARD	B. POTENTIAL HAZARD (mark 'X')	C. ALLEGED INCIDENT (mark 'X')	D. DATE OF INCIDENT (mo., day, yr.)	E. REMARKS
1. NO HAZARD				
2. HUMAN HEALTH	X		10/31/83	Although discharges to surface waters have been contained, fire continues to emit combustion products to air. Continuation of problem also indicative of possible groundwater contamination.
3. NON-WORKER INJURY/EXPOSURE				
4. WORKER INJURY				
5. CONTAMINATION OF WATER SUPPLY				
6. CONTAMINATION OF FOOD CHAIN	X		10/31/83	
7. CONTAMINATION OF GROUND WATER		X	10/31/83	
8. CONTAMINATION OF SURFACE WATER		X	10/31/83	
9. DAMAGE TO FLORA/FAUNA	X		10/31/83	
10. FISH KILL	X		10/31/83	
11. CONTAMINATION OF AIR		X	10/31/83	
12. NOTICEABLE ODORS		X	10/31/83	
13. CONTAMINATION OF SOIL		X	10/31/83	
14. PROPERTY DAMAGE				
15. FIRE OR EXPLOSION		X	10/31/83	
16. SPILLS/LEAKING CONTAINERS/ RUNOFF/STANDING LIQUIDS				
17. SEWER, STORM DRAIN PROBLEMS				
18. EROSION PROBLEMS				
19. INADEQUATE SECURITY				
20. INCOMPATIBLE WASTES				
21. MIDNIGHT DUMPING				
22. OTHER (specify):				

## VII. PERMIT INFORMATION

## A. INDICATE ALL APPLICABLE PERMITS HELD BY THE SITE.

None known

- ☐ 1. NPDES PERMIT    ☐ 2. SPCC PLAN    ☐ 3. STATE PERMIT (specify): \_\_\_\_\_  
☐ 4. AIR PERMITS    ☐ 5. LOCAL PERMIT    ☐ 6. RCRA TRANSPORTER  
☐ 7. RCRA STORER    ☐ 8. RCRA TREATER    ☐ 9. RCRA DISPOSER  
☐ 10. OTHER (specify): \_\_\_\_\_

## B. IN COMPLIANCE?

- ☐ 1. YES    ☐ 2. NO    ☐ 3. UNKNOWN

N/A

4. WITH RESPECT TO (list regulation name &amp; number): \_\_\_\_\_

## VIII. PAST REGULATORY ACTIONS

- ☐ A. NONE    ☒ B. YES (summarize below)

Circuit court closed the facility on October 7, 1983, in response to complaints from neighbors.

## IX. INSPECTION ACTIVITY (past or on-going)

- ☐ A. NONE    ☒ B. YES (complete items 1, 2, 3, & 4 below)

1. TYPE OF ACTIVITY	2. DATE OF PAST ACTION (mo., day, & yr.)	3. PERFORMED BY: (EPA/State)	4. DESCRIPTION
Air	11/3/83	EPA	Continuous sampling & monitoring thru 11/30/83
Surface water & sediments	11/3/83	EPA/VA SWCB	Joint sampling and monitoring thru 11/30/83
Groundwater	1/3/84	VA SWCB IT Corp.	7 wells drilled to determine the extent of groundwater contamination and hydrogeologic conditions.

## X. REMEDIAL ACTIVITY (past or on-going)

- ☐ A. NONE    ☒ B. YES (complete items 1, 2, 3, & 4 below)

1. TYPE OF ACTIVITY	2. DATE OF PAST ACTION (mo., day, & yr.)	3. PERFORMED BY: (EPA/State)	4. DESCRIPTION
Runoff containment	11/3/83	EPA	450,000 gallon containment capacity via 3 containment ponds
Removal of byproduct oils	11/30/83	unknown	800,000 gallons were pumped from the ponds and removed from the site

NOTE: Based on the information in Sections III through X, fill out the Preliminary Assessment (Section II) information on the first page of this form.

AR100181

**APPENDIX A**

AR100182

**ORIGINAL**  
(Red)

1. COST CENTER:		<b>REM/FIT ZONE CONTRACT</b> <b>TECHNICAL DIRECTIVE DOCUMENT (TDD)</b>			2. NO.:	
ACCOUNT NO.:					F3-8403-07	
3. PRIORITY:	4. ESTIMATE OF TECHNICAL HOURS:	5. EPA SITE ID:	6. COMPLETION DATE:	7. REFERENCE INFO.:		
	<input checked="" type="checkbox"/> HIGH <input type="checkbox"/> MEDIUM <input type="checkbox"/> LOW	120				VA-278
	4A. ESTIMATE OF SUBCONTRACT COST:	5A. EPA SITE NAME:				
		<u>Rhinehart Tire</u> <u>Dump</u> <u>Winchester, VA</u>	4/23/84	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> ATTACHED <input checked="" type="checkbox"/> PICK UP		
8. GENERAL TASK DESCRIPTION: <u>Conduct a Desktop PA/SI/HRS of subject site.</u>						
9. SPECIFIC ELEMENTS:				10. INTERIM DEADLINES:		
1.) <u>Review background information.</u>						
2.) <u>Contact state or local authorities, if needed.</u>						
3.) <u>Submission of report.</u>						
11. DESIRED REPORT FORM:      FORMAL REPORT <input checked="" type="checkbox"/> LETTER REPORT <input type="checkbox"/> FORMAL BRIEFING <input type="checkbox"/>						
OTHER (SPECIFY): <u>Contact Darius Ostrauskas for additional information.</u>						
12. COMMENTS: <u>Potential NPL Site.</u>						
13. AUTHORIZING RPO:				14. DATE:		
<u>Harold G. Byer</u> (SIGNATURE)				<u>3/23/84</u>		
15. RECEIVED BY:				16. DATE:		
<input type="checkbox"/> ACCEPTED <input type="checkbox"/> ACCEPTED WITH EXCEPTIONS <input type="checkbox"/> REJECTED <u>[Signature]</u> (CONTRACTOR RPM SIGNATURE)				<u>3/26/84</u>		

Sheet 1  
Sheet 2

White - FITL Copy  
Canary - DPO Copy

Sheet 3  
Sheet 4


Pink - Contracting Officer's Copy (Washington, D. C.)  
Goldenrod - Project Officer's Copy (Washington, D. C.)

AR100183

APPENDIX B

AR100184

ORIGINAL  
(Red)



FROM 7.5 MINUTE U.S.G.S. HAYFIELD, VA. QUAD.

FIGURE 1


SITE LOCATION MAP  
RHINEHART TIRE DUMP, WINCHESTER, VA.  
( NO SCALE )

 **NUS**  
CORPORATION

 A Halliburton Company

AR100185

Scale  $\approx 1000'$   
ORIGINAL (Red)



AR100186

**APPENDIX C**

AR100187





ORIGINAL  
(Red)

# COMMONWEALTH of VIRGINIA

## STATE WATER CONTROL BOARD

Valley Regional Office

116 North Main Street

P.O. Box 268

Bridgewater, Virginia 22812

(703) 828-2595

17 January 1984

Richard N. Burton  
Executive Director

Post Office Box 11143  
Richmond, Virginia 23230  
(804) 257-0056

BOARD MEMBER:  
John H. Ariail, Jr.  
Chairman  
Patrick L. Standing  
Vice Chairman

Watkins M. Abbitt, J  
Joseph S. Cragwall, J  
David H. Miller  
Millard B. Rice, Jr.  
Robert C. Wininger

Mr. Darius C. Ostrauskos  
Environmental Scientist -  
Super Fund Branch  
U.S. Environmental Protection Agency  
Region III  
6th and Walnut Streets  
Philadelphia, Pennsylvania 19106

Dear Mr. Ostrauskos:

Attached are copies of lab data on water samples taken at the Tire Fire site in Frederick County. The data was performed by the State Lab. Please note that the date which the lab received the samples is the next day following the sampling.

These are all of the data which I have. As more is received, a copy will be forwarded.

Very truly yours,

R. F. Tesh, Director  
Division of Surveillance  
and Field Studies

Ref: 3AW22.

jes

Attachment

cc: VRO File  
Harry Allen  
EPA-ERT  
Raritan Depot, Bldg. 10, Woodbridge Ave.  
Edison, NJ 08837  
An Affirmative Action/Equal Opportunity Employer

AR100T88

ORIGINAL  
(Red)

## CERTIFICATE OF ANALYSIS

November 28, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 22312

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-04-83

Identification No.:

Lab #: 10583-10587

Submitted By: Dave Chance

Analyst: James C. Peterson, Ph.D.

## Description:

10583--Unnamed tributary to Hogue Creek

Upper portion unnamed tributary--pool of collected product

10584--Unnamed tributary to Hogue Creek

Free flowing stream upper portion, just above big pool of product

10585--X-tributary Hogue Creek

Lower portion unnamed tributary from fire site

10586--Hogue Creek Control

Hogue Creek just above confluence with unnamed tributary from fire site

10587--Hogue Creek

Hogue Creek downstream from confluence with unnamed tributary from fire site

## Results:

Priority Pollutants	10584	10585	10586	10587
Benzene	0.9ug/L	1.3ug/L	0.3ug/L	0.5ug/L
Toluene	1.7ug/L	2.3ug/L	<0.2ug/L	<0.2ug/L
Ethylbenzene	4.6ug/L	1.2ug/L	0.8ug/L	<0.2ug/L
Xylenes	2.4ug/L	0.6ug/L	<0.2ug/L	<0.2ug/L
Naphthalene	30 ug/L	10 ug/L	<1 ug/L	<1 ug/L
Fluorene	13 ug/L	4.6ug/L	<1 ug/L	<1 ug/L
Phenanthrene	4.1ug/L	2.0ug/L	<1 ug/L	<1 ug/L
Caprolactam	13 mg/L	4.8mg/L	140 ug/L	210 ug/L

## Other Components Identified in 10584, 10585, 10586, 10587:

Benzonitrile, Acetophenone, Tolunitrile, Phthalonitrile, Benzothiazole,  
Methyl benzothiazole, 1-methyl naphthalene, C<sub>3</sub> benzenes, C<sub>4</sub> benzenes

Sample 10583 was redundant with 10584 and was not analyzed.

STATE OF VIRGINIA  
CITY/COUNTY OF \_\_\_\_\_ to-wit:

THIS day personally appeared before me \_\_\_\_\_ a notary public, in and for said city/county in the Commonwealth of Virginia, \_\_\_\_\_ who signed the foregoing Certificate of Analysis, before me, and after being duly sworn, made oath (1) that he performed the analysis and/or examination the results of which are herein contained, (2) that said analysis and/or examination was performed in a laboratory operated by the Division of Consolidated Laboratory Services of the Commonwealth or authorized by such Division to conduct such analysis and/or examination and (3) that this Certificate of Analysis is true and correct.

Given under my hand this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_

Notary Public

My commission expires \_\_\_\_\_, 19\_\_\_\_

Page 1 of 1

CERTIFICATE OF ANALYSIS

November 28, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 22312

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-14-83

Identification No.:

Lab #: S83-695 through S83-700

Submitted By: Ray Miller

Analyst: James C. Peterson, Ph.D.

Description:

S83-695 -- Site 01, tributary  
S83-696 -- Site 02, downstream  
S83-697 -- Site 03, upstream  
S83-698 -- Site 03a, upstream  
S83-699 -- Site 04, confluence  
S83-700 -- VOA blank

Results:

Priority Pollutants	695	696	697	698	699	700
Benzene	1.5ug/L	0.3ug/L	no volatile sample	<0.2ug/L	no volatile sample	<0.2ug/L
Toluene	3.3ug/L	0.3ug/L		<0.2ug/L		<0.2ug/L
Ethylbenzene	9.1ug/L	0.2ug/L		<0.2ug/L		<0.2ug/L
Xylenes	7.6ug/L	0.3ug/L		<0.2ug/L		<0.2ug/L
Naphthalene	56 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	<1 ug/L	<1 ug/L
Acenaphthalene	22 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	1.0ug/L	<1 ug/L
Acenaphthene	26 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	1.6ug/L	<1 ug/L
Fluorene	13 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	<1 ug/L	<1 ug/L
Phenanthrene	6 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	<1 ug/L	<1 ug/L
Caprolactam	8.5mg/L	1.6mg/L	140ug/L	<1 ug/L	9.0mg/L	<1 ug/L

Other Components Identified in 695, 696, 699:

Benzonitrile, Acetophenone, Tolunitrile, Benzothiazole, Methylbenzothiazole,  
1-methyl naphthalene, C<sub>3</sub> benzenes, C<sub>4</sub> benzenes

STATE OF VIRGINIA  
CITY/COUNTY OF \_\_\_\_\_ 10-wit

THIS day personally appeared before me \_\_\_\_\_

\_\_\_\_\_ a notary public, in and for said city/county in &

Commonwealth of Virginia, \_\_\_\_\_ who signed the foregoing Certificate of Analysis, before me, and after being duly sworn, made oath (that he performed the analysis and/or examination the results of which are herein contained, (2) that said analysis and/or examination was performed in a laboratory operated by the Division of Consolidated Laboratory Services of the Commonwealth or authorized by such Division to conduct such analysis and/or examination and (3) that the Certificate of Analysis is true and correct

Given under my hand this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_

Notary Public

My commission expires \_\_\_\_\_, 19\_\_\_\_

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

November 28, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 22312

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-17-83

Identification No.:

Lab #: S83-722-724

Submitted By: Ray Miller

Analyst: James C. Peterson, Ph.D.

Description: unnamed trib  
S83-722--Site 01, Masey Run  
S83-723--Site 02, Hogue Creek  
S83-724--Site 02a, Rt. 614 bridge

Results:  
Priority Pollutants (Volatiles Only)

	<u>722</u>	<u>723</u>	<u>724</u>
Benzene	1.1ug/L	<0.2ug/L	<0.2ug/L
Toluene	7.2ug/L	0.2ug/L	<0.2ug/L
Ethylbenzene	13.4ug/L	0.2ug/L	<0.2ug/L
Xylenes	26.9ug/L	0.5ug/L	<0.2ug/L

STATE OF VIRGINIA  
CITY/COUNTY OF \_\_\_\_\_, to-wit:

THIS day personally appeared before me \_\_\_\_\_, a notary public, in and for said city/county in the Commonwealth of Virginia, \_\_\_\_\_, who signed the foregoing Certificate of Analysis, before me, and after being duly sworn, made oath (1) that he performed the analysis and/or examination the results of which are herein contained, (2) that said analysis and/or examination was performed in a laboratory operated by the Division of Consolidated Laboratory Services of the Commonwealth or authorized by such Division to conduct such analysis and/or examination and (3) that this Certificate of Analysis is true and correct.

Given under my hand this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_

My commission expires \_\_\_\_\_, 19\_\_\_\_

Notary Public

Page 1 Of 1



Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(3d)

CERTIFICATE OF ANALYSIS

December 5, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 23212

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-18-83

Identification No.:

RECEIVED

DEC 6 1983

Lab #: S83-770-772

Submitted By:

Ray Miller, SWCS

BY

NORTHERN REGIONAL  
OFFICE

Analyst:

Mike Martin

Description:

S83-770: Site 01, water from pool on *unnamed trib* ~~Massey Run~~  
S83-771: Site 02, water, 100 yards downstream of confluence of *unnamed trib* ~~Massey Run~~  
and Hogue Creek  
S83-772: Site 02A, water at Rt. 614 bridge, Hogue Creek

Request: Volatile priority pollutants

Results:

Priority Pollutants	770	771	772
Benzene	2.0ug/L	<0.2	<0.2
Toluene	5.1	<0.2	<0.2
Ethyl benzene	6.0	0.8	<0.2
Xylenes	18.1	<0.2	<0.2

RECEIVED  
DEC 14 1983

VALLEY REGIONAL  
OFFICE



Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

December 5, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 23212

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-21-83

RECEIVED

DEC 5 1983

Lab #: S83-767-769

Identification No.:

Submitted By: Ray Miller, SWCB

BY  
NORTHERN REGIONAL  
OFFICE

Analyst:

M. E. Martin  
Mike Martin

Description:

S83-767: Site 01, water from pool on ~~Massey Run~~ *unnamed trib*  
S83-768: Site 02, water, 100 yards downstream of confluence with ~~Massey Run~~ *unnamed trib*  
on Hogue Creek  
S83-769: Site 02A, water at Rt. 614 brodge, Hogue Creek

Request: Volatile priority pollutants

Results:

Priority Pollutants	767	768	769
Benzene	0.5ug/L	0.2	<0.2
Toluene	1.1	<0.2	<0.2
Ethyl benzene	3.5	<0.2	<0.2
Xylenes	3.3	<0.2	<0.2

RECEIVED

DEC 14 1983

NORTHERN REGIONAL  
OFFICE

Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

December 22, 1983

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-30-83

Identification No.:

Lab #:

Submitted By: REM

Analyst: J. C. Peterson, Ph.D.

Description:

11178, 11187: Station 01, approximately 1500 ft. upstream of confluence with Hogue Cree  
11179, 11188: Station 02, 100 yds. downstream of confluence with Massy Run  
11180, 11192: Station 02A, at Rt. 614 bridge (gauging station) UN-NAMED trib.

Results:

Priority Pollutants	01	02	02A
Benzene	5.1 ug/L	<0.2ug/L	0.2 ug/L
Toluene	10.9	0.3	<0.2
Ethyl benzene	1.9	1.0	1.7
Xylenes	5.9	<0.2	<0.2
Naphthalene	20.	<1.	<1.
Phenol	460.	6.8	1.0

No other priority pollutants were detected (Limit of Detection = 0.2 to 5ug/L)

Other Contaminants\*

2(2-n-butoxyethoxy)ethanol	9.7 mg/L	110. ug/L	23. ug/L
benzothiazole	380. ug/L	2.7ug/L	3.7 ug/L
caprolactam	12.9 mg/L	110. ug/L	84. ug/L
2-methylbenzothiazole	180. ug/L	1.2ug/L	2.3 ug/L
Benzoic Acid	10. mg/L	16.6ug/L	1.5 ug/L

\*Confirmed by GC/MS with authentic standards.

Other major contaminants identified by GC/MS, not yet confirmed with authentic standards: phenylisocyanate, hexanedinitrile, N,N dimethylbenzamide, 3-methylbenzoic acid, cyanobenzoic acid.

RECEIVED  
JAN 3 1984

VALLEY REGIONAL  
OFFICE

Page 1 of 1

AR100194



Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

December 23, 1983

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 12-07-83

Identification No.:

Lab #:

Submitted By: REM, D. Wright

Analyst: J. C. Peterson, Ph.D.

Description:

11400, 11404, 11408: Station 01, approximately 1500 ft. upstream of confluence with Hogue Creek  
11401, 11405, 11409: Station 02, 100 yds. downstream of confluence with Massey Run  
11402, 11406, 11410: Station 02A, at Rt. 614 bridge (gauging station)  
11399, 11403, 11407: Rhinehart's Pond (R.P.)

Results:

Priority Pollutants	R.P.	01	02	02A
Benzene	141 ug/L	4.7 ug/L	0.5 ug/L	1.1 ug/L
Toluene	171	9.4	0.7	<0.2
Ethylbenzene	112	7.6	0.5	<0.2
Xylenes	88	7.1	0.4	<0.2
Naphthalene	100	14	2.0	1.1
Acenaphthylene	350 ppb	51	3.2	<2
Phenol	2.7 mg/L	260	5.1	<2

No other priority pollutants were detected (Limit of Detection: 0.2 to 5ug/L)

Other Contaminants\*

2(2-n-butoxyethoxy)ethanol	9.7 mg/L	1.6 mg/L	190 ug/L	100 ug/L
benzothiazole	2.2 mg/L	320 ug/L	49 ug/L	30 ug/L
caprolactam	66 mg/L	11 mg/L	340 ug/L	210 ug/L
2-methylbenzothiazole	560 mg/L	230 ug/L	16 ug/L	11 ug/L
benzoic acid	27 mg/L	8.8 mg/L	200 ug/L	<2 ug/L

\*confirmed by GC/MS with authentic standards

Other contaminants identified by GC/MS, not yet confirmed with authentic standards:  
phenylisocyanate hexanedinitrile, N,N dimethylbenzamide, 3-methylbenzoic acid,  
cyanobenzoic acid.

RECEIVED

Page 1 of 1





Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

December 22, 1983

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: December 13-14, 1983

Identification No.:

Lab #: 134-151, 152, 153, 148,  
150, 149

Submitted By:

Analyst: J. C. Peterson, Ph.D.

Description:

11704, 11708 Donald Swaner well 134-151  
11705, 11709 Robinson well 134-152  
11706, 11710 W. T. Rhinehart well 134-153  
11628, 11629 Rhinehart spring 134-148  
11631-11632 Palmer well 134-150  
11634-11635 Pigeon well 134-149 PC84-196

RECEIVED  
DEC 29 1983

VALLEY REGIONAL  
OFFICE

Results:

Priority Pollutants	134-151	152	153	148	150	149
Benzene	<0.2ug/L	<0.2	<0.2	<0.2	<0.2	<0.2
Toluene	0.8	0.3	<0.2	<0.2	<0.2	<0.2
Ethyl benzene	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
Xylenes	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
Naphthalene	<1	<1	<1	<1	<1	<1

No other priority pollutants were detected (Limit of Detection = 0.2 to 5ug/L)

No non-priority pollutant tire fire constituents normally found in Hogue Creek and Massey Run were detected in these well waters. (Limit of Detection = 1 to 10ug/L)

STATE OF VIRGINIA  
CITY/COUNTY OF Richmond to-wit:

THIS day personally appeared before me

J. C. Peterson a notary public, in and for said city/county in the

Commonwealth of Virginia, J. C. Peterson who signed the foregoing Certificate of Analysis, before me, and after being duly sworn, made oath (1) that he performed the analysis and/or examination the results of which are herein contained, (2) that said analysis and/or examination was performed in a laboratory operated by the Division of Consolidated Laboratory Services of the Commonwealth or authorized by such Division to conduct such analysis and/or examination and (3) that the Certificate of Analysis is true and correct.

Given under my hand this 22 day of Dec, 1983

My commission expires May 18, 1987

William Shene Notary Public

AR100196

ORIGINAL  
(Red)



# COMMONWEALTH of VIRGINIA

## STATE WATER CONTROL BOARD

Richard N. Burton  
Executive Director

Post Office Box 11143  
Richmond, Virginia 23230  
(804) 257-0056

Valley Regional Office  
116 North Main Street  
P.O. Box 268  
Bridgewater, Virginia 22812  
(703) 828-2595

BOARD MEMBER  
John H. Ariail, Jr.  
Chairman  
Patrick L. Standing  
Vice Chairman

Watkins M. Abbitt,  
Joseph S. Cragwall,  
David H. Miller  
Millard B. Rice, Jr.  
Robert C. Wininger

13 February 1984

Mr. Darius C. Ostrauskos  
Environmental Scientist -  
Super Fund Branch  
U. S. Environmental Protection Agency  
Region III  
6th and Walnut Streets  
Philadelphia, Pennsylvania 19106

Dear Mr. Ostrauskos:

Attached are copies of lab data on water samples taken at the Tire Fire site in Frederick County. The data was performed by the State Lab. Please note that the date which the lab received the samples is the next day following the sampling.

These are all of the data which I have received since I last corresponded on 17 January 1984. As more is received, a copy will be forwarded to update your file.

Very truly yours,

R. F. Tesh, Director  
Division of Surveillance  
and Field Studies

jes

Attachment

cc: VRO File



CERTIFICATE OF ANALYSIS

February 2, 1984

TO: Ray Tesh  
Valley Regional Office  
116 N. Main Street  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 01-05-84

Identification No.: 134-156, 134-157

Lab #: 14, 15, 16, 17, 18, 19

Submitted By: RWB

Analyst:

*James C. Peterson*  
James C. Peterson, Ph.  
Michael F. Martin  
*Michael F. Martin*

Description:

14, 17: Hogue Creek station (02A)  
15, 18: Leonard Hartman well (C&H Market) (134-156)  
16, 19: Emmert Boyce well (E&M process) (134-157)

Results:

Priority Pollutants	02A	134-156	134-157
Benzene	<0.2ug/L	<0.2ug/L	<0.2ug/L
Toluene	<0.2	<0.2	<0.2
Ethylbenzene	<0.2	<0.2	<0.2
Xylenes	<0.2	<0.2	<0.2
Naphthalene	0.2	<1	<1
Acenaphthylene	<1	<1	<1
Phenol	<1	<1	<1

No other priority pollutants were detected (limit of detection - 0.2 to 5ug/L)

Other Contaminants*	02A	134-156	134-157
Cyanobenzene	3.4ug/L	<0.2ug/L	<0.2ug/L
2(2-n-butoxyethoxy)ethanol	4.2	<1	<1
Benzothiazole	3.6	<0.2	<0.2
Caprolactam	53	<5	<5
2-methylbenzothiazole	2.3	<0.2	<0.2
Benzoic Acid	6.4	<1	<1
N,N dimethylbenzamide	1.0	<0.2	<0.2

\*confirmed by GC/MS with authentic standards

Significant contaminants identified by GC/MS in sample 02A, not yet confirmed with authentic standards: hexanedinitrile, 3-methylbenzoic acid (3-toluic acid) cyanobenzoic acid.



Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

February 1, 1984

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 01-06-84

Identification No.: 134-158, 134-159,  
134-160, 134-161

Lab #: 70, 71, 72, 73, 74, 75, 76

Submitted By:

Analyst: *James C. Peterson*  
James C. Peterson, Ph.D.  
Michael F. Martin  
*Michael F. Martin*

Description:

70, 74: G. Whitacre, Box 208 Mt. Falls, Winchester, VA (134-160)  
71, 75: Gerald Phelps, Box 198 Mt. Falls, Winchester, VA (134-161)  
72, 76: Vivian Rosenberger well, Box 180 Mt. Falls, Winchester, VA (134-158)  
73: Pete Kerns well (Pete's Auto) (134-159)  
(no extractable sample received)

Results:

Priority Pollutants	160	161	158	159
Benzene	<0.2ug/L	<0.2ug/L	<0.2ug/L	<0.2ug/L
Toluene	<0.2	<0.2	<0.2	<0.2
Ethylbenzene	<0.2	<0.2	<0.2	<0.2
Xylenes	<0.2	<0.2	<0.2	<0.2
Naphthalene	<1	<1	<1	<1
Acenaphthylene	<1	<1	<1	<1
Phenol	<1	<1	<1	<1

No other priority pollutants were detected (limit of detection - 0.2 to 5ug/L)

No non-priority pollutant tire fire constituents normally found in Hogue Creek and Massey Run were detected in these well waters (limit of detection - 0.2 to 10ug/L)

FEB 6 1984

VALLEY REGIONAL  
OFFICE

AR100199



Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

February 3, 1984

TO: State Water Control Board  
Valley Regional Office  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-5736

Date Received: 11-14-83

Identification No.: 01--tributary  
02--downstream  
03--upstream  
3A--upstream  
04--confluence  
Submitted By: YOA--blank

Lab #: S83-695 through S83-700

Analyst: Jim Anderson

Description:

Item 3: plastic bottles identified as 01, 02, 03, 3A, 04 and YOA Blank of liquid

Results:

Cadmium on samples (01, 02, 03, 3A, 04 and YOA) was found at a level of less than 10ug/L.

RECEIVED  
FEB 7 1984

VALLEY REGIONAL  
OFFICE

STATE OF VIRGINIA  
CITY/COUNTY OF

*R. Anderson*

to-wit:

*J. Anderson*

THIS day personally appeared before me

*W. F. Anderson*

a notary public, in and for said city/county in the

Commonwealth of Virginia, who signed the foregoing Certificate of Analysis, before me, and after being duly sworn, made oath (1) that he performed the analysis and/or examination the results of which are herein contained, (2) that said analysis and/or examination was performed in a laboratory operated by the Division of Consolidated Laboratory Services of the Commonwealth or authorized by such Division to conduct such analysis and/or examination and (3) that the Certificate of Analysis is true and correct.

Given under my hand this 6 day of Feb, 1984

*W. F. Anderson* Notary Public

My commission expires 1987

Page \_\_\_\_ Of \_\_\_\_



Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

January 9, 1984

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 12-20-83

Identification No.:

RECEIVED  
JAN 19 1984

Submitted By: REM

VALLEY REGIONAL  
OFFICE

Analyst:

James C. Peterson  
James C. Peterson, Ph.D.

Description:

11854, 11859: Hogue Creek, site 3A  
11855, 11860: Hogue Creek, site 02  
11856, 11861: X tributary, site 01  
11857, 11862: Hogue Creek, site 2A, gauge 1.11  
11858, 11863: Agnes Rosenberger (spring) Box 175, Mt. Falls Road, Winchester

Results:

Priority Pollutants	3A	02	01	02A	Spring
Benzene	<0.2	<0.2	0.6ug/L	<0.2	<0.2
Toluene	<0.2	<0.2	2.2	<0.2	<0.2
Ethylbenzene	<0.2	<0.2	0.8	<0.2	<0.2
Xylenes	<0.2	<0.2	1.0	<0.2	<0.2
Naphthalene	<1	<0.3	27 ug/L	<0.3	<1
Acenaphthylene	<1	<1	11 ug/L	<1	<1
Phenol	<1	2.6ug/L	130 ug/L	<1	<1

No other priority pollutants were detected (Limit of Detection = 0.2 to 5ug/l)

Other Contaminants*	03A	02	01	02A	Spring
2(2-n-butoxyethoxy)ethanol	<1ug/L	61ug/L	3.1mg/L	3.3ug/L	<1ug/L
benzothiazole	<0.2	12	720 ug/L	2.5ug/L	<0.2
caprolactam	<5	250	9.7mg/L	44 ug/L	<5
2-methylbenzothiazole	<0.2	5.2	300 ug/L	1.0ug/L	<0.2
benzoic acid	<1ug/L	260	5.6mg/L	27 ug/L	<1ug/L
cyanobenzene	<0.2	12	1.3mg/L	2.6ug/L	<0.2
N,N dimethylbenzamide	<0.2	2.2	100 ug/L	0.5ug/L	<0.2

\*confirmed by GC/MS with authentic standards

Significant contaminants identified by GC/MS in samples from sites 02, 01, 02A, not yet confirmed with authentic standards: hexanedinitrile, 3-methylbenzoic acid, cyanobenzoic acid.



ORIGINAL  
(Red)

# COMMONWEALTH of VIRGINIA

## STATE WATER CONTROL BOARD

Richard N. Burton  
Executive Director  
Post Office Box 11143  
Richmond, Virginia 23230  
(804) 257-0056

Valley Regional Office  
116 North Main Street  
P.O. Box 268  
Bridgewater, Virginia 22812  
(703) 828-2595

26 March 1984

BOARD MEMBERS  
John H. Ariail, Jr.  
Chairman  
Patrick L. Standing  
Vice Chairman

Watkins M. Abbitt, Jr.  
Joseph S. Cragwall, Jr.  
David H. Miller  
Millard B. Rice, Jr.  
Robert C. Wininger

Mr. Darius C. Ostrauskos  
Environmental Scientist -  
Super Fund Branch  
U. S. Environmental Protection Agency  
Region III  
6th and Walnut Streets  
Philadelphia, Pennsylvania 19106

Dear Mr. Ostrauskos:

Attached are copies of lab data on water samples taken at the Tire Fire site in Frederick County. The data was performed by the State Lab. Please note that the date which the lab received the samples is the next day following the sampling.

These are all of the data which I have received since I last corresponded on 13 February 1984. As more is received, a copy will be forwarded to update your file.

Very truly yours,

R. F. Tesh, Director  
Division of Surveillance  
and Field Studies

jes

Attachment

cc: VRO File

Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

March 16, 1984

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
116 N. Main Street  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: ~~02-13-84~~ Error  
2/14/84 & 2/16/84

Identification No.:

Lab #:

Submitted By:

Analyst: Paul W. Kohler  
Michael F. Martin

Description:

1054, 1060: Rhineharts Pond  
1055, 1061: Rhineharts Spring  
1056, 1062: Station 03A, upstream of confluence  
1057, 1063: Station 02, downstream of confluence  
1058, 1064: Station 01  
1059, 1065: Station 02A, Rt. 614, bridge  
1231, 1230: Dutchman's pumpage

Sampling Date

2/13/84

"

"

"

"

"

2/15/84

Flow estimated at 300 cfs

Results: (in ug/l)

Priority Pollutants	Pond	Spring	03A	02	01	02A	Pumpage
Benzene	34	<0.2	<0.2	<0.2	0.2	<0.2	112
Toluene	82	<0.2	<0.2	<0.2	0.7	<0.2	204
Ethylbenzene	27	<0.2	<0.2	<0.2	0.7	<0.2	96
Xylenes	69	<0.2	<0.2	<0.2	1.3	<0.2	115
Naphthalene	870	<0.5	<0.5	<0.5	8.3	<0.5	900
Acenaphthalene	970	<.5	<.5	<.5	6.6	<.1	230
Phenol	84	<1	<1	<1	40	<1	120

No other priority pollutants were detected (Limit of Detection = 0.2 to 5ug/l)

Other Contaminants\*

Benzonitrile (Cyanobenzene)	7400	<0.5	<0.5	6.6	90	0.73	9400
2(2-n-butoxyethoxy) ethanol	2100	<1	<1	1.3	287	<1	116,000
Benzothiazole	5500	<0.5	<0.5	7.9	83	2.1	8700
Caprolactam	11,900	<1	<1	57	710	17.5	118,000
2-Methylbenzo- thiazole	290	<0.5	<0.5	3.9	48	1.6	3300
N,N-dimethyl- benzamide	130	<0.5	<0.5	2.5	18	0.56	990
Benzoic Acid	11,700	<1	<1	13	410	<1	143,000
p-toluic Acid	1,700	<1	<1	13	210	1.9	15,000
3-Cyanobenzoic Acid	910	<1	<1	3.2	38	<1	560

\*Confirmed by GC/MS with authentic standards 101-1-01-1

AR100203





Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

March 5, 1984

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
116 N. Main Street  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 01-27-84

Identification No.:

Lab #:

Submitted By:

Analyst: Paul W. Kohler  
Michael F. Martin

*P. W. Kohler*  
*Michael F. Martin*

Description:

558, 561: well #134-111, Holme Smoke  
559, 562: well #134-162, Ola M. Racey  
560, 563: well #134-170, Gilbert Puffenberger  
564: well #134-152, Alfred Robinson

Results:

Priority Pollutants	134-111	134-162	134-170	134-152
Benzene	<0.2	<0.2	<0.2	<0.2
Toluene	<0.2	<0.2	<0.2	<0.2
Ethylbenzene	<0.2	<0.2	<0.2	<0.2
Xylenes	<0.2	<0.2	<0.2	<0.2
Naphthalene	<0.2	<0.2	<0.2	*NR
Phenol	<1	<1	<1	NR

\*Not requested

No other priority pollutants were detected (Limit of Detection = 0.2 to 5ug/l).

No other contaminants normally associated with Hogue Creek were detected  
(Limit of Detection = 1 to 5ug/l).

RECEIVED  
MAR 12 1984

VALLEY REGIONAL  
OFFICE

Commonwealth of Virginia  
Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

February 27, 1984

TO: Ray Tesh  
State Water Control Board  
Valley Regional Office  
116 N. Main Street  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

RECEIVED  
MAR 2 1984

Date Received: 02-01-84

Identification No.:

Lab #:

VALLEY REGIONAL  
OFFICE

Submitted By: RWB Sampled 1-31-84

Analyst: Michael E. Martin  
Michael F. Martin  
Paul W. Kohler

Description:

699, 706: Station 02A Route 614 bridge flow 17.3 cfs  
700, 707: Station 03A Upstream of confluence  
701, 708: Station 02 Downstream of confluence  
702, 709: Station 01 Downstream of confluence  
703, 710: TF-2S Test well  
704, 711: TF-2D Test well  
705, 712: TF-1 Test well

Results:

Priority Pollutants	02A	03A	02	01	TF-2S	TF-2D	TF-1
Benzene	<0.2ug/l	<0.2ug/l	<0.2ug/l	0.31ug/l	3.3ug/l	<0.2ug/l	0.21ug/l
Toluene	<0.2	<0.2	<0.2	1.2	6.8	<0.2	<0.2
Ethylbenzene	<0.2	<0.2	<0.2	2.7	10	<0.2	<0.2
Xylenes	<0.2	<0.2	<0.2	1.5	16	<0.2	0.43
Naphthalene	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
Phenol	<1.0	<1.1	<1.2	9.7	<0.2	<0.2	0.2

No other priority pollutants were detected (Limit of Detection = 0.2 to 5ug/l)

Other Contaminants\*

Cyanobenzene	<0.5ug/l	<0.5ug/l	1.2ug/l	52 ug/l	<0.5ug/l	<0.5ug/l	<0.5 ug/l
2(2-n-butoxyethoxy) ethanol	<1	1.5	6.9	.11mg/l	0.2 mg/l	<1	<1
Benzothiazole	1.6	<0.5	6.07	56ug/l	<.5ug/l	<0.5	<.5
Caprolactam	13.	1.9	32.	1.1mg/l	4.1mg/l	2.7	<1
2-methylbenzothiazole	0.82	<0.5	2.7	25ug/l	<0.5ug/l	<0.5	<0.5
Benzoic Acid	<1	<1	<1	1.8mg/l	<1	<1	<1
N,N-dimethylbenzamide	<0.5	<0.5	0.6	4.3ug/l	<0.5	<0.5	<0.5
m-toluic acid	<1	<1	<1	5.8	<1	<1	<1
p-toluic acid	1.3	<1	<1	7.1	<1	1.0	<1
3-cyanobenzoic acid	3.7	<1	<1	2.2	3.04	<1	<1
4-cyanobenzoic acid	<1	<1	<1	6.9	2.21	<1	<1
2(2-n-butoxyethoxy) ethanoic acid	<1	<1	<1	<1	**0.6mg/l	<1	<1
p-tolunitrile	<0.5	<0.5	0.8	17.4	<0.5ug/l	<0.5	<0.

AR100205

ORIGINAL  
(Red)

\*Confirmed by GC/MS with authentic standards

\*\*Contaminant identified by GC/MS but not yet confirmed with authentic standards:  
phthalonitrile, ethylbenzothiazole, dimethylquinoline, benzamide

AR100206

CERTIFICATE OF ANALYSIS

February 16, 1984

VALLEY REGIONAL  
OFFICE

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 01-18-84

Identification No.:

Lab #: 304-311

Submitted By: REM *sampled 1-17-84*

Analyst:

*James C. Peterson*

James C. Peterson  
Michael F. Martin

*Michael F. Martin*

Description:

309, 305: Station 03A, upstream of confluence  
308, 304: Station 02A, Rt. 614 bridge *flow 8.06 cfs*  
310, 306: Station 01  
311, 307: Station 02, downstream of confluence

Results:

Priority Pollutants	03A	02A	01*	02
Benzene	<0.2	<0.2	1.0	<0.2
Toluene	<0.2	<0.2	2.6	0.3
Ethylbenzene	<0.2	<0.2	2.5	<0.2
Xylenes	<0.2	<0.2	2.5	0.3
Naphthalene	<0.2	<0.2	----	<0.2
Phenol	<1	<1	----	<1

No other priority pollutants were detected (Limit of Detection - 0.2 to 5ug/L)

Other Contaminants*	03A	02A	01**	02
Cyanobenzene	<0.5	2.4	----	9.4
2(2-n-butoxyethoxy)ethanol	<2	0.7	----	22
Benzothiazole	<0.5	4.9	----	16
Caprolactam	<5	53	----	220
2-methylbenzothiazole	<0.5	1.6	----	6.0
Benzoic Acid	<1	<1	----	150
N,N dimethylbenzamide	<0.5	1.0	----	3.2
p-tolunitrile	<0.5	0.6	----	2.9

\*Confirmed by GC/MS with authentic standards. Significant contaminants identified by GC/MS in samples from 02A and 02 not yet confirmed with authentic standards: hexanedinitrile, 3-methylbenzoic acid, cyanobenzoic acid.

\*\*The 01 extractables bottle was broken prior to receipt at the Trace Organic Section.

AR100207

ORIGINAL  
(Red)

RECEIVED

FEB 28 1984

CERTIFICATE OF ANALYSIS

February 2, 1984

VALLEY REGIONAL  
OFFICE

TO: Ray Tesh  
Valley Regional Office  
116 N. Main Street  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4808

ORIGINAL

Date Received: 01-05-84

Identification No.: 134-156, 134-157

Lab #: 14, 15, 16, 17, 18, 19

Submitted By: RWB *sampled 1-4-84*

Analyst: James C. Peterson, Ph.  
Michael F. Martin

Description:

14, 17: Hogue Creek station (02A) *Flow: 9.29 cfs*  
15, 18: Leonard Hartman well (C&H Market) (134-155)  
16, 19: Emert Soyce well (E&M process) (134-157)

Results:

Priority Pollutants	02A	134-156	134-157
Benzene	<0.2ug/L	<0.2ug/L	<0.2ug/L
Toluene	<0.2	<0.2	<0.2
Ethylbenzene	<0.2	<0.2	<0.2
Xylenes	<0.2	<0.2	<0.2
Naphthalene	0.2	<1	<1
Acenaphthylene	<1	<1	<1
Phenol	<1	<1	<1

No other priority pollutants were detected (limit of detection - 0.2 to 5ug/L)

Other Contaminants*	02A	134-156	134-157
Cyanobenzene	3.4ug/L	<0.2ug/L	<0.2ug/L
2(2-n-butoxyethoxy)ethanol	4.2	<1	<1
Benzothiazole	3.6	<0.2	<0.2
Caprolactam	53	<5	<5
2-methylbenzothiazole	2.3	<0.2	<0.2
Benzoic Acid	6.4	<1	<1
N,N dimethylbenzamide	1.0	<0.2	<0.2

\*confirmed by GC/MS with authentic standards

Significant contaminants identified by GC/MS in sample 02A, not yet confirmed with authentic standards: hexanedinitrile, 3-methylbenzoic acid (3-toluic acid) cyanobenzoic acid.

APPENDIX D

AR100209

AGENDA

- I. INTRODUCTION - Bruce Smith
- II. Technical Considerations & Approach Regarding the Fire - Bruce Smith
- III. Environmental Concerns - Dr. Harry Allen
- IV. Current Status of Operations - Thomas Massey
- V. Enforcement Considerations - Heather Gray

FREDERICK COUNTY, VIRGINIA TIRE FIRETechnological Considerations and Approach Regarding the FireBackground

In November, 1983 ERT developed a report entitled "Determination of Long Term Superfund Immediate Removal approaches for Frederick County Tire Fire". This report identified several possible options for dealing with the fire under the following three major categories:

- I. Controlled Burning, Containment and Collection of Pyrolytic Tar (Status Quo)
- II. Accelerated Burning of the Pile
- III. Extinguish the Fire

On November 21, 1983, IT Envirosience was tasked to do a feasibility study ; and cost estimate on the most viable options in each category. The resulting IT Report entitled "Report on Recommendation for the Frederick County Tire Fire" was made available to EPA Region III and the State on December 8, 1983, and is the basis for our current operating mode on scene. On December 9, 1983 EPA Region III held a meeting on scene with the State and various technical experts to discuss the findings of the report.

Findings of IT Report

I. Extinguish the fire - three options considered

- A. Injection of gas such as Nitrogen or Carbon Dioxide to break the flow of air into the tire fire.

Rejected because:

1. distribution system needed to inject gases too uncertain
2. cost of gas prohibitive (\$4 million minimum)
3. it could take up to 400 days to cool the pile, during which time the oil could continue to flow
4. volume of gas needed ( $2.3 \times 10^9$  scf)

- B. Injection of steam (water) to cool tires to a temperature below the reignition point.

Rejected because:

1. actual test of this option proved unsuccessful

AR100211



- C. Smother fire by covering it with dirt - this is the option recommended in IT's report - approximate cost \$375,000.00

Temporarily rejected because:

1. property owner's consent would be required
2. EPA would be creating a landfill and possible leachate problems
3. cool down period may still be 400 days during which time the oil could continue to flow (the main problem at the site would still not be solved)
4. the oil flow from the site has steadily been decreasing (presently 1-4 gpm) and may stop in another month, making it unnecessary to extinguish the fire
5. covering the fire may prove too dangerous.

II. Accelerate Burning -

- A. Injection of air into the pile to accelerate burning

Rejected because:

1. there would be a higher rate and quantity of air emissions
2. an extremely large air flow rate (200,000 - 400,000 scfm) would be needed to significantly reduce the burn rate. This would require a complex and expensive distribution system.

III. Status Quo -

- A. Allow fire to burn, continue to contain and collect the tar

this is the option currently being practiced by the region because:

1. no environmental monitoring data collected so far indicates ~~an~~ immediate need to extinguish the fire
2. all of the options considered so far for extinguishing the fire have undesirable elements associated with them that argue in favor of maintaining status quo approach
3. the oil flow is decreasing to the point that it may stop shortly, or to the point that the oil can be dammed up in the fire - in which case the removal action will be over
4. the present collection system has successfully dealt with the principal contamination problem associated with this fire. Industry experts have recommended that the oil collection, not the fire be the main concern of the Agency.

In light of the options presented above, it is the Region's opinion that EPA should maintain status quo efforts for at least another month or two before making any decision on dealing with the fire. During this time, response costs will be scaled down to a "bare bones" operation, and other options for extinguishing the fire, which are outside the scope of the IT report, can be considered.

AR100212

CHRONOLOGY of FUNDING REQUESTS and EXPLANATION of NEED

- 11/02/83 Regional Administrator approves \$250,000.00 (limit of his funding authority) to initiate action.
- 11/04/83 On-Scene Coordinator (OSC) requests \$500,000.00 ceiling increase but is granted only \$225,000.00 by Headquarters that same day.
- 11/08/83 OSC requests \$425,000.00 ceiling increase bringing project ceiling to \$900,000.00 - NOTE: According to Removal Guidance OSC could not request an increase that would cause project ceiling to exceed \$900,000.00 prior to requesting an exemption of the \$1 million limitation on removals.
- 11/09/83 Ceiling increase granted by Headquarters.
- 11/14/83 Exemption to \$1 million limitation requested.
- 11/17/83 Exemption granted - OSC is now free to request another ceiling increase.
- 11/17/83 OSC requests ceiling increase of \$250,000.00 to deal with unanticipated wash out of containment structures due to heavy rains.
- 11/18/83 Ceiling increase granted.
- 11/21 - Period of time during which ERT and IT are developing a report  
12/09/83 on the feasibility of putting out the fire.
- 11/29/83 OSC requests ceiling increase of \$200,000.00 in order to maintain site operations while awaiting completion of IT report. Recommendations of report will determine future course of action and cost.
- 12/01/83 Ceiling increase granted.
- 12/09/83 Report issued - EPA and State decide not to attempt to extinguish fire but to continue collection operation and enter into a planned removal.
- 12/20/83 OSC requests ceiling increase of \$100,000.00 in order to carry on site operations while developing planned removal.
- 12/21/83 Headquarters approves only \$35,000.00 increase.

AR100213

**APPENDIX E**

AR100214

Average Hydraulic Conductivities  
by Bouwer + Rice Method  $(1.6 \times 10^{-4} \text{ cm/sec})$   
Overburden Wells 15, 23, 35, 45  $K = 5.4 \times 10^{-6} \text{ ft/sec}$   
Bedrock Wells 10, 20, 40  $K = 1.4 \times 10^{-4} \text{ ft/sec}$   
 $(1.4 \times 10^{-4} \text{ ft/sec})$

AP-6  
ORIGINAL  
(Red)

GROUND WATER TABLE ELEVATION DATA

Project Number- 9616.58

Project Location- Rhinehart Tire Fire, Winchester VA.

All measurements are in feet

Well Number	TF-15	TF-10	TF-25	TF-20	TF-35	TF-45	TF-40
Well Depth	20.0	68.0	20.7	71.5	20.4	13.5	43.0
Screen Interval	10-20	—	10.7-20.7	—	10.4-20.4	8.5-13.5	—
Open Hole Interval	—	39-60	—	39.8-71.5	—	—	24-43
Grade Elev.	1057.10	1057.00	953.10	953.40	972.10	912.20	912.10
Casing Stickup	1.45	1.80	1.60	1.80	2.25	3.30	1.44
Casing Elev.	1058.55	1058.80	954.70	955.20	974.35	915.50	913.54

Date 2/9/84

Depth to water	9.83	9.82	10.64	11.90	5.90	N.A.	N.A.
Water level elev.	1048.72	1048.98	944.14	943.22	968.45		

Date 2/10/84

Depth to water	9.80	9.41	10.81	12.06	6.89	9.22	5.00
Water level elev.	1048.75	1049.39	943.97	943.14	967.46	906.28	908.46

Date 2/29/84

Depth to water	6.76	7.61	10.20	12.24	4.66	7.52	4.77
Water level elev.	1051.79	1051.19	944.58	942.96	969.69	907.98	908.77

Date 3/1/84

Depth to water	10.01	8.24	10.47	12.51	7.24	7.70	4.70
Water level elev.	1048.54	1050.56	944.31	942.69	967.11	907.80	908.84

AR100215

CERTIFICATE OF ANALYSIS

March 28, 1984

Rhinehart Tire Fire

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
116 N. Main Street  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 03-02-84

Identification No.:

Lab #

Submitted By:

Analyst: Paul W. Kohler  
Michael F. Martin

Description:

1763, 1772: Monitoring well, TF-2S  
1764, 1773: Monitoring well, TF-2D  
1765, 1774: Monitoring well, TF-4D  
1766, 1775: Monitoring well, TF-4S  
1767, 1776: Monitoring well, TF-3S  
1768, 1777: Monitoring well, TF-1S  
1769, 1778: Monitoring well, TF-1D  
1770: Monitoring well, TF-Blank  
1771, 1779: well, Virginia Snapp

Results: (in ug/l)

Priority Pollutants:

	TF-2S	TF-2D	TF-4D	TF-4S	TF-3S	TF-1S	TF-1D	Blank <sup>+</sup>	Well
Benzene	8.6	<0.2	6.4	69	3.3	<0.2	<0.2	<0.2	<0.2
Toluene	2.9	0.2	6.4	105	0.7	<0.2	<0.2	0.71	<0.2
Ethylbenzene	0.7	<0.2	<0.2	61	0.6	<0.2	<0.2	<0.2	<0.2
Xylenes	8.6	0.45	9.5	72	3.8	0.9	<0.2	0.26	<0.2
Naphthalene	3.3	0.81	4.5	3.9	3.5	<.5	<.5	<.5	<0.5
Acenaphthalene	<.5	<.5	1.2	0.89	<.5	<.5	<.5	<.5	<0.5
Phenol	<1	<1	2.2	58	<1	<1	<1	<1	<1

No other priority pollutants were detected (Limit of Detection = 0.2 to 5ug/l)

<sup>+</sup> Blank was prepared and submitted by SWCB

Note Well 4S & 4D  
drilled through  
contaminated fill  
& may not represent  
true ground water  
quality - S 4/84

RECEIVED  
APR 2 1984

VALLEY REGIONAL  
OFFICE

ORIGINAL  
(Red)Other Contaminants\*

	TF-2S	TF-2D	TF-4D	TF-4S	TF-3S	TF-1S	TF-1D	Blank	Well
Phenyl isocyanide (Cyanobenzene)	< .5	< .5	4.0	74	2.1	< .5	< .5	< .5	< .5
2(2-n-butoxyethoxy) ethanol	20	< 1	13	391	6.7	< 1	< 1	< 1	< 1
2(2-n-butoxyethoxy) ethanoic acid	180	< 1	< 1	< 1	1	< 1	< 1	< 1	< 1
Benzothiazole	2.1	< .5	8.6	63	2.6	< .5	< .5	< .5	< .5
Caprolactam	21	3.5	170	800	27	< 1	< 1	< 1	< 1
2-Methylbenzothiazole	14	< .5	32	26	.5	< .5	< .5	< .5	< .5
N,N-dimethylbenzamide	2.4	< .5	3.0	9.6	3.1	< .5	< .5	< .5	< .5
Benzoic Acid	< 1	< 1	27	300	< 1	< 1	< 1	< 1	< 1
p-Toluic Acid	0.5	< 1	1.9	78	1.9	< 1	< 1	< 1	< 1
3-Cyanobenzoic Acid	< 1	< 1	< 1	52	1.0	< 1	< 1	< 1	< 1

Confirmed by GC/MS with authentic standards

RECEIVED  
APR 2 1984VALLEY REGIONAL  
OFFICE

AR100217

ORIGINAL  
(Red)

4683

1 -

TF3S

TF2S

TF2D

TF4D

TF4S


TF1D

TF1S

Aerial Photo for  
Geographic Survey  
November 10 1983

Test Well Locations

AR100218



100% Not for Distribution

AR100219

10000010



STONE

EPA-17

ORIGINAL  
(Red)



COMMONWEALTH OF VIRGINIA

DEPARTMENT OF CONSERVATION  
AND ECONOMIC DEVELOPMENT

DIVISION OF MINERAL RESOURCES

# GEOLOGY AND MINERAL RESOURCES OF FREDERICK COUNTY

Charles Butts and  
Raymond S. Edmundson

BULLETIN 80

VIRGINIA DIVISION OF MINERAL RESOURCES

James L. Calver  
Commissioner of Mineral Resources and State Geologist

CHARLOTTESVILLE, VIRGINIA  
1966

AR100220

COMMONWEALTH OF VIRGINIA  
DEPARTMENT OF CONSERVATION AND ECONOMIC DEVELOPMENT  
DIVISION OF MINERAL RESOURCES

James L. Calver

Commissioner of Mineral Resources and State Geologist


ORIGINAL  
(Red)

EXPLANATION


MISSISSIPPIAN




Pocono (?) formation  
*Shale, sandstone, and conglomerate. Noted only in Shockey's Knob along the Virginia - West Virginia boundary.*




Hampshire formation  
*Chiefly red shale, mudrock, and sandstone.*



Chemung formation  
*Chiefly gray shale and sandstone with thin conglomerates and a few red zones.*



Brallier formation  
*Greenish to brown micaceous shale with thin intercalated layers of fine-grained gray sandstone.*




Hamilton formation  
*Dark-gray to olive-green fine-grained sandstone with interbedded dark-colored shale.*



Marcellus shale  
*Dark-gray to black, fissile shale; weathers gray.*



Onondaga formation  
*Dark-green, non-fissile shale; in part calcareous.*




Oriskany sandstone  
*Gray to white, coarse-grained, thick-bedded sandstone.*



New Scotland limestone

DEVONIAN


ORDOVICIAN




Juniata form  
*Chiefly red shale or red, and thin-bedded, red, ark*




Oswego form  
*Gray and greenish, thin grained sandstone and co*



Martinsburg f  
*Brownish, fissile shale, nated, fine-grained sands*




Edinburg (Chamber) formatic  
*Dark-gray to black, cony nodular layers, thin sills amounts of black shale.*



Lincolnshire (Lenoi)  
*Dark-gray, finely crystall; stringers and nodules of b*



New Market (Moshe)  
*Dove-colored, compact, l stone.*



Bellefonte (Upper B) formatio  
*Light to dark-colored lim crystalline gray dolomite.*



Nittany Lower Bee formation  
*Bluish-gray limestone with of gray dolomite*

AR100221



APR 10 1962



APPENDIX F

AR100224

ORIGINAL  
(Red)

NUS CORPORATION

TELECON NOTE

CONTROL NO:

DATE:

3/26/84

TIME:

10:30 AM

DISTRIBUTION:

TO FILE

BETWEEN:

J. STEVEN DORRER

OF:

CHIEF  
EPA-EMERG. RESP. BR.

PHONE:

(201) 321-6600

AND:

DAVE KINDIG

(NUS)

DISCUSSION:

CALLED FOR BACKGROUND INFO. ON RHINEHART TIRE

- HAS LITTLE INFO. ON SITE PREVIOUS TO

FIRE. SUGGESTED CONTACTING TOM MASSEY (ERT -

ON SITE COORDINATOR) 597-9858

ACTION ITEMS:

AR100225

ORIGINAL

NUS CORPORATION

(Red)

TELECON NOTE

CONTROL NO:

DATE:

3/26/84

TIME:

DISTRIBUTION:

TO FILE

BETWEEN:

MAC STERRETT

OF:

VA. WCB

PHONE:

(703) 828-2595

AND:

DAVE KINDIG

(NUS)

DISCUSSION:

CALLED FOR BACKGROUND IN COMPLETING RHINEHART  
TIRE FIRE PA/SE/MRS.

- COUNTY BANNED DUMPING IN L.F., RHINEHART REC'D  
PERMISSION TO DUMP ON HIS LAND, BUT SOLICITED BUSINESS  
AS FAR AS 200 MI AWAY. TIRES SOLD TO SEAWARD  
INTERNAT'L FOR DOCKING BUMPERS. ALSO HAD PLANS TO  
RECOVER OIL W/INCINERATOR HE BUILT. INCINERATOR ON  
SITE BUT NOT TESTED. 1° CONTAINMENT W/ 50' Ø POND  
DUG BY ERT (50K GAL), 2° CONTAINMENT LARGER (400K GAL)  
AND LINED, OILS PUMPED FROM 2°.

- 17 DOMESTIC WELLS SAMPLED, NO CONTAMINATION  
7 MONITORING WELLS AROUND FACILITY - ONLY  
XYLENE (16 mg/l) AND CAPROLACTAM (400 mg/l)  
FOUND IN SHALLOW WELLS. DEEP WELLS CAPROLACTAM  
FOUND IN LOW CONC. (2.7 mg/l) 1ST 3 WELLS

ACTION ITEMS:

SAMPLED 1/31/84, ALL 7 SAMPLED 2/28/84 (RESULTS  
NOT IN YET)

- FIRE STILL SMOLDERING, ALMOST ALL TIRES DESTROYED,  
~ 20% OF ORIGINAL VOLUME → RHINEHART HAS  
SCRAPED UP RESIDUE. WATER STORAGE POND HAS NO  
RELATIONSHIP TO DUMP SITE.

AR100226

NUS CORPORATION

TELECON NOTE

CONTROL NO:

DATE:

3/26/84

TIME:

10:45 AM

DISTRIBUTION:

TO FILE

BETWEEN:

TOM MASSEY

OF:

EPA - ERT

PHONE:

(215) 597-9858

AND:

DAVE KINDIG

(NUS)

DISCUSSION:

NEEDED BACKGROUND TO COMPLETE DESKTOP PA/HRS/SI

- FACILITY STARTED APPROX TEN YRS AGO. OWNER

(PAUL RHINEHART) RECEIVED MONEY FOR TAKING

OLD TIRES. WANTED TO USE THEM FOR MAKING

CARBON BLACK. FURNACE FOR BURNING TIRES ON

SITE &amp; OPERATIONAL, BUT NOT FUNCTIONING. PHOTOS

IN POSSESSION OF ERT &amp; VA. WCB. NO PERMITS OR

PAST REGULATORY ACTION. CITED BY COUNTY &amp; STATE,

BUT NO ACTIONS TAKEN. TWO WOODEN GARAGES ON

SITE BETWEEN RHINEHART HOME &amp; SITE (ONE

BURNED DOWN). APPROX 1000 PEOPLE IN 3MI RADIUS.

ERT NO LONGER ON SITE. FIRE STILL SMOLDERING.

CONTACT STEVE JARVELLA - 597-9325 (ERT)

ACTION ITEMS:

AR100227



NUS CORPORATION

CONTROL NO:

DATE:

3/29/84

TIME:

9:15 AM

DISTRIBUTION:

TO FILE

BETWEEN:

STEVE JARVELLA

OF:

EPA ERT (10th  
FIR  
6th 3/29/84)

PHONE:

(215) 597-9325

AND:

DAVE KINDIG

(NUS)

DISCUSSION:

087  
83

- APPROX. 800,000 gal. removed from site - fire still smoldering - no oil being produced - slope of discharge area  $\approx$  45° - injunction to stop dumping - 2 wks before fire, issued by County result of complaints from neighbors - incinerator to carbon black & oil

- CALL JOHN RILEY - FRED CITY ADMINISTRATOR  
ABOUT COURT ACTIONS 703-667-2365

- HARRY ALLEN - ERT - EDISON, NJ - GROUNDWATER  
201-

ACTION ITEMS:

AR100228

NUS CORPORATION

TELECON NOTE

CONTROL NO:

DATE:

3/29/84

TIME:

9:30 AM

DISTRIBUTION:

TO FILE

BETWEEN:

JOHN RILEY - COUNTY  
ADMINISTR.

OF:

FREDERICK CTY.

PHONE:

(703) 667-2365

AND:

DAVE KINDIG

(NUS)

DISCUSSION:

- COMPLAINT FROM BILL PULLMAN (NEIGHBOR) ABOUT DUMPING/PILOT INCINERATOR. RHINEHART HAD SEVERAL TRUCKS FOR DELIVERING DISCARDED TIRES TO SITE. TRUCKS MAINTAINED ON SITE, BUT WERE USUALLY OUT ON ROAD. COUNTY FILED SUIT TO STOP HIM IN CIRCUIT COURT. TO PREVENT HIM FROM DUMPING AFTER OCT 7, 1983, TRIED TO CONTINUE OPERATION, BUT TRUCKS WERE TURNED AWAY. APPARENTLY, THERE WAS NO VIOLATION OF STATE LAW, & COUNTY WAS AWAITING RHINEHART'S RESPONSE TO INJUNCTION WHEN TIRES CAUGHT FIRE.

7 MILLION TIRES - EST. BY SURVEYOR (TOM SHOCKEY)  
SITE APPROX 700' X 300' (5 ACRES)

RHINEHART WELL IS A SPRING

ACTION ITEMS:

AR100229

ORIGINAL

(Red)

TELECON NOTE

NUS CORPORATION

CONTROL NO:

DATE:

3/29/84

TIME:

2:00 PM

DISTRIBUTION:

TO FILE

BETWEEN:

TIM STONE - Hydrogeologist

OF:

IT CORP.  
(EERU)

PHONE:

(201) 548-9660

AND:

DAVE KINDIG

(NUS)

DISCUSSION:

STONE DID CONSTRUCTION & SAMPLING OF GROUNDWATER  
MONITORING WELLS (7) IN VICINITY OF FIRE. REPORT TO BE  
SUBMITTED TO EPA WITHIN 2 WKS (REQUESTED COPY).

- SOIL TYPES - FINE SAND, SILT & SOME CLAYS ->

BASICALLY WEATHERED SHALE & SANDSTONE - APPROX.

20-30' IN DEPTH

- PERMEABILITY - BOUWER & RICE TEST

SHALLOW -  $10^{-6}$  FT/SEC DEEP -  $10^{-4}$  -  $10^{-5}$  FT/SEC

SHALLOW WELLS - AQUIFER 140' FEET DEEP THICK,

SATURATED ZONE ~ 10' BELOW SURFACE

DEEP WELLS - 100-300' BELOW SURFACE ELEV.

- YIELDS - SHALLOW -  $< \frac{1}{2}$  GPM, DEEP - 0.1-15 GPM.

ACTION ITEMS:

AR100230

ORIGINAL

APP 6

NUS CORPORATION

(Red)

TELECON NOTE

CONTROL NO:

DATE:

4/6/84

TIME:

11:30 AM

DISTRIBUTION:

TO FILE

BETWEEN:

JOHN RILEY - ADMINISTRATIVE

OF:

FREDERICK CO.

PHONE:

(703) 667-2365

AND:

DAVE KINDIG

(NUS)

DISCUSSION:

- LOCAL FIRE MARSHALL HAS NOT DESIGNATED SITE TO BE FIRE OR EXPLOSION THREAT
- NO STATE PARKS IN AREA; AREA IS LARGELY RURAL, LITTLE/NO INDUSTRY
- SOME AGRICULTURAL LAND IN AREA (RHINEHART PROPERTY USED TO RAISE HORSES - MAY BE CLASSIFIED AGRICULTURAL

ACTION ITEMS:

AR100230A

NUS CORPORATION

TELECON NOTE

CONTROL NO:

DATE:

4/18/84

TIME:

11 AM

DISTRIBUTION:

TO FILE

BETWEEN:

TIM STONE

OF:

IT CORP.

PHONE:

(201) 548-9660

AND:

DAVID R. KINDIG

(NUS)

DISCUSSION:

- Groundwater monitoring/testing has distinguished 2 ~~sq~~ levels of groundwater (shallow and deep).
- shallow flow is to NW, deep flow has not been defined
  - groundwater in shallow aquifer shows a 100 ft gradient over ~1 mile to NW
  - contamination is confined to shallow aquifer with a majority surfacing at the unnamed tributary to Hague Creek - no long range contamination problem, should have decreasing concentrations over the years
  - unsat. zone - permeability (hyd. conductivity) =  $10^{-6}$  ft/sec, and  $10^{-4}$ - $10^{-5}$  ft/sec in bedrock
  - some wells are in deeper aquifer and are unaffected (200-300' deep)

ACTION ITEMS:

AR100231

## NUS CORPORATION

## TELECON NOTE

CONTROL NO:

FB-8403-07

DATE:

25  
9-~~27~~-84

TIME:

1553

DISTRIBUTION:

F.1e

P1 of 2

RE: Confirmation of geology/hydro. information collected by IT consultant at Rhinehart Time Fire.

BETWEEN:

Tim Stone - Hydrogeologist

OF:

IT Corp

PHONE:

(201) 548-9660

AND:

Martin R. House - Geologist / Hydrogeologist

(NUS)

DISCUSSION:

- Underlying formation is the Channing. Strike NE-SW. Dip 45° ESE. Syncline plunges southerly in area of site. <sup>~1500 ft thick</sup> 2000 ft vertical thickness to underlying formation.
- Bedrock was mostly fine grained, very hard, sandstone, some shale, some ~~the~~ weathered zones / 1/2" to 2" clay zones. Some fracture traces. Most of the formation was very massive.
- Thickness of the overburden ranged from 0-30' in and around the site and averaged about 20-30 feet. Generally, thickest near top of ridge and absent in valley. (stripped off by stream). Muddy Run runs into bedrock.
- The overburden is gradational to bedrock with definite zones of competence.
- Flow believed to be mostly confined to the overburden in this area & ultimately discharges to Muddy Run. Artesian conditions in the bedrock created by topographic relief off Hunting Ridge produce a vertical flow component believed to be strong enough to impede impede most flow infiltration. Infiltration from ~~one~~ surface to bedrock would be greatest in areas of thin or none existing ~~bedrock~~ overburden. Shallow well

ACTION ITEMS:

- Put in Muddy Run showed some contamination. This was expected because it is believed that Rhinehart's park has discharged to the run in the past. The only bedrock well to show contamination was a well <sup>installed</sup> ~~placed~~ directly downgradient of the fire pile.
- Since only 3 bedrock wells were installed, IT Corp. could not accurately determine regional flow direction for the area. It is suspected the regional flow would be in a south ~~west~~ east direction.

NUS CORPORATION

TELECON NOTE

CONTROL NO:

F3-840307

DATE:

25  
9-~~24~~84

TIME:

DISTRIBUTION:

Rhinehart Tire Fire

P2 of 2

BETWEEN:

Tim Stone - Hydrogeologist

OF:

IT Corp.

PHONE:

(701) 548-9660

AND:

M. Howe

(NUS)

DISCUSSION:

the structural nature of the geology in the site area. Principal flow is believed to along near vertical joint sets. Fracture tracer measurements reveal a SE-NW alignment of the joints. These vertical joints allow artesian flow to force water in the overburden up thus impeding infiltration.

A leachate (oil) seep was found at 50 to 75 feet laterally of the pad area. Trenching revealed that flow was along a more competent zone within the overburden.

Mr. Stone believes that it is possible for wastes from the site to enter the bedrock aquifer; however it would most likely travel toward and ultimately discharge to Wassy Run. Infiltration seems to depend on the thickness of the overburden and to what degree it has been reworked. It is not known to what extent Mr. Rhinehart reworked the soils in the site area prior to starting the dump.

ACTION ITEMS:

There are over a dozen home wells in the area. Drillers for IT Corp. stated to Mr. Stone that wells near the ridge top (Hunting Ridge) go to a depth of 300'. Yields in the bedrock are between 1 to 15 gpm which seems to depend on the amount of fractures hit. Mr. Rhinehart draws water from a spring on his property. Analysis of this spring has yet to show contamination. Rhinehart's well is the closest to the site. Next closest is .25 miles or so away.

AR100233

ORIGINAL  
(Red)

NUS CORPORATION

TELECON NOTE

CONTROL NO:  
F3-8443-47

DATE:  
9/27/84

TIME:  
1356

DISTRIBUTION:

TO FILE

BETWEEN:

MARK DAVIS

OF:

FREDERICK County  
DISTRICT CONSERVATIONIST

PHONE:

(703) 662-3312

AND:

R. Gornell, FIT III

(NUS)

DISCUSSION:

Call was made to inquire about Frederick County Soil Survey availability for the documentation of existing soils at the Rhinclart Fire Site.

Mr. Davis explained that the area has been mapped but, the final edition of the Soil Survey is not available. I described the location of the site and, Mr. Davis referred to his copy of the map and provided the following:

Sites at the site are of the Wubert Berles Channery Silt Loam 25-65%  
are

ACTION ITEMS:

AR100234



**APPENDIX G**

AR100235

ORIGINAL  
(Red)

## memorandum

DATE: February 15, 1984

REPLY TO  
ATTN OF:Harry L. ATten, Ph.D.  
Environmental Response Branch

SUBJECT:

Transmittal of the Preliminary Environmental Assessment Report  
for the Rhinehart Tire Fire

TO:

Thomas Massey, Senior On-Scene Coordinator  
Environmental Protection Agency, Region IIITHRU: J. Stephen Dorrlor, Chief  
Environmental Response Branch

Enclosed is Environmental Response Team's Preliminary Environmental  
Assessment Report for Rhinehart Tire Fire, Winchester, Virginia.

Since I anticipate questions, complaints, and/or praise for this report,  
I have included most of the documentation with the names of the preparers  
as appendices. The principal ERT contacts are Rod Turpin for the air  
work and myself for the rest of the report. I have not included the  
ERT Field Data Sheets or the Analytical Reports from ETC, Inc. for the  
ERT water quality data summarized in Table 5.

If we can be of any additional assistance, please do not hesitate to  
call.

Enclosure

RECEIVED EEB  
FEB 23 1984OPTIONAL FORM N  
(REV. 1-80)  
GSA FPMR (41 CFR) 101-11.6  
5010-114

AR100236

ORIGINAL  
(Red)

PRELIMINARY ENVIRONMENTAL ASSESSMENT REPORT

RHINEHART TIRE FIRE  
WINCHESTER, VIRGINIA

FEBRUARY 1984

REC-113  
FEB 21 1984



ENVIRONMENTAL RESPONSE TEAM  
WOODBIDGE AVENUE, EDISON, NEW JERSEY

AR100237

## PRELIMINARY ENVIRONMENTAL ASSESSMENT OF THE RHINEHART TIRE FIRE

1.0 BACKGROUND

At about 1:00 A.M. on October 31, 1983, a fire of suspicious origin broke out in a 5-acre tire storage area on a steep hillside on the Rhinehart property near Winchester, Frederick County, Virginia. Fire fighters failed to control the blaze, which spread to engulf an estimated 5 to 7 million tires. Black smoke from the fire was visible over twenty miles away. Shortly after the fire started, hot oil produced from melting and pyrolysis of the tire mass, began to seep out of the toe of the tire pile and into an unnamed tributary to Hogue Creek. An unestimated quantity of oil flowed into Hogue Creek, which is a tributary to the Potomac River system. The nearest public water supply intake on this system is 22 miles downstream.

On October 31st, a catch basin was installed to trap the oil and to provide water for fighting the fire. High rates of oil and water seepage threatened to exceed the basin's storage capacity and the Environmental Protection Agency (EPA), Region III was activated. Shortly thereafter, Mr. Tom Massey, EPA On-Scene Coordinator, activated the Environmental Response Team (ERT).

1.1 PURPOSE

The ERT was requested to evaluate the immediate hazards to public health relating to air emissions from the fire and to the health and safety of response personnel. An air monitoring program was designed for this purpose. The ERT was also requested to conduct a joint study with the Virginia Water Control Board (WCB) to investigate surface water and groundwater contamination. The surface water study was dovetailed into an emergency monitoring program already being conducted by the WCB. The groundwater program, designed mainly to determine whether contamination is reaching the deeper aquifer, was deferred until the imminent hazard could be brought under control, and is now underway.

1.2 DESCRIPTION OF STUDY AREA

The Rhinehart site is located along Hunting Ridge; in the ridge and valley province of the Blue Ridge Mountains. The location has been mapped by the U.S. Geological Survey (see Figure 1, USGS Hayfield, VA quadrangle). The principal drainage of Hunting Ridge is Hogue Creek, which flows northeast along the strike of the Ridge and collects runoff from tributaries and groundwater outcrops from the wooded transverse valleys along its route. Drainage from the Rhinehart site enters one of these unnamed tributaries, which has been nicknamed "Massey Run" for temporary identification purposes. Hogue Creek has been designated a put-and take trout stream (Class V) by the Water Control Board. Very stringent water quality standards apply.

The site is underlain by a consolidated shale formation with some interbedded sandstone. Overburden consists of weathered bedrock. The strike of the formation is from SW-NE (along the strike of the Ridge). The formation dips to the east-southeast (ESE) at an angle of 35° - 50°. Hence, the bedding planes under the site dip into the Ridge at a downward angle such that one foot of run results in about one foot of drop-back under the tire pile. Groundwater flow in the weathered overburden is clearly toward Massey Run, as attested to by the oil-water seepage. Deeper flow probably follows the exposed bedding planes, particularly towards the southwest, although some flow may be occurring down-dip into the rock formation through fractures or loose joints. The groundwater study will address these concerns in more detail.

The air dispersion characteristics common to the eastern ridge and valley provinces apply to this site. The generally prevailing west to northwest winds carry the plume across the ridge tops and into the valleys beyond. Inversion conditions could lead to an excessive buildup of airborne materials in nearby valleys, which when added to the accumulated emissions from the woodstoves of the residents themselves could produce an air pollution condition. The issue is whether intermediate dispersion is adequate to eliminate this possibility for this particular site. The nearby downwind area is sparsely populated, except for the Rhinehart residence, which is less than 1000 feet from the fire perimeter.

## 2.0 DESCRIPTION OF SURVEY

### 2.1 AIR

Primary consideration was given to monitoring of vapors and aerosols in the air and smoke because of the dual needs of establishing respiratory protection levels for exposed workers on-site and establishing a possible evacuation perimeter for affected residents. For both these reasons, air monitoring programs were coordinated with the Centers for Disease Control (CDC) to determine the health risk.

In addition to the ERT air monitoring efforts, CDC requested NIOSH to do some additional air monitoring. The status of the NIOSH effort is unknown at this time.

An integrated air monitoring program was designated and implemented on 11/3/83 in accordance with ERT's protocol for uncontrolled hazardous waste sites. This guideline addresses five steps which provide a rapid and cost-effective characterization of air pollution from the site. The five include: 1) Determining Background Conditions; 2) Determining Concentrations On-site; 3) Determining Site (or Impact) Area Concentrations; 4) Identifying Specific Contaminants (if needed); and 5) Identifying Particulate Contaminants (if needed).

The sampling array is shown in Figure 2. Monitoring stations are described in Table 1. The program consisted of one background station, two off-site downwind stations, six on-site stations and off-site grab samples with the Real-Time Aerosol Monitor (RAM). The following is a breakdown of the type of samples:

1. NIOSH P&CAM-168 (Aromatic Amines) 3-stage silica gel tubes = 11 samples.
2. NIOSH P&CAM-127 (Organic Vapor Scan) 150 mg carbon tubes = 5 samples.  
600 mg carbon tubes = 15 samples
3. ERT 2-stage tubes (Organic Vapors) Tenax/Chromosorb  
102 collection tubes = 23 samples
4. OVA/Thermal desorption collection tubes = 6 samples
5. Particulate cassettes for analyses of organic/inorganic  
contaminants = 14 samples

On November 22, 1983, and again on November 30, 1983, the clean-up contractor began programmed spraying of the fire with water from Rhinehart's pond to reduce the pond volume and to protect the integrity of the retaining dam. Quenching the fire in this manner was of great concern because of the possibility of forming noxious products by limiting combustion at the fire surface and releasing them in the steam generated. Another air monitoring program was begun to duplicate the earlier schemes under the spraying conditions and to provide rapid field data for control of the spraying operation in case high levels of particulates or volatile materials indicated any imminent hazard.

See Appendix A for the ERT Air Monitoring Report.

## 2.2 SURFACE WATER

The major concerns of the surface water studies included the immediate impacts of the spill on the water resource and on the water supplies downstream and the long term impact of residual seepage on the water supply and on the environment.

The State WCB began to monitor the water quality of Massey Run and Hogue Creek on November 3rd, and has continued monitoring on a weekly to bi-weekly schedule since that time. The WCB sampling locations are shown in Figure 3. The results of the State studies from November 3 to December 16, 1983 arrived in the ERT office on January 19, 1984. The WCB data reports are included as Appendix B. The results of the December 19th survey were obtained by phone a few days later. The WCB samples usually were analyzed for priority pollutant volatiles and several were analyzed for acid compounds, base neutrals, and caprolactam (nylon monomer). Flow data for the sampling days (mean daily discharge) were collected from the State gaging station located on Hogue Creek at Route 614, downstream of the fire site. The flow data and selected water quality data are summarized in Table 2.

The ERT participated with the State in conducting a water quality survey on November 18, 1983. See Figure 4 for sampling locations.

The surface water study consisted of sampling water and sediment from the affected waterways between the lower containment pond and the gaging station at Route 614. The Microtox® unit was employed as a rapid and sensitive indicator of toxicity associated with the tire fire leachate because the major constituents, aromatics and phenolics, give excellent Microtox responses. However, the Microtox measures toxicity to bioluminescent marine bacteria, which would seem to be of small value in estimating the environmental impact on the Hogue Creek ecosystem. Therefore, selected samples were analyzed chemically to determine whether the Microtox results correlated with the known toxicity of chemical compounds present to human health and indigenous aquatic life. Real time measurements of pH and temperature were made to determine whether large quantities of benzoic acid and/or heat from the leachate could be influencing stream toxicity. ERT chemical samples were also analyzed for total organic carbon (TOC) as a relative indicator of total contamination.

Upstream control samples for complete analysis were taken on the presumably uncontaminated western tributary to the lower containment pond, and on Hogue Creek about 1000 feet upstream of the confluence with Massey Run. Stream flow was estimated at the Hogue Creek control station using a portable velocity meter and a tape measure. Massey Run could not be gaged accurately because it was too shallow and had poor channel characteristics. Its flow was determined by the difference in flow on Hogue Creek above and below the confluence.

Samples for complete analysis were also taken at the mid-point in Massey Run and in Hogue Creek about 1500 feet downstream of the confluence. Streamflow was also estimated at the latter station. Duplicate samples were taken by the WCB for purgeable organic analysis at both of these stations.

Microtox-only samples were taken in the lower containment pond and at three intermediate points along Massey Run (two above and one below WCB Station 01) and at two points downstream on Hogue Creek (near the point where a small fish kill had occurred earlier and at the gaging station).

The following table summarizes the water analyses performed by the EPA (ERT) and the State (WCB) for the samples taken on 11/18/83:

<u>Station # (ERT/WCB)</u>	<u>Purgeable Organics</u>	<u>Acid Compounds</u>	<u>Base/ Neutrals</u>	<u>TOC/Phenols/ Cyanide</u>	<u>Microtox</u>
H01/03A	ERT	ERT	ERT	ERT	ERT
H02/02	ERT/WCB	ERT	ERT	ERT	ERT
H03	-	-	-	-	ERT
H04/02A	WCB	-	-	-	ERT

<u>Station #</u> <u>(ERT/WCB)</u>	<u>Purgeable</u> <u>Organics</u>	<u>Acid</u> <u>Compounds</u>	<u>Base/</u> <u>Neutrals</u>	<u>TOC/Phenols/</u> <u>Cyanide</u>	<u>Microtox</u>
T05	ERT	ERT	ERT	ERT	ERT
T06	-	-	-	-	ERT
T04	-	-	-	-	ERT
T03/01	ERT/WCB	ERT	ERT	ERT	ERT
T02	-	-	-	-	ERT
T01	-	-	-	-	ERT

The State water quality data for these samples are included in Appendix B (report dated December 5, 1983). The ERT chemistry data is summarized in Table 3 (5 pages). The ERT Microtox Data is summarized in Table 4. The full Microtox Report is included as Appendix C.

### 2.3 GROUNDWATER

The geology of the site suggests subsurface contamination is a possibility. Preliminary investigations have revealed there is considerable artesian pressure in the lower aquifer which may not permit infiltration by the oily leachate. However, the probability of fracture flow or flow along the bedding planes cannot be ruled out without further study. As of this date, the well drilling program is nearing completion as planned, except that unforeseen problems due to weather and equipment failure have interfered with the schedule. Once the wells are in place, the ERT and the WCB will conduct the necessary well testing, sampling, and analysis. The groundwater report will be included as an addendum to this Preliminary Environmental Assessment.

The Groundwater Study Plan is included as Appendix D.

### 3.0 DATA INTERPRETATION

This chapter addresses the significance of the analytical findings in the areas of emissions, transport, and environmental concentrations. Where statements are made regarding health impacts, they should be considered very preliminary subject to a review to be made by the Centers for Disease Control (CDC).

#### 3.1 AIR

Field monitoring of airborne organic vapors and particulates resulting from the tire fire revealed significantly elevated levels in the nearby environment. Concentrations were sufficient to be considered hazardous in the smoke plume given prolonged exposure and sufficient to cause concern



for potential exposure to gusts of smoke and exposure to plume settlement downwind. Subsequent chemical analysis confirmed the field monitoring results and supported the recommendation of an air pollution alert by ERT and the CDC on November 4, 1983. Subsequent to this recommendation, VA Department of Health released a public health advisory regarding potential plume exposure.

The duration and magnitude of the exposure hazard are principally related to the source strength and its changes with time and the air dispersion and dilution characteristics and their changes with time. As the fire loses its power, the source strength diminishes. Periodic flare-ups produce only a fraction of the original emission rate on a daily basis. If dispersion does not also decrease proportionately, exposure potential decreases dramatically. Restructuring of the exposure scenario mandates reconsideration of acceptable emission concentrations.

The initial approach used by the ERT is to estimate safe air concentrations using a method developed by Monsanto Corporation and modified slightly by EPA. We term the method, "Public Safety Factor" or PSF. The method consists of taking the American Conference of Governmental Industrial Hygienists (ACGIH) Threshold Limit Values (TLV's) for the workplace and adjusting them for a 24-hour, seven-day per week exposure period. To allow for the increased sensitivity of the general public as opposed to workers, for possible synergistic effects and for eliminated recovery (or purge) time, a safety factor of 1/100 is also applied. A small buffer is included to provide an early warning function. In short, acceptable air levels for longterm exposure may be estimated by dividing the ACGIH Time-Weighted Average criteria by 440.

This method is especially valid for gaseous emissions and respirable particulates. For larger particulates and certain skin active substances more latitude is warranted and extremely low permissible concentrations must be viewed cautiously. The particulate data calculated from the RAM studies is a case in point. The TLV for benzene soluble coal tar pitch volatiles or particulate polynuclear aromatic hydrocarbons (read "smoke") is 0.2 mg/m<sup>3</sup>. Applying the PSF method, yields an acceptable concentration of about 0.0004 mg/m<sup>3</sup>. However, the background levels observed at the control station ranged from 0.01 to 0.06 mg/m<sup>3</sup>. In such cases, it is more reliable to consider an incremental increase above background as an action level. In this case, we used a sustained particulate level of 0.1 mg/m<sup>3</sup> as cause for concern.

Except for direct exposure in the plume (Station No. 1), dispersion was generally sufficient to cause at least a tenfold dilution at the nearest downwind station (No. 5) even though the smoke was visibly present. Since the volatile organics of greatest concern, chloroform and benzene, were present at Station No. 1 at maximum concentrations of about 20 and 30 times their respective PSF limits, it is readily apparent that they would quickly diminish to acceptable levels a short distance downwind. Hence, it may be concluded that no widespread environmental problem can exist.

The localized problem is another matter. The volatile organics and soot as measured at the perimeter of the fire (Station No. 1), present levels which range from marginally hazardous to very hazardous in reference to accepted

TLV's. Working in the fire area itself (within the perimeter where there is less dilution) provides exposure opportunities well in excess of acceptable limits. Extreme health and safety measures are required to limit exposure in this area.

### 3.2 SURFACE WATER

Toxic substances in toxic amounts have migrated from the tire fire site into the Hogue Creek system. Water quality data of the State and EPA indicate emissions have been occurring since the fire began and will continue for an undetermined time into the future. Aside from the first slug of oil which escaped into the system, seepage and leachate into Massey Run and Hogue Creek persisted as of the last sampling date for which the ERT has reported data (i.e., December 19, 1983). The evidence indicates that toxic substances are being carried from the site in shallow groundwater which outcrops into Massey Run and into Hogue Creek via Massey Run and along the alluvial aquifer associated with it.

The available data indicate that ever since the surface flow of oil has been placed under control, pollutant loadings to Hogue Creek have been related to total stream flow, which is reflective of a system where contaminants are dissolved in shallow groundwater closely associated with an outcropping stream system, such as Massey Run. However, the toxic effects of the leachate appear to be confined to Massey Run under the current situation. Although toxic substances are reaching Hogue Creek, they do not appear to warrant extraordinary concern over environmental effects.

The first set of data received were the Microtox results from water and sediments sampled on November 18th. The data for those water samples, which yielded any significant toxicity, are shown graphically in Figures 5 and 6. The minimum dilution of the water samples was 45%, which means a significant toxic response must occur at about a 1:1 dilution before it may be detected by the unit. Moreover, samples which do not yield a toxic response in the test at the highest concentration (minimum dilution) might actually still have a toxic effect at full strength. However, no toxicity would be detected. This is but one of the reasons correlative chemical data is valuable in interpreting the results.

As shown in the figures, toxicity was evidenced in the lower containment pond and in Massey Run as far downstream as Hogue Creek. Below the confluence, toxicity of Hogue Creek water was reduced to non-detectable levels, although significant toxicity was still evidenced in the sediments immediately downstream. Samples from stations further downstream yielded no significant toxicities in either water or sediments.

Table 5 shows a summary of Microtox toxicity testing and selected chemical data for each water station sampled on November 18th. The Microtox results are expressed as percent waste eliciting EC<sub>50</sub> and EC<sub>20</sub> responses. An EC<sub>50</sub> is an "effect concentration" of sample resulting in a 50% light reduction and an

EC<sub>20</sub> is an "effect concentration" resulting in a 20% light reduction. These numbers are determined by interpolation, where possible, or extrapolation, where necessary, from the curves shown in Figure 5 and 6, using standard bioassay methods.

The summary (Table 5) includes chemical data for the significant contaminants likely to produce an acutely toxic effect on the Microtox organisms. These chemicals include phenol and total phenolics, caprolactam, cyanide (CN), and total organic carbon (TOC). Analysis of this table yields no striking results. While we can state in general that significant Microtox toxicities are associated with high concentrations of phenolics and caprolactam, the data cannot be used to prove cause and effect. If either of these chemical indicators were itself the causative agent, we would have observed more toxicity in the Hogue Creek samples (01830 and 01831) than in the tributary to the lower containment pond (01838). A scan of the raw data also shows no qualitative difference between samples 01838 and 01831. More than likely, the toxic effect is exerted synergistically, with contributory agents which were not quantified.

Evaluation of the chemical data taken by the State and EPA shows considerable time variability over the first month and a half since the fire began (See Table 2). However, a relationship to streamflow is also suggested. One possible relationship may be postulated by making a logical assumption that caprolactam loading on Hogue Creek is related to gaged stream flow. Since only a few real data points are available, no conclusions may be drawn, but the concept is useful for predicting future conditions. If the relationship continues to hold with additional sampling, we could make an estimate of the loading on Hogue Creek for the duration of the incident using State flow records. Using the data in Table 2 for November 29th and December 6th and 19th, a standard curve may be prepared for log-linear regression caprolactam loading (lbs/day) vs. gaged flow (cfs). Using the flow data for other sampling dates, we can calculate estimated loadings for each. The standard curve is shown in Figure 7. Using estimated loadings and measured flows, one may then estimate the caprolactam concentrations at the gaging station. Admittedly, the level of confidence is very low, but a rough indication is still useful.

### 3.3 GROUNDWATER

Preliminary Microtox data on the groundwater study program indicate that the deep aquifer has not been contaminated downgradient from the fire site. However, Microtox toxicity was evident in the water table aquifer downgradient.

On January 31, 1984, the two completed downgradient wells - TF2D and TF2S, and the partially completed upgradient well - TD1D, were sampled by ERT. ERT samples were to be analyzed for purgeable organics and Microtox toxicity. ERT also collected samples for the State WCB, which is to provide a more complete chemical analysis.

The Microtox data for the ERT samples was reported verbally on February 6, 1984. The deep well TF2D and the half-drilled well TF1D (depth at the time was 54 feet) yielded no detectable toxicity. The downgradient shallow well (TF2S) yielded the results which follow:

<u>Dilution</u>	<u>Normalized Percent Light Decrease</u>
5.65%	8.4%
11.3%	21.8%
22.5%	41.0%
45.0%	38.0%

The resulting curve is plotted in Figure 8. Interpolation yields an EC<sub>20</sub> of 10.3%, which corresponds to the results of the marginally contaminated sample from the westerly tributary to the lower containment pond. Compare the 12.0% light reduction for sample 01838.

Further discussion must wait until the chemical data is received from the State and EPA.

#### 4.0 CONCLUSIONS AND RECOMMENDATIONS

This chapter draws together the findings to date in the air, water, and groundwater studies to reach general conclusions as to the environmental impact of the present and projected situation at the Rhinehart site. It is not intended to assess environmental damage that may have occurred during the course of the incident.

##### 4.1 CONCLUSIONS

While emission of organic vapors from the fire did reach concentrations significant enough to require the use of personnel protection equipment, they did not reach concentrations which were considered hazardous beyond a short distance downwind of the source. Plume dispersion was adequate to ensure an effective exposure would not occur beyond the Rhinehart property.

Particulate emissions from the fire were severe, achieving levels of at least 40 mg/m<sup>3</sup> in the smoke at breathing height along the perimeter of the fire. This concentration is 200 times the recommended TLV for "smoke" and 400 times the level of concern established by CDC and ERT for particulates. Although good plume dispersion characteristics generally prevailed during the height of the incident, the decisions to provide smoke exposure warnings on and off-site were well justified.

The diminishing source strength of the fire is reducing the perimeter of the area of concern over human health from airborne contaminants but the exposure risk remains in the immediate vicinity of the fire.

Emissions of oil and water mixtures have contaminated the water and sediments of Massey Run. The toxicity effect, as measured by the Microtox, extends at least to the confluence with Hogue Creek. The chemical evidence does not conclusively link the Microtox results with a particular chemical substance. Rather, a combined effect of the materials present is indicated.

Residual contamination persists in Massey Run. It appears that the shallow groundwater table, the sediments, and the stream itself are interrelated and are serving as a reservoir and transport mechanism for contaminants which once flowed from or are leaching from the fire area. The total quantity of material present and its leaching rate cannot be determined at this time, hence the duration of the effect cannot be estimated.

There appears to be a relationship between organic loading (as measured by caprolactam loading) and streamflow in Hogue Creek. This relationship could indicate higher pollutant loading will occur at high streamflows. Spring flows could result in toxicity being manifested in Hogue Creek below the confluence.

The shallow groundwater downgradient from the fire site is contaminated to the extent that a Microtox response is elicited. However, the toxicity would be classified as moderate. Based on limited data, the deeper aquifer appears to be clean. Preliminary flow studies indicate that the shallow aquifer flows towards Massey Run via the Rhinehart Pond drainage system or by subsurface transport. The deep aquifer seems to flow in the same direction and may outcrop closer to Hogue Creek. Conclusions regarding the environmental impact on groundwater must be deferred until the groundwater studies are completed.

Overall, the environmental impact of the tire fire does not appear to be severe at this time. Long term impacts from air releases appear to be negligible. The immediate surface water impact from large releases of oil has passed and the potential for instantaneous large releases has diminished with reduced oil production in the fire. Outcropping of leachate into Massey Run and Hogue Creek is likely to occur for an undetermined time, but it appears that any major toxic effects will be confined to the Run and will not be widespread in Hogue Creek. Quantities of contaminants of non-detectable levels may reach the downstream water supply intakes until acclimated stream bacteria become more active in the warmer weather and biodegradation is enhanced. The groundwater contamination issue remains open at this time.

#### 4.2 RECOMMENDATIONS

Given the current site characteristics, there is no need for additional air monitoring. Should major changes occur in source strength or distribution, another air monitoring program may be needed.

Should mitigative action be taken at the site, an air monitoring program should be established as part of it.

Personnel safety requirements applied during the incident should continue to apply adjacent to the fire area.

Water quality monitoring should be continued on a bi-weekly to monthly basis at the WCB monitoring stations to establish a trend in contaminant loadings. We recommend that the State continue to monitor for caprolactam as well as for purgeable organics since caprolactam appears to be a useful indicator of loading rate.

Streamflow records appear to be an intergral part of determining the magnitude and duration of the environmental impact of the leachate. Hence, obtaining flow records for Hogue Creek and opportunistic flow measurements on both streams should be considered part of the surface water monitoring program.

We recommend the groundwater studies be carried to their conclusion and that the resulting report be appended to this environmental assessment by reference.

Attachments

### LIST OF FIGURES

- Figure 1 Portion of USGS 7 1/2 Minute Quadrangle, Hayfield, VA
- Figure 2 Air Monitoring Stations
- Figure 3 Virginia Water Control Board Water Quality Stations
- Figure 4 Environmental Response Team Water Quality Stations
- Figure 5 Microtox® Results for Massey Run - Upstream
- Figure 6 Microtox® Results for Massey Run - Downstream
- Figure 7 Caprolactam Loading at Gaging Station
- Figure 8 Microtox® Results for Well TF2S

### LIST OF TABLES

- Table 1 Air Monitoring Station Descriptions
- Table 2 Selected Water Quality and Flow Data
- Table 3 Environmental Response Team Water Quality Data
- Table 4 Microtox® Data for Massey Run
- Table 5 Summary of Microtox® and Selected Chemical Data

### LIST OF APPENDICES

- Appendix A Environmental Response Team Air Monitoring Report
- Appendix B Virginia Water Control Board Water Quality Data
- Appendix C Microtox® Analysis Report - Waters and Sediments of Massey Run and Hogue Creek
- Appendix D Groundwater Study Plan

FIGURE 1 - PORTION OF USGS 7 1/2  
MINUTE QUADRANGLE,  
HAYFIELD, VA

AR 160250



FIGURE 2 - AIR MONITORING STATIONS  
(Red)


# ERT AIR MONITORING EFFORTS RHINEHART TIRE FIRE (NOT TO SCALE)

GENERAL WIND DIRECTION



ORIGINAL  
(Red)


FIGURE 3 - VIRGINIA WATER CONTROL  
BOARD WATER QUALITY  
STATIONS



ARJ00252


ORIGINAL  
(Red)

FIGURE 4 - ENVIRONMENTAL RESPONSE  
TEAM WATER QUALITY  
STATIONS




AR100253

FIGURE 5 - MICROTOX® RESULTS FOR  
MASSEY RUN - UPSTREAM




ORIGINAL  
(Red)

FIGURE 6 - MICROTOX® RESULTS FOR  
MASSEY RUN - DOWNSTREAM




AR100254

FIGURE 7 - CAPROLACTAM LOADING AT  
GAGING STATION



AR100255

FIGURE 8 - MICROTOX® RESULTS FOR  
WELL TF2S



AR100256

### RHINEHART TIRE FIRE - TABLE 3

# ERT WATER QUALITY DATA SUMMARY - NOVEMBER 1983

SAMPLE TYPE		WATER						
ERT SAMPLE NUMBER		01838	NA	01833	01830	01831	Blank	
DESCRIPTION		Trib to Lower Pond	Rhine-hart's Pond	Mid-Massey's Run	Hogue Creek Upstream	Hogue Cr Down-stream	Bottled Water	
VOLATILE COMPOUNDS/ UNITS		ug/L						
Acrolein								
Acrylonitrile								
Benzene			757.	<10				
bis (Chloromethyl) ether								
Bromoform								
Carbon tetrachloride								
Chlorobenzene								
Chlorodibromomethane								
Chloroethane								
2-Chloroethyl vinyl ether								
Chloroform								
Dichlorobromomethane								
Dichlorodifluoromethane								
1,1-Dichloroethane								
1,2-Dichloroethane								
1,1-Dichloroethylene								
1,2-Dichloropropane								
1,3-Dichloropropylene								
Ethylbenzene			296.	17.				
Methyl bromide								
Methyl chloride								
Methylene chloride		<10	<100		<10	<10	<10	
1,1,2,2-Tetrachloroethane								
tetrachloroethylene								
Toluene			621.	<10				
1,2-Trans-dichloroethylene								
1,1,1-Trichloroethane				<10				
1,1,2-Trichloroethane								
Trichloroethylene								
Trichlorofluoromethane								
Vinyl chloride								
1,2,3-Trichloropropane								
Caprolactam		81.	294000.	8800.			127.	

[illegible]

**ORIGINAL**  
**(Red)**

AR100257



### CHINESE FIRE - TABLE 3

**ERT WATER QUALITY DATA SUMMARY - NOVEMBER 1983 (Cont.)**

SAMPLE TYPE		WATER					
ERT SAMPLE NUMBER		01838	NA	01833	01830	01831	Blank
DESCRIPTION		Trib to Lower Pond	Rhinehart's Pond	Mid-Massey's Run	Hogue Creek Upstream	Hogue Cr Downstream	Bottled Water
ACID COMPOUNDS/ UNITS		ug/L					
	2-Chlorophenol						
	2,4-Dichlorophenol						
	2,4-Dimethylphenol		<12500				
	4,6-Dinitro-o-cresol						
	2,4-Dinitrophenol						
	2-Nitrophenol			<25			
	4-Nitrophenol						
	p-Chloro-m-cresol						
	Pentachlorophenol						
	Phenol	<25	<12500	1150.			<25
	2,4,6-Trichlorophenol						
	Total Phenolics	<50	14000.	1800.	51.	<50	<50

[illegible]

AR100258

**ORIGINAL**  
(Ref)

ERT WATER QUALITY DATA SUMMARY - NOVEMBER 1983 (Cont.)

[illegible]

**ORIGINAL**  
**(Red)**

**RHINEHART TIRE FIRE - TABLE 3**

SAMPLE TYPE	ERT SAMPLE NUMBER	WATER					Blank
		01838	NA	01833	01830	01831	
DESCRIPTION		Trib to Lower Pond	Rhine-hart's Pond	Mid-Massey's Run	Hogue Creek Upstream	Hogue Cr Down-stream	Bottled Water
BASE NEUTRAL CMPS/ UNITS		ug/L					
Fluorene							
Hexachlorobutadiene							
Hexachlorocyclopentadiene							
Hexachloroethane							
Indeno (1,2,3-c,d)pyrene							
Isophorone			<100				
Naphthalene			328.				
Nitrobenzene							
N-Nitrosodimethylamine							
N-Nitrosodi-N-propylamine							
N-Nitrosodiphenylamine			239.				
Phenanthrene		<10	203.				
Pyrene			108.				
1,2,4-Trichlorobenzene							
2,3,7,8-TCDD							

[illegible]

**ORIGINAL**  
**(Red)**

AR100260

RHINEHART TIRE FIRE - TABLE 3  
ERT WATER QUALITY DATA SUMMARY - NOVEMBER 1983 (Concl.)

SAMPLE TYPE	WATER				
	01838	NA	01833	01830	01831
ERT SAMPLE NUMBER	Trib to Lower Pond	Rhinehart's Pond	Mid-Massey's Run	Hogue Creek Upstream	Blank
DESCRIPTION					
METALS, CYANIDE, etc./UNITS	ug/L				
Antimony		<70			
Arsenic		5.			
Beryllium					
Cadmium		13.			
Chromium		<9			
Copper		11.			
Lead		<60			
Mercury					
Nickel		90.			
Selenium					
Silver		<9			
Thallium					
Zinc		94000.			
Cyanide, Total	31.	2400.	214.	26.	28.
Oil & Grease					
Total Organic Carbon	3150.		197000.	3000.	7300.

SEDIMENT				
01838	01833	01830	01831	
Trib to Lower Pond	Mid-Massey's Run	Hogue Creek Upstream	Hogue Cr Down-stream	
mg/Kg				
		26.		
		1.6		
		0.7		
		28.		
		24.		
		31.		
		<0.1		
		46.		
		3.		
		<0.6		
		110.		
	<0.5	<0.5	<0.5	
	1100.	1200.	1600.	

AR100261

ORIGINAL  
(Red)

ORIGINAL  
(Red)

FILE: DX080/GRAPHICS/RHMI..4

TABLE 4 - MICROTOX® DATA FOR  
MASSEY RUN

RHINEHART MICROTOX DATA 01838

2	.1700e+01	.5650e+01
2	.1070e+02	.1130e+02
2	.1900e+02	.2250e+02
2	.3450e+02	.4500e+02

9

RHINEHART MICROTOX DATA 01839

2	.2260e+02	.5650e+01
2	.3210e+02	.1130e+02
2	.5000e+02	.2250e+02
2	.6320e+02	.4500e+02

9

RHINEHART MICROTOX DATA 01835

2	.2200e+02	.5650e+01
2	.3560e+02	.1130e+02
2	.5360e+02	.2250e+02
2	.6900e+02	.4550e+02

9

RHINEHART MICROTOX DATA 01834

2	.2630e+02	.5650e+01
2	.3930e+02	.1130e+02
2	.5580e+02	.2250e+02
2	.7550e+02	.4500e+02

9

RHINEHART MICROTOX DATA 01833

2	.2600e+02	.5650e+01
2	.3800e+02	.1130e+02
2	.5400e+02	.2250e+02
2	.6800e+02	.4500e+02

9

RHINEHART MICROTOX DATA 01832

2	.1090e+02	.5650e+01
2	.1900e+02	.1130e+02
2	.3010e+02	.2250e+02
2	.4680e+02	.4500e+02

9

ARI00262

## RHINEHART TIRE FIRE - TABLE 5

## SUMMARY OF MICROTOX® AND SELECTED CHEMICAL DATA - NOVEMBER 1983

SAMPLE NUMBER	STATION DESCRIPTION	MICROTOX NPLD (%)		CHEMICAL RESULTS (ug/L)				
		EC20	EC50	PHENOL/PHENOLICS	CAPROLACTAM	CYANIDE	TOC	
01838	T-05 TRIB. TO LOWER CONTAINMENT POND	24	91 ext.	<25/<50	81	31	3,150	
01839	T-06 LOWER CONTAIN- MENT POND	5 ext.	23					
01835	T-04 MASSEY RUN JUST BELOW CONTAINMENT POND	5 ext.	20					
01834	T-03 MASSEY RUN AT OIL SPILL POOL LIMIT	4 ext.	18					
01833	T-02 MID-MASSEY RUN AT VAMCB STATION 01	4 ext.	19	1150/1800	8,800	214	197,000	
01832	T-01 SURFACE POOL ON LOWER MASSEY RUN	12	51 ext.					
01830	H-01 HOGUE CR. CONTROL ABOVE VAMCB STA. 03A	ND	ND	ND/51	ND	26	3,000	
01831	H-02 HOGUE CR. DOWN- STREAM AT VAMCB STA 02	ND	ND	ND/<50	127	28	7,300	
01836	H-03 HOGUE CR. DOWN- STREAM	ND	ND					
01837	H-04 HOGUE CR. GAGING STATION VAMCB STA. 02A	ND	ND					

NOTES: NPLD = Normalized percent light decrease.

ext. = extrapolated value. Minimum and maximum concentrations tested are 5.25% and 45%, respectively.

AR100263

AIR MONITORING REPORT

RHINEHART TIRE FIRE  
Winchester, Virginia

NOVEMBER 3 to NOVEMBER 30, 1983



ENVIRONMENTAL RESPONSE TEAM  
Woodbridge Avenue, Edison, New Jersey

AR100264

ORIGINAL  
(Red)

UNITED STATES GOVERNMENT

# memorandum

DATE: January 30, 1984

REPLY TO  
ATTN OF: Rodney D. Turpin *Rodney D. Turpin*  
Safety and Occupational Health Manager

SUBJECT: ERT Air Monitoring Efforts at the Rhinehart Tire Fire, Winchester, VA

TO: Thomas Massey, Senior On-Scene Coordinator  
EPA, Region III

THRU: Joseph P. Laforanara, Chief *J. Allen for JPL*  
Analytical Support Section

## ACTIONS TAKEN

An air sampling program was developed and implemented on November 3, 1983, following all five steps of the ERT Air Monitoring Guides. The ERT air monitoring efforts covered a period from November 3, 1983 to November 30, 1983. In addition to the standard collection media, samples were collected using the ERT 2-Stage Tenax/Chromosorb 102 thermal desorption tube. A total of 74 samples were collected for analysis. Our program consisted of:

- A. Modifying NIOSH P&CAM methods 127 and 168, respectfully, to scan for organic vapors and aromatic amines.
- B. Following the ERT 2-Stage Tenax/Chromosorb 102 collection tube procedures. Analyses were performed on a GC/MS utilizing thermal desorption extraction methods.
- C. Collecting particulate filter cassettes for both organic and inorganic analysis.
- D. Surveying the site with portable field instruments. Instruments used for this survey were the photoionization detector (PID), organic vapor analyzer (OVA's) and a Real-Time Aerosol Monitor (RAM-1).
- E. Collecting thermal desorption tubes for on-site OVA FID/GC analysis.
- F. In addition to monitoring the plume under normal burning conditions, the fire was also monitored during phases of the spraying operation.
- G. Off-site grab sampling for particulates using the RAM-1.

OPTIONAL FORM NO. 10  
(REV. 1-80)  
GSA FPMR (41 CFR) 101-11.6  
5010-114

AR100265



The sampling scheme consisted of one background station, two off-site downwind stations, 6 on-site stations, and several off-site grab samples with the RAM-1. The following is a breakdown of the type of samples:

1. NIOSH P&CAM - 168 (Aromatic Amines) 3-stage silica gel tubes: 11 samples.
2. NIOSH P&CAM - 127 (Organic Vapor Scan) 150 mg carbon tubes: 5 samples; 600 mg carbon tubes: 15 samples.
3. ERT 2-stage tubes (Organic Vapors) Tenax/Chromosorb 102 collection tubes: 23 samples.
4. OVA FID/GC thermal desorption collection tubes: 6 samples.
5. Particulate cassette analyzer for organic/inorganic contaminants: 14 samples.

## RESULTS

See Attachment No. 1 for a summary sheet of sample numbers, volumes, and stations. Attachment No. 2 locates the sample stations. The following is a summary of the results of the actions taken:

- A. The following are highlights of the P&CAM 168 aromatic amines samples (See Attachment No. 3 for data summary and detection limits):
  1. Sample No. 882/38 collected from Station No. 1 on 11/04/83 was found to have an unknown peak. A gas chromatograph/mass spectrometer (GC/MS) analysis identified it as 0.03 ppm Naphthalene.
  2. Sample No. 868/9 (Station No. 1, 11/22/83) and 886/16 (Station No. 1, 11/22/83) were found to contain 0.044 ppm and 0.067 ppm of Aniline, respectively.
  3. Sample No. 868/9 (Station No. 1, 11/22/83) and 886/16 were found to contain 0.0092 ppm and 0.014 ppm of p-Nitroaniline.
  4. Sample No. 868/9 (Station No. 1, 11/22/83) and 886/16 were found to contain 0.007 ppm and 0.018 ppm of p-Ansidine.
- B. The following are highlights of the particulate, mixed cellulose ester filter (MCEF) cassette samples. Some filters were digested with Nitric Acid and particulates were dissolved in the same acid. The resulting solution was diluted to a 50 milliliter volume with 5% HNO<sub>3</sub> in distilled water and analyzed by atomic absorption for inorganic contents. Other filters were extracted with Carbon Disulfide and the resulting extracts were injected in gas chromatographs to evaluate organic content. See Attachment No. 4 for data summary and detection limits.

1. The 7 particulate samples collected for organic analysis did not identify any concentration above the GC detection limit.
  2. Sample No. 889/15 (Station No. 1, 11/22/83) identified 0.001 mg/m<sup>3</sup> Arsenic, 1.532 mg/m<sup>3</sup> Zinc, and 0.006 mg/m<sup>3</sup> Copper.
  3. Sample No. 861/18 (Station 6, 11/22/83) identified 0.007 mg/m<sup>3</sup> Zinc.
  4. Sample No. 865/21 (Station 3, 11/22/83), background identified 0.054 mg/m<sup>3</sup> Zinc.
  5. Sample No. 888/36 (Station No. 5, 11/04/83) identified 0.003 ug/l of Zinc; 0.051 ug/l Tellurium and 0.021 ug/l of Arsenic.
- C. The following are the highlights P&CAM 127 method organic vapor analysis (See Attachment No. 5 for data summary and detection limits):

CHEMICAL	SAMPLE No./DATE	STATION	CONCENTRATION (ppm)
Acetone	892/29 (11/04/83)	No. 1	0.05
	888/17 (11/22/83)	1	0.09
Methylene Chloride	892/29 (11/04/83)	1	0.24
	883/0 (11/30/83)	1	0.10
	885/0 (11/30/83)	1	0.16
	874/0 (11/30/83)	1	0.10
	867/0 (11/30/83)	1	0.06
	887/7 (11/22/83)	1	0.05
	888/17 (11/22/83)	1	0.12
Chloroform	892/29 (11/04/83)	1	0.23
	858/27 (11/04/83)	5	0.08
	893/26 (11/04/83)	4	0.08
	883/0 (11/30/83)	1	0.29
	885/0 (11/30/83)	1	0.47
	874/0 (11/30/83)	1	0.47
	867/0 (11/30/83)	1	0.20
	887/7 (11/22/83)	1	0.04
	888/17 (11/22/83)	1	0.11

CHEMICAL	SAMPLE No./DATE	STATION	CONCENTRATION (ppm)
Ethylene Dichloride	892/29 (11/04/83)	No. 1	0.05
	883/0 (11/30/83)	1	0.05
	885/0 (11/30/83)	1	0.08
	874/0 (11/30/83)	1	0.08
	867/0 (11/30/83)	1	0.04
	888/17 (11/22/83)	1	0.02
	887/7 (11/22/83)	1	0.01
Benzene	892/29 (11/04/83)	1	0.74
	858/27 (11/04/83)	5	0.01
	893/26 (11/04/83)	4	0.01
	883/0 (11/30/83)	1	0.62
	885/0 (11/30/83)	1	0.69
	874/0 (11/30/83)	1	0.66
	867/0 (11/30/83)	1	0.50
	887/7 (11/22/83)	1	0.40
	888/17 (11/22/83)	1	0.49
Methyl Ethyl Ketone	892/29 (11/04/83)	1	0.08
	883/0 (11/30/83)	1	0.06
	885/0 (11/30/83)	1	0.09
	874/0 (11/30/83)	1	0.09
	874/0 (11/30/83)	1	0.04
	888/17 (11/22/83)	1	0.02
1,1,1-Trichloroethane	892/29 (11/04/83)	1	0.05
Toluene	892/29 (11/04/83)	1	0.28
	858/27 (11/04/83)	5	0.01
	893/26 (11/04/83)	4	0.003
	883/0 (11/30/83)	1	0.34
	254/0 (11/30/83)	7	0.002
	885/0 (11/30/83)	1	0.37
	874/0 (11/30/83)	1	0.37
	867/0 (11/30/83)	1	0.33
	252/0 (11/30/83)	7	0.003
Xylenes	892/29 (11/04/83)	1	0.18
	858/27 (11/04/83)	5	0.004
	883/0 (11/30/83)	1	0.28
	885/0 (11/30/83)	1	0.30
	874/0 (11/30/83)	1	0.33
	867/0 (11/30/83)	1	0.27

CHEMICAL	SAMPLE No./DATE	STATION	CONCENTRATION (ppm)
Trichloroethylene	892/29 (11/04/83)	No. 1	0.08
	883/0 (11/30/83)	1	0.09
	885/5 (11/30/83)	1	0.12
	874/0 (11/30/83)	1	0.11
	867/0 (11/30/83)	1	0.16
	887/7 (11/22/83)	1	0.18
	888/17 (11/22/83)	1	0.29
Styrene	892/29 (11/04/83)	1	0.03
1,1,2-Trichloroethane	892/29 (11/04/83)	1	0.04
	883/0 (11/30/83)	1	0.06
	885/0 (11/30/83)	1	0.07
	874/0 (11/30/83)	1	0.10
	867/0 (11/30/83)	1	0.07
	887/7 (11/22/83)	1	0.01
	888/17 (11/22/83)	1	0.04
Total Hydrocarbons measured as Toluene	892/29 (11/04/83)	1	0.88
	858/27 (11/04/83)	5	0.01
Mineral Spirits	883/0 (11/30/83)	1	0.55
	885/0 (11/30/83)	1	0.59
	874/0 (11/30/83)	1	0.65
	867/0 (11/30/83)	1	0.50
	887/7 (11/22/83)	1	0.10
	888/17 (11/22/83)	1	0.31

2. The following is a summary of those samples which exceeded the Public Safety Factor (PSF):

COMPOUND	STATION No./DATE	TLV (ppm)	PSF (ppm)	CONCENTRATION (ppm)
1,1,2-Trichloroethane	No. 1 (11/04/83)	10	0.023	0.04
	1 (11/22/83)	10	0.023	0.04
	1 (11/30/83)	10	0.023	0.07
	1 (11/30/83)	10	0.023	0.10
	1 (11/30/83)	10	0.023	0.06

COMPOUND	STATION No./DATE	TLV (ppm)	PSF (ppm)	CONCENTRATION (ppm)
Ethylene Dichloride	No. 1 (11/04/83)	10	0.023	0.05
	1 (11/30/83)	10	0.023	0.04
	1 (11/30/83)	10	0.023	0.08
	1 (11/30/83)	10	0.023	0.08
	1 (11/30/83)	10	0.023	0.05
Xylenes	1 (11/30/83)	100	0.227	0.28
	1 (11/30/83)	100	0.227	0.30
	1 (11/30/83)	100	0.227	0.33
	1 (11/30/83)	100	0.227	0.27
Trichloroethylene	1 (11/22/83)	50	0.114	0.29
	1 (11/22/83)	50	0.114	0.18
	1 (11/30/83)	50	0.114	0.16
	1 (11/30/83)	50	0.114	0.12
Toluene	1 (11/04/83)	100	0.227	0.28
	1 (11/30/83)	100	0.227	0.33
	1 (11/30/83)	100	0.227	0.37
	1 (11/30/83)	100	0.227	0.34
	5 (11/30/83)	100	0.227	0.37
Methylene Chloride	1 (11/04/83)	100	0.227	0.24
Chloroform	1 (11/04/83)	10	0.023	0.23
	5 (11/04/83)	10	0.023	0.08
	4 (11/04/83)	10	0.023	0.08
	1 (11/22/83)	10	0.023	0.11
	1 (11/22/83)	10	0.023	0.04
	1 (11/30/83)	10	0.023	0.20
	1 (11/30/83)	10	0.023	0.47
	1 (11/30/83)	10	0.023	0.47
	1 (11/30/83)	10	0.023	0.29
Benzene	1 (11/04/83)	10	0.023	0.74
	1 (11/22/83)	10	0.023	0.49
	1 (11/22/83)	10	0.023	0.40
	1 (11/30/83)	10	0.023	0.50
	1 (11/30/83)	10	0.023	0.66
	1 (11/30/83)	10	0.023	0.69
	1 (11/30/83)	10	0.023	0.62

- D. The following are highlights of the ERT 2-stage Tenax/Chromosorb 102 data. (See Attachment No. 6 for data summary and detection limits). Those collected on 11/03/83 revealed the following low levels:

1. Background samples: - The 11/04/83 background samples did not identify any significant compounds after correction for the blank.

Benzene	<0.02
Possible Hydrocarbon	<0.03
Unknown	<0.03
Hydrocarbon	<0.03

The 11/22/83 background samples revealed the following compounds:

Nonanal	0.002
Decanal	<0.002
Possible Lauric Acid	0.002
Myristic Acid	0.002
Possible Palmitic Acid	<0.0009
Benzaldehyde	0.006
E <sub>10</sub> H <sub>14</sub> Alkylbenzene	<0.004
Styrene	<0.005
Acetophene	<0.004
Ethylstyrene	<0.004
Unsaturated Hydrocarbon	<0.003
Hydrocarbon and Unknown	<0.002
Unknown	0.007
Unknown	0.01
Unknown	0.04
Acetic Acid	0.016

2. While the number of compounds identified is too large to summarize, the concentrations ranged from <0.001 ppm for Ethylbenzene, Xylene, Styrene (Sample No. A21, 11/04/83) to 1 ppm for Benzene (Sample No. K/18, 11/04/83 and Sample No. F/13, 11/22/83) and Toluene (Sample No. F/13, 11/22/83).
3. Station No. 1 samples were consistently positive while the other samples did not identify any significant concentrations with the following exceptions:
- a. Station No. 4, sample R/20, 11/04/83 identified 18 compounds ranging in concentration from 0.004 ppm for Trimethyl phenyl indane to 0.26 ppm for Benzene.

- b. Station No. 5, sample A/21, 11/04/83 identified 9 compounds ranging in concentrations from <0.0009 ppm for Naphthalene to 0.006 ppm for Toluene.
- c. Station No. 5, sample I/25, 11/04/83 identified 5 compounds ranging in concentrations from <0.2 ppm for Trichlorofluoromethane, Ethylbenzene and Xylene to 0.4 ppm for Benzene.
- d. Station No. 6 (Decon), sample J/12, 11/22/83 identified 9 compounds ranging in concentrations from 0.004 ppm for an Unknown to 0.01 ppm for an Unknown and Acetic Acid.
- E. Attachment No. 7 is the result of the organic vapor analysis (FID/GC) from the thermal desorption collection tubes on-site. The following is a summary of this data:
1. Station No. 1 results revealed 12 GC peaks for 11/03/83 and 10 GC peaks for 11/04/83.
  2. Station No. 4 results revealed 2 GC peaks for 11/03/83 and 4 GC peaks for 11/04/83.
  3. Station No. 3 (background) results revealed 1 GC peak for 11/03/83 while Station No. 5 results revealed 5 GC peaks for 11/04/83.
- F. On-Site grab samples with the Real-Time Aerosil Monitor (RAM-1) revealed the following:
1. 11/03/83 - Station No. 1 (a.m.) 22.0 mg/m<sup>3</sup>  
- Rhinehart House (a.m.) 0.03 mg/m<sup>3</sup>
  2. 11/04/83 - Station No. 1 (a.m.) 34.6 mg/m<sup>3</sup>  
- Station No. 5 (a.m.) 19.0 mg/m<sup>3</sup>
  3. 11/22/83 - Station No. 1 (2 p.m.) 40 mg/m<sup>3</sup>  
- Station No. 3 (2 p.m.) 0.010 mg/m<sup>3</sup> (Background)  
- Station No. 4 (2 p.m.) 0.038 mg/m<sup>3</sup>  
- Station No. 5 (2 p.m.) 1.40 mg/m<sup>3</sup>  
- Station No. 6 (2 p.m.) 0.014 mg/m<sup>3</sup>  
- Station No. 7 (2 p.m.) 0.014 mg/m<sup>3</sup>
  4. 11/22/83 - Station No. 3 (10 p.m.) 0.060 mg/m<sup>3</sup> (Background)  
- Station No. 4 (10 p.m.) 0.06 mg/m<sup>3</sup>  
- Station No. 5 (10 p.m.) 0.06 mg/m<sup>3</sup>  
- Station No. 7 (10 p.m.) 0.045 mg/m<sup>3</sup>

5.	11/23/83	- Station No. 3	(2 a.m.)	0.015	mg/m <sup>3</sup>	(Background)
		- Station No. 4	(2 a.m.)	0.024	mg/m <sup>3</sup>	
		- Station No. 5	(2 a.m.)	0.026	mg/m <sup>3</sup>	
		- Station No. 7	(2 a.m.)	0.026	mg/m <sup>3</sup>	
6.	11/23/83	- Station No. 3	(6:30 a.m.)	0.050	mg/m <sup>3</sup>	(Background)
		- Station No. 4	(6:30 a.m.)	0.028	mg/m <sup>3</sup>	
		- Station No. 5	(6:30 a.m.)	0.090	mg/m <sup>3</sup>	
		- Station No. 6	(6:30 a.m.)	0.040	mg/m <sup>3</sup>	
		- Station No. 7	(6:30 a.m.)	0.130	mg/m <sup>3</sup>	

G. Off-Site grab samples with the RAM-1 revealed the following:

1. On 11/03/83 Rt. 608 downwind of sites ranged from 0.04 mg/m<sup>3</sup> to 0.07 mg/m<sup>3</sup> with the exception of a grab sample collected at the Raymond A. Carter residence which was 0.233 mg/m<sup>3</sup>.
2. 11/30/83 - Station No. 1 Off: - 0.19 mg/m<sup>3</sup>  
- Station No. 2 Off: - 0.20 mg/m<sup>3</sup>

CONCLUSIONS

An important factor to consider in reviewing this data is that the ERT air monitoring guides are designed to give a broad spectrum of possible air contaminants. While the type of collection media, flow rates, humidity, ambient temperatures, etc. all have some effect on the reported concentrations, it is correct to say that the amounts reported are the minimum amounts present during the sampling period. This is especially true with the ERT 2-stage Tenax/Chromosorb 102 tube. This tube has only been used at a few sites and we are still experimenting with the sample rates and volumes.

While the concentrations reported by the ERT 2-stage tube are relatively low when compared to the NIOSH P&CAM samples collected at the same stations, the number of compounds identified is considerably greater. This indicates there are possibly some unidentified concentrations of compounds present that are not collected/desorbed from the P&CAM methods or their concentrations are below the P&CAM detection limits.

On 11/03/83 and 11/04/83, ERT recommended to the on-scene coordinator and CDC that an Air Pollution Alert be released advising those with respiratory problems to keep all windows closed and avoid being outside under the plume. This recommendation was based on the data furnished by the field instruments (Real-Time Aerosol Monitor, RAM-1, and Organic Vapor Analyzer, OVA (FID/GC) as well as on-site observations of plume behavior. All off-site data generated by the various collection media and techniques were immediately reported (verbal) to the EPA Region III, TAT, at the command post. Either Region III, TAT, or ERT relayed this information to CDC. ERT was in agreement with the CDC Air Pollution Alert notice.



The conclusions are based on the data collected during the sampling period and potential contamination. If site conditions differ from the sampling period, additional sampling is recommended.

When applicable, we use an estimated health alert concentration, which we term the "Public Safety Factor" (PSF) to assist in the evaluation of the air data. While the Public Safety Factor is not a safe/non-safe designation for a specific concentration, it is an action level used by ERT during chemical spill, fires, explosion responses, etc. to alert those professionals whose responsibility it is to make occupational health and safety, as well as public health/ environmental effects decisions from air data. The Public Safety Factor is the American Conference of Governmental Industrial Hygienist TLV's expanded to include a 24 hour exposure condition while providing a safety factor. PSF is calculated by dividing the TLV by 440.

**A. P&CAM 168 AROMATIC AMINES:**

1. Of the two days (11/04/83 and 11/22/83) samples were collected and analyzed for aromatic amines only the 11/22/83 sample results indicated a positive finding. None of the samples indicated a level at or near the TLV and/or PEL (OSHA's Permissible Exposure Level). Three of the four positive samples did exceed the Public Safety Factor; however, the positive results were found only in the plume.

Three of the aromatic amines Public Safety Factors are based on TLV's with a skin notation. In evaluating the extent of potential hazard, one must consider potential route(s) of exposure. The data indicated that the aromatic amines were collected only at Station No. 1, which was directly inside the plume, and only on 11/22/83. Since the most logical route of exposure is direct contact with the plume, and since a 100-fold dilution is normally achieved a short distance away, it was concluded that the aromatic amines present did not present a grave health risk to the surrounding public or the environment. However, if site conditions vary significantly from the period sampled further evaluation is recommended. In addition, the fact that aromatic amines are present should be evaluated as a potential for exposure from the Occupational Health and Safety prospective.

**B. ORGANIC/INORGANIC PARTICULATES:**

1. Organics - Since standard sampling/analysis procedures are not published for organic particulates, the sampling method was adapted by modifying P&CAM 127 collection and extraction techniques. Of the 7 particulate samples which were collected for organic analysis, two were collected within the plume (Station No. 1) and 2 were collected off-site. None of the samples revealed organics above the GC detection limit. Thus, it is reasonable to conclude

that the plume particulates did not contain high concentrations of organics. The data indicates that particulate fall-out should not have an adverse environmental effect.

2. Inorganics - The inorganic particulate samples revealed the presence of some inorganics at Station No. 1, 6, 3, and 5. The concentrations found at these sampling points were well below the TLV or PEL, and should not pose environmental problems.

C. P&CAM 127 ORGANIC VAPORS:

1. With the exceptions of Stations No. 4 and 5 on 11/04/83, Stations No. 5 and 7 on 11/30/83, and Station No. 1 on 11/04, 11/22, and 11/30/83, the other stations did not detect organic vapors above the GC detection limit. If a peak had been observed other than one of the standards identified in P&CAM 127 and was of sufficient concentration, it would have been analyzed by GC/MS. However, if the peak concentration was not sufficient for GC/MS analyses, the total number of unknown peaks would be added and a total hydrocarbon concentration quantified as if it was Toluene.
2. Of the 14 organic identified by this method, 2 do not have TLV information available (mineral spirits and total hydrocarbons measured as Toluene). Of the 12 organic identified with TLV's 4 compounds did not exceed the Public Safety Factor (Acetone, 1,1,1-Trichloroethane, Methyl Ethyl Ketone, Styrene) while the remaining 8 compounds (See Results section, paragraph (c)(2)) exceeded the Public Safety Factor during at least one sampling period.

With the exception of Station No. 5 on 11/04/83 (Chloroform 0.08 ppm), and Station No. 4 on 11/04/83 (Chloroform 0.08 ppm), all the other concentrations which exceeded the Public Safety Factor were found at Station No. 1 (plume sample) during the sampling period.

Since the data showed that the worst-case condition occurs only in the plume and that concentrations exceed the Public Safety Factor action levels by factors generally less than tenfold, it is reasonable to conclude that downwind dilution would mitigate any adverse effects within a short distance. Although the 11/04/83 data was not available when ERT recommended an air pollution alert based on the RAM-1, field FID/GC, and observation, some data was available on 11/09/83 and this confirmed our field readings.

D. ERT 2-STAGE TENAX/CHROMOSORB 102 DATA:

While the ERT 2-stage Tenax/Chromosorb 102 collection tube is still undergoing field evaluation, its objective is to furnish a

convenient screening medium for air samples where multiple contaminants might be present. Also, it provides a rapid analytical turn around time. Since compounds are collected in both stages of the collection tube, it is not possible to determine the amount of break-through. Therefore, the data reported is the minimum concentration of the contaminant.

Of the 14 organics identified by the P&CAM 127 method, the ERT 2-stage collection tube identified 5 of those compounds. While the concentrations are not in total agreement, the following shows their relationship:

COMPOUND	DATE/STATION NO.	ERT 2-STAGE (ppm)	P&CAM 127 (ppm)
Methylene Chloride	11/04/83 No. 1	----	0.24
	11/04/83 4	0.08	----
Toluene	11/04/83 1	0.27	0.28
	11/04/83 1	0.20	----
	11/04/83 4	0.03	0.003
	11/22/83 1	1.00	----
	11/22/83 1	0.02	----
	11/03/83 1	0.12	not collected
Benzene	11/03/83 1	0.14	not collected
	11/04/83 1	1.20	0.74
	11/22/83 1	0.40	0.40
	11/22/83 1	0.10	----
	11/22/83 1	1.00	0.49
	11/04/83 4	0.26	0.01
Styrene	11/03/83 1	0.07	not collected
	11/04/83 1	0.08	0.03
	11/22/83 1	0.04	----
	11/22/83 1	0.20	----
	11/22/83 1	0.04	----
	11/04/83 4	0.06	----
Xylenes	11/03/83 1	0.06	not collected
	11/04/83 1	0.08	0.18
	11/22/83 1	0.05	----
	11/22/83 1	0.04	----
	11/22/83 1	0.20	----
	11/04/83 4	0.01	----

RHINEHART TIRE FIRE - 11/03/83 thru 11/30/83

Station #	ERT 2-Stage Sample # (Vol. in liter)	MCEF 0.45 u Sample # (Vol. in liter)	600 mg Carbon Sample # (Vol. in liter)	3 Stage Silica Sample # (Vol. in liter)	Carbon/Tenax Thermal Desorption Tubes (Vol. in liter)
11/03/83	J/1 (6.16)	848/11 (552)			897/14 (64.35)
1	A/5 (11.66)				
2	All Pumps and Samples were destroyed in fire.....				
3- (Background)	F/4 (4.36) C/7 (10.71)	888/13 (588.8)			894/15 (83)
4	E/3 (2.69)* R/8 (7.14)*	889/10 (307.5)			865/16 (67.7)
<hr/>					
11/04/83					
1	K/18 (10.33) J/22 (4.99)	889/31 (414)	892/29 (360)	882/38 (163.6)	866/42 (22.96)
3- (Background)	C/19 (9.16) F/23 (3.59)	890/35 (414)	864/28 (360)	857/37 (360)	
4	R/20 (9.38) E/24 (13.55)	887/30 (414)	893/26 (360)**	881/40 (360)	886/41 (72)
5	A/21 (41.49) I/25 (4.11)	888/36 (414)	858/27 (360)	878/39 (360)	865/43 (90)
1 off		848/32 (395.4)	893/47 (344.6)	857/52 (347)	
2 off		890/44 (319.6)	864/48 (318.4)	878/51 (320)	

TABLE 1 - AIR MONITORING STATION  
DESCRIPTIONS  
ORIGINAL  
(Red)

ARI00277

Station #	ERT 2-Stage Sample # (Vol. in liter)	MCEF 0.45 u Sample # (Vol. in liter)	600 mg Carbon Sample # (Vol. in liter)	3 Stage Silica Sample # (Vol. in liter)	Carbon/Tenax Thermal Desorption Tubes (Vol. in liter)
11/22/83					
1 (am)	A/1 (9.02) E/4 (4.04)	865/6 (348)	887/7 (360)	868/9 (270)	
1 (pm)	F/13 (4.8) B/14 (8.79)	889/15 (360)	888/17 (360)	886/16 (270)	
3 (am) (Background)	R/2 (10.14) J/3 (5.00)	889/5 (360)	888/8 (360)	886/10 (303.8) 886/20 (270)	
3 (pm) (Background)	A/19 (14.92)	865/21 (360)	887/22 (360)	868/9 (270)	
6 (pm) (Decon)	R/11 (11.02) J/12 (5.52)	861/18 (421.2)			
<hr/>					
Station #	150 mg Carbon Sample # (Vol. in liter)	MCEF 0.45 u Sample # (Vol. in liter)	600 mg Carbon Sample # (Vol. in liter)	3 Stage Silica Sample # (Vol. in liter)	Carbon/Tenax Thermal Desorption Tubes (Vol. in liter)
11/30/83					
1	874/0 (44.25) 867/0 (88.5)		885/0 ( 88.5) 883/0 (177.4)		
6(Decon)	225/0 (85.5)		253/0 (171.2)		
7	252/0 (88.7)		254/0 (177.6)		
3 (Background)	856/0 (78.4)		251/0 (157.4)		

\*Samples E/3 and R/8 on 11/3/83 were both identified as R/8

\*\*893/26 marked 897/33

AR100278

ORIGINAL  
(Red)RHINEHART TIRE FIRE - TABLE 2  
SELECTED WATER QUALITY AND FLOW DATA

STATION DESCRIPTION /SAMPLED BY	HOGUE CREEK CTRL/WCB	HOGUE CR CTRL/ ERT/WCB	RHINE- HART PND WATER	MASSEY RUN WAT/ ERT/WCB	LOWER MASSEY RUN/WCB	HOGUE CR DOWN- STREAM	HOGUE CR GAGING STATION	HOGUE CR GAGING FLOW
STATION NUMBER - ERT	NA	H-01	NA	T-02	ST-01	H-02	H-04	H-04
STATION NUMBER - WCB	03	03A	R.P.	01	04<->01	02	02A	02A
SAMPLING DATE 11/03/83	UNITS ug/L							2.8 CF
Benzene	0.3			0.9	1.3	0.5		
Toluene	<0.2			1.7	2.3	<0.2		
Ethylbenzene	0.8			4.6	1.2	<0.2		
Xylenes	<0.2			2.4	0.6	<0.2		
Caprolactam	140.			13000.	4800.	210.		
SAMPLING DATE 11/10/83	UNITS ug/L (04 MIX)							10.8 CF
Benzene		<0.2		1.5		0.3		
Toluene		<0.2		3.3		0.3		
Ethylbenzene		<0.2		9.1		0.2		
Xylenes		<0.2		7.6		0.3		
Caprolactam	140.	<1.		8500.	9000.	1600.		
SAMPLING DATE 11/16/83	UNITS ug/L							9.7 CF
Benzene				1.1		<0.2	<0.2	
Toluene				7.2		0.2	<0.2	
Ethylbenzene				13.4		0.2	<0.2	
Xylenes				26.9		0.5	<0.2	
Caprolactam								
SAMPLING DATE 11/17/83	UNITS ug/L							6.83 CF
Benzene				2.0		<0.2	<0.2	
Toluene				5.1		<0.2	<0.2	
Ethylbenzene				6.0		0.8	<0.2	
Xylenes				18.1		<0.2	<0.2	
Caprolactam								
SAMPLING DATE 11/18/83	UNITS ug/L							15.0 CF
Benzene				<10./0.5		/ 0.2	<0.2	
Toluene				<10./1.1		/ <0.2	<0.2	
Ethylbenzene				17./3.5		/ <0.2	<0.2	
Xylenes				3.3		/ <0.2	<0.2	
Caprolactam				8800./		127./		
SAMPLING DATE 11/29/83	UNITS ug/L (12/2/83)							15.0 CF
Benzene			757.	5.1		<0.2	0.2	
Toluene			621.	10.9		0.3	<0.2	
Ethylbenzene			296.	1.9		1.0	1.7	
Xylenes				5.9		<0.2	<0.2	
Caprolactam			294000.	12900.		110.	84.	
SAMPLING DATE 12/06/83	UNITS ug/L							40.0 CF
Benzene			141.	4.7		0.5	1.1	
Toluene			171.	9.4		0.7	<0.2	
Ethylbenzene			112.	7.6		0.5	<0.2	
Xylenes			88.	7.1		0.4	<0.2	
Caprolactam			66000.	11000.		340.	210.	
SAMPLING DATE 12/19/83	UNITS ug/L							15.6 CF
Benzene				0.5		0.2	<0.2	
Toluene				1.1		<0.2	<0.2	
Ethylbenzene				3.5		<0.2	<0.2	
Xylenes				3.3		<0.2	<0.2	
Caprolactam				9700.			44.	

AR100279

This information was not available when ERT recommended that the CDC declare an Air Pollution Alert based on the field direct reading instruments and visual observations (see below). The ERT 2-stage tube data confirmed this action after the fact.

E. ON-SITE THERMAL DESORPTION AND FIELD OVA GC/FID RESULTS:

The data collected with this field instrument on 11/03/83 and 11/04/83, indicated the presence of airborne contaminants above background levels at Stations No. 1, 4 and 5. Based on this data as well as the RAM-1 data, ERT recommended an Air Pollution Alert. As additional data were received from the other methods/ collection media, it confirmed the presence of organic concentrations above background at Stations No. 1, 4 and 5.

F. ON-SITE GRAB SAMPLES WITH THE RAM-1:

While the data collected along Route 608 was subject to interference from residential woodburning stoves, the presence of the plume over this area was visually confirmed via a helicopter flight. In addition to the RAM-1 reading varying from 22 mg/m<sup>3</sup> to 40 mg/m<sup>3</sup>, visual contact could not be maintained with members of the Air Sampling Team at Station No. 1 some 50-60 feet away.

Attachments

cc: Steve Dorrier  
Harry Allen

## RHINEHART TIRE FIRE - 11/03/83 thru 11/30/83

Station #	ERT 2-Stage Sample # (Vol. in liter)	MCEF 0.45 u Sample # (Vol. in liter)	600 mg Carbon Sample # (Vol. in liter)	3 Stage Silica Sample # (Vol. in liter)	Carbon/Tenax Thermal Desorption Tubes (Vol. in liter)
11/03/83	J/1 (6.16)	848/11 (552)			897/14 (64.35)
1	A/5 (11.66)				
2	All Pumps and Samples were destroyed in fire.....				
3- (Background)	F/4 (4.36) C/7 (10.71)	888/13 (588.8)			894/15 (83)
4	E/3 (2.69)* R/8 (7.14)*	889/10 (307.5)			865/16 (67.7)
11/04/83					
1	K/18 (10.33) J/22 (4.99)	889/31 (414)	892/29 (360)	882/38 (163.6)	866/42 (22.96)
3- (Background)	C/19 (9.16) F/23 (3.59)	890/35 (414)	864/28 (360)	857/37 (360)	
4	R/20 (9.38) E/24 (13.55)	887/30 (414)	893/26 (360)**	881/40 (360)	886/41 (72)
5	A/21 (41.49) I/25 (4.11)	888/36 (414)	858/27 (360)	878/39 (360)	865/43 (90)
1 off		848/32 (395.4)	893/47 (344.6)	857/52 (347)	
2 off		890/44 (319.6)	864/48 (318.4)	878/51 (320)	

AR100281




Station #	ERT 2-Stage Sample # (Vol. in liter)	MCEF 0.45 u Sample # (Vol. in liter)	600 mg Carbon Sample # (Vol. in liter)	3 Stage Silica Sample # (Vol. in liter)	Carbon/Tenax Thermal Desorption Tubes (Vol. in liter)
11/22/83					
1 (am)	A/1 (9.02) E/4 (4.04)	865/6 (348)	887/7 (360)	868/9 (270)	
1 (pm)	F/13 (4.8) B/14 (8.79)	889/15 (360)	888/17 (360)	886/16 (270)	
3 (am) (Background)	R/2 (10.14) J/3 (5.00)	889/5 (360)	888/8 (360)	886/10 (303.8) 886/20 (270)	
3 (pm) (Background)	A/19 (14.92)	865/21 (360)	887/22 (360)	868/9 (270)	
6 (pm) (Decon)	R/11 (11.02) J/12 (5.52)	861/18 (421.2)			
<hr/>					
Station #	150 mg Carbon Sample # (Vol. in liter)	MCEF 0.45 u Sample # (Vol. in liter)	600 mg Carbon Sample # (Vol. in liter)	3 Stage Silica Sample # (Vol. in liter)	Carbon/Tenax Thermal Desorption Tubes (Vol. in liter)
11/30/83					
1	874/0 (44.25) 867/0 (88.5)		885/0 ( 88.5) 883/0 (177.4)		
6(Decon)	225/0 (85.5)		253/0 (171.2)		
7	252/0 (88.7)		254/0 (177.6)		
3 (Background)	856/0 (78.4)		251/0 (157.4)		

\*Samples E/3 and R/8 on 11/3/83 were both identified as R/8

\*\*893/26 marked 897/33

# ERT AIR MONITORING EFFORTS RHINEHART TIRE FIRE (NOT TO SCALE)

GENERAL WIND DIRECTION



## Clayton Environmental Consultants, Inc.

Raritan Center • 160 Fieldcrest Ave • Edison, New Jersey 08837 • Telephone (201) 225-6040  
(formerly Occupational Health Services)

ORIGINAL  
(Red)

November 30, 1983

Mr. Kenneth Sullivan  
Operations Manager  
I. T. CORPORATION - EERU  
GSA Raritan Depot  
Bldg. 209, Bay F  
Edison, New Jersey 08837

CEC Job No. 8695-47  
Re: Winchester, VA. Site

Dear Mr. Sullivan:

The samples which you submitted to us on November 7, 1983 were analyzed and reported to you on November 10, 14 and 18, 1983.

One silica gel sample (#882/38) showed presence of an unknown peak which was analyzed by Gas Chromatography/Mass Spectrometer for identification, has been completed. The unknown peak is identified as Naphthalene in the range of 20 to 30 micrograms level.

Lab I.D.#	Sample Description	Vol. in Liters	Conc. of Naphthalene (ug)	(mg/m <sup>3</sup> )	(ppm)
16275	882/38 Silica Gel 3-Stage	163.6	20-30	0.18	2183

Above reported results of milligrams per cubic meter and parts per million are calculated utilizing 30 micrograms value. Therefore, this should be considered as maximum exposure.

If there are any questions, please advise. Thank you.

Very truly yours,

*Kirte H. Vora*  
Kirte H. Vora, Manager  
New Jersey Office and Laboratory

KHV:dc

Clayton Environmental Consultants, Inc.

Page 1 of 3

Results of Analyses

for

I. T. Corporation

CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume Liters	Aniline (mg)	Aniline (mg/m <sup>3</sup> )	(ppm)	Dimethylaniline (mg)	Dimethylaniline (mg/m <sup>3</sup> )	(ppm)
16274	857/37	360.0	<0.010	<0.028	<0.007	<0.010	<0.028	<0.006
16275	882/38	163.6	<0.010	<0.061	<0.016	<0.010	<0.061	<0.012
16276	878/39	360.0	<0.010	<0.028	<0.007	<0.010	<0.028	<0.006
16277	881/40	360.0	<0.010	<0.028	<0.007	<0.010	<0.028	<0.006
16278	857/52	347.0	<0.010	<0.029	<0.008	<0.010	<0.029	<0.006
16279	878/51	320.0	<0.010	<0.031	<0.008	<0.010	<0.031	<0.006

Limit of Detection:

0.010 mg

0.010 mg

AR100285

ORIGINAL  
(Red)

## Clayton Environmental Consultants, Inc.

Page 2 of 3

## Results of Analyses

for

I. T. Corporation

CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume Liters	o-Toluidine			2,4-Xylydine		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16274	857/37	360.0	<0.010	<0.028	<0.006	<0.010	<0.028	<0.006
16275	882/38	163.6	<0.010	<0.061	<0.014	<0.010	<0.061	<0.012
16276	878/39	360.0	<0.010	<0.028	<0.006	<0.010	<0.028	<0.006
16277	881/40	360.0	<0.010	<0.028	<0.006	<0.010	<0.028	<0.006
16278	857/52	347.0	<0.010	<0.029	<0.007	<0.010	<0.029	<0.006
16279	878/51	320.0	<0.010	<0.031	<0.007	<0.010	<0.031	<0.006

Limit of Detection:

0.010 mg

0.010 mg

AR100286

# Clayton Environmental Consultants, Inc.

Page 3 of 3

## Results of Analyses

for

I. T. Corporation

CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume Liters	o-Anisidine		p-Nitroaniline	
			(mg)	(mg/m <sup>3</sup> )	(mg)	(mg/m <sup>3</sup> )
				(ppm)		(ppm)
16274	857/37	360.0	<0.010	<0.028	<0.010	<0.028
16275	882/38	163.6	<0.010	<0.061	<0.010	<0.061
16276	878/39	360.0	<0.010	<0.028	<0.010	<0.028
16277	881/40	360.0	<0.010	<0.028	<0.010	<0.028
16278	857/52	347.0	<0.010	<0.029	<0.010	<0.029
16279	878/51	320.0	<0.010	<0.031	<0.010	<0.031

Limit of Detection:

0.010 mg

0.010 mg

AR100287

ORIGINAL  
(Red)

ORIGINAL  
(Red)

190.

190.

AR100288

[illegible]

DATE	DESCRIPTION	AMOUNT	CHECK NO.	BANK	INTEREST	TOTAL
10/01	10/01	10.00				10.00
10/02	10/02	10.00				10.00
10/03	10/03	10.00				10.00
10/04	10/04	10.00				10.00
10/05	10/05	10.00				10.00
10/06	10/06	10.00				10.00
10/07	10/07	10.00				10.00
10/08	10/08	10.00				10.00
10/09	10/09	10.00				10.00
10/10	10/10	10.00				10.00
10/11	10/11	10.00				10.00
10/12	10/12	10.00				10.00
10/13	10/13	10.00				10.00
10/14	10/14	10.00				10.00
10/15	10/15	10.00				10.00
10/16	10/16	10.00				10.00
10/17	10/17	10.00				10.00
10/18	10/18	10.00				10.00
10/19	10/19	10.00				10.00
10/20	10/20	10.00				10.00
10/21	10/21	10.00				10.00
10/22	10/22	10.00				10.00
10/23	10/23	10.00				10.00
10/24	10/24	10.00				10.00
10/25	10/25	10.00				10.00
10/26	10/26	10.00				10.00
10/27	10/27	10.00				10.00
10/28	10/28	10.00				10.00
10/29	10/29	10.00				10.00
10/30	10/30	10.00				10.00
10/31	10/31	10.00				10.00
10/32	10/32	10.00				10.00
10/33	10/33	10.00				10.00
10/34	10/34	10.00				10.00
10/35	10/35	10.00				10.00
10/36	10/36	10.00				10.00
10/37	10/37	10.00				10.00
10/38	10/38	10.00				10.00
10/39	10/39	10.00				10.00
10/40	10/40	10.00				10.00
10/41	10/41	10.00				10.00
10/42	10/42	10.00				10.00
10/43	10/43	10.00				10.00
10/44	10/44	10.00				10.00
10/45	10/45	10.00				10.00
10/46	10/46	10.00				10.00
10/47	10/47	10.00				10.00
10/48	10/48	10.00				10.00
10/49	10/49	10.00				10.00
10/50	10/50	10.00				10.00
10/51	10/51	10.00				10.00
10/52	10/52	10.00				10.00
10/53	10/53	10.00				10.00
10/54	10/54	10.00				10.00
10/55	10/55	10.00				10.00
10/56	10/56	10.00				10.00
10/57	10/57	10.00				10.00
10/58	10/58	10.00				10.00
10/59	10/59	10.00				10.00
10/60	10/60	10.00				10.00
10/61	10/61	10.00				10.00

[illegible]



Serial  
Number

0-50, 100, 200, 300, 400, 500, 600, 700, 800, 900, 1000

25305  
25306  
25307  
25308  
25309  
25310

88873  
88874  
88875  
88876  
88877  
88878

270.  
303.9  
270.  
270.

0.01  
0.01  
0.01  
0.01  
0.01  
0.01

0.01  
0.01  
0.01  
0.01  
0.01  
0.01

0.007  
0.007  
0.018  
0.018  
0.018  
0.018

Results of laboratory  
performance by the chromatography  
method for 0-50, 100, 200, 300, 400, 500, 600, 700, 800, 900, 1000  
have been corrected and  
the results of the various  
tests by the chromatography  
method.

Please contact us at (312) 424-8060 if you have any questions.

*Robert L. Smith*  
Robert L. Smith Jr., C.I.H.  
Manager, Laboratory Services  
Southfield Office

Attachment No.

ORIGINAL  
(Red)

Results analyses  
for  
I. T. Corporation  
CEC Job No. 8745-47

Lab Number	Sample Description	Air Vol. Liters	Copper		Nickel		Silver		Chromium	
			Cu	( $\mu\text{g}/\text{sample}$ ( $\text{mg}/\text{m}^3$ ))	Ni	( $\mu\text{g}/\text{sample}$ ( $\text{mg}/\text{m}^3$ ))	Ag	( $\mu\text{g}/\text{sample}$ ( $\text{mg}/\text{m}^3$ ))	Cr	( $\mu\text{g}/\text{sample}$ ( $\text{mg}/\text{m}^3$ ))
16673	889/5	360.0	<1.25	<0.003	<2.50	<0.007	<1.25	<0.003	<1.25	<0.003
16674	865/6	348.0	<1.25	<0.004	<2.50	<0.007	<1.25	<0.004	<1.25	<0.004
16675	Blank	-	<1.25	-	<2.50	-	<1.25	-	<1.25	-
Analytical Method:			P&CAM 173/AAS	flame	P&CAM 173/AAS	flame	P&CAM 173/AAS	flame	P&CAM 173/AAS	flame
Limit of Detection:			1.25 $\mu\text{g}/\text{sample}$		2.50 $\mu\text{g}/\text{sample}$		1.25 $\mu\text{g}/\text{sample}$		1.25 $\mu\text{g}/\text{sample}$	

AR 100296A

ATT. No. #4, pg. 1 of 6

ORIGINAL  
(Ref)

CLAYTON ENGINEERING & CONSULTING, INC.

Results of Analyses

for

I. T. Corporation

CEC Job No. 8745-47

Lab Number	Sample Description	Air Vol. Liters	Mercury Hg		Arsenic As		Zinc Zn		Tellurium Te	
			( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )	( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )	( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )	( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )
16673	889/5	360.0	<0.50	<0.001	<0.25	<0.001	<0.63	<0.002	<12.50	<0.035
16674	865/6	348.0	<0.50	<0.001	0.30	0.001	108.19	0.311	<12.50	<0.036
16675	Blank	-	<0.50	-	<0.25	-	<0.63	-	<12.50	-
Analytical Method:			P&CAM 173/MHS-10		P&CAM 173/MHS-10		P&CAM 173/AAS flame		P&CAM 173/AAS flame	
Limit of Detection:			0.50 $\mu\text{g}/\text{sample}$		0.25 $\mu\text{g}/\text{sample}$		0.63 $\mu\text{g}/\text{sample}$		12.50 $\mu\text{g}/\text{sample}$	

AR100291

7. N. #4. 226

ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.  
Results of Analyses

Page 1 of 2

for

I. T. Corporation

CEC Job No. 8747-47

AR100292

Lab Number	Sample Description	Air Vol. Liters	Mercury Hg		Arsenic As		Zinc Zn		Tellurium Te	
			( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )	( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )	( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )	( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )
16707	#889/15	360	<0.50	<0.001	0.52	0.001	551.49	1.532	<12.50	<0.035
16708	#861/18	421.2	<0.50	<0.001	<0.25	<0.001	2.89	0.002	<12.50	<0.030
16709	#865/21	360	<0.50	<0.001	<0.25	<0.001	19.34	0.054	<12.50	<0.035

Analytical Method: PACAM 173/MHS-10      PACAM 173/MHS-10      PACAM 173/AAS flame      PACAM 173/AAS flame

Limit of Detection: 0.50  $\mu\text{g}/\text{sample}$       0.25  $\mu\text{g}/\text{sample}$       0.63  $\mu\text{g}/\text{sample}$       12.50  $\mu\text{g}/\text{sample}$

A.N. #4, 03 30/6

ORIGINAL  
(Red)

Udylon Environmental Consultants, Inc.

Page 2 of 2

Results of Analyses

for

I.T. Corporation

CEC Job No. 8747-47

Lab Number	Sample Description	Air Vol. Liters	Copper Cu		Nickel Ni		Silver Ag		Chromium Cr	
			( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )	( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )	( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )	( $\mu\text{g}/\text{sample}$ )	( $\text{mg}/\text{m}^3$ )
16707	#889/15	360	2.14	<del>0.006</del>	<2.50	<0.007	<1.25	<0.003	<1.25	<0.003
16708	#861/18	421.2	<1.25	<0.003	<2.50	<0.006	<1.25	<0.003	<1.25	<0.003
16709	#865/21	360	<1.25	<0.003	<2.50	<0.007	<1.25	<0.003	<1.25	<0.003

Analytical Method:

Limit of Detection:

P&CAM 173/AAS flame

P&CAM 173/AAS flame

P&CAM 173/AAS flame

P&CAM 173/AAS flame

1.25  $\mu\text{g}/\text{sample}$

2.50  $\mu\text{g}/\text{sample}$

1.25  $\mu\text{g}/\text{sample}$

1.25  $\mu\text{g}/\text{sample}$

A.N. #4, p. 496

AR100293

ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.

Page 1 of 1

Results of Analyses  
for  
I. T. Corporation  
CEC Job No. 8695-47

AR100294

Lab Number	Sample Description	Copper ( $\mu\text{g}/\text{sample}$ )	Nickel ( $\mu\text{g}/\text{sample}$ )	Zinc ( $\mu\text{g}/\text{sample}$ )	Silver ( $\mu\text{g}/\text{sample}$ )	Chromium ( $\mu\text{g}/\text{sample}$ )	Tellurium ( $\mu\text{g}/\text{sample}$ )	Mercury ( $\mu\text{g}/\text{sample}$ )	Arsenic ( $\mu\text{g}/\text{sample}$ )
16296	#888/36	<2.5	<5.00	<del>1.25</del> 0.003 ug/l	<2.5	<2.5	<del>21.00</del> 0.001 ug/l	<0.50	<del>8.71</del> 0.01 ug/l
Analytical Method:		P&CAM173	P&CAM173	P&CAM173	P&CAM173	P&CAM173	P&CAM173	MHS-10	MHS-10
Limit of Detection:		0.05 $\mu\text{g}/\text{ml}$	0.1 $\mu\text{g}/\text{ml}$	0.025 $\mu\text{g}/\text{ml}$	0.05 $\mu\text{g}/\text{ml}$	0.05 $\mu\text{g}/\text{ml}$	0.5 $\mu\text{g}/\text{ml}$	0.01 $\mu\text{g}/\text{ml}$	0.01 $\mu\text{g}/\text{ml}$

R.N. 38596

Clayton Environmental Consultants, Inc.

Page 1 of 8

## Results of Analyses

for

I. T. Corporation

CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume, Liters	Total Hydrocarbons as Hexanes		
			(mg)	(mg/m <sup>3</sup> )	(ppm)
16289	889/10	307.5	<0.017	<0.055	<0.02
16290	848/11	552.0	<0.017	<0.031	<0.01
16291	888/13	588.8	<0.017	<0.029	<0.01
16292	887/30	414.0	<0.017	<0.041	<0.01
16293	889/31	414.0	<0.017	<0.041	<0.01
16294	848/32	395.37	<0.017	<0.043	<0.01
16295	890/35	414.0	<0.017	<0.041	<0.01
16297	890/44	367.54	<0.017	<0.046	<0.01

Analytical Method:

Limit of Detection:

P&amp;CAM 127

0.017 mg

Analyzed From  
PARTICULATE Filter

AR100295

A.N. 5/6/6

ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.

Page 2 of 8

Results of Analyses

for

I. T. Corporation

CEC Job No. 8695-47

AR100296

Lab Number	Sample Description	Air Volume		Acetone		Methylene Chloride	
		Liters	(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(ppm)
16298	864/28	360.0	<0.060	<0.167	<0.07	<0.014	<0.039
16299	892/29	360.0	0.039	0.108	<del>0.05</del> 0.04	0.301	0.836
16300	858/27	360.0	<0.060	<0.167	<0.07	<0.014	<0.039
16301	893/47	344.6	<0.060	<0.174	<0.07	<0.014	<0.041
16302	864/48	318.4	<0.060	<0.188	<0.08	<0.014	<0.044
16303	893/26 marked 897/33	360.0	<0.060	<0.167	<0.07	<0.014	<0.039

Analytical Method:

P&amp;CAM 127

P&amp;CAM 127

Limit of Detection:

0.060 mg

0.014 mg

ATT No. 5 pg. 1 of 2



ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.

Page 3 of 8

Results of Analyses  
for

I. T. Corporation  
CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume		Chloroform			Ethylene Dichloride		
		Liters	(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)	(ppm)
16298	864/28	360.0	<0.030	<0.083	<0.04	<0.012	<0.033	<0.01	<0.01
16299	892/29	360.0	0.192	0.533	0.23	0.071	0.197	0.05	0.05
16300	858/27	360.0	0.065	0.181	0.08	<0.012	<0.033	<0.01	<0.01
16301	893/47	344.6	<0.030	<0.087	<0.04	<0.012	<0.035	<0.01	<0.01
16302	864/48	318.4	<0.030	<0.094	<0.04	<0.012	<0.038	<0.01	<0.01
16303	893/26 marked 897/33	360.0	0.070	0.194	0.09	<0.012	<0.033	<0.01	<0.01

Analytical Method:

Limit of Detection:

P&CAM 127

0.030 mg

P&CAM 127

0.012 mg

AR100297  
A.N. #5 10/2/28

ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.

Page 4 of 8

Results of Analyses

for

I. T. Corporation

CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume		Benzene		Methyl Ethyl Ketone	
		Liters	(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> ) (ppm)
16298	864/28	360.0	<0.008	<0.022	<0.01	<0.016	<0.044
16299	892/29	360.0	0.851	2.364	0.74	0.090	0.250
16300	858/27	360.0	0.012	0.033	<0.01	<0.016	<0.044
16301	893/47	344.6	<0.008	<0.023	<0.01	<0.016	<0.046
16302	864/48	318.4	<0.008	<0.025	<0.01	<0.016	<0.050
16303	893/26 marked 897/33	360.0	0.009	0.025	<0.01	<0.016	<0.044

Analytical Method:

P&CAM 127

P&CAM 127

Limit of Detection:

0.008 mg

0.016 mg

AR100298

AR100298 Page 3 of 4

## Clayton Environmental Consultants, Inc.

Page 5 of 8

Results of Analyses  
for

I. T. Corporation

CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume Liters	1,1,1-Trichloroethane (mg) (mg/m <sup>3</sup> ) (ppm)	(mg)	Toluene (mg/m <sup>3</sup> ) (ppm)
16298	864/28	360.0	<0.014	<0.002	<0.006
16299	892/29	360.0	0.092	0.377	1.047
16300	858/27	360.0	<0.014	0.008	0.022
16301	893/47	344.6	<0.014	<0.002	<0.006
16302	864/48	318.4	<0.014	<0.002	<0.006
16303	893/26 marked 897/33	360.0	<0.014	0.004	0.011

Analytical Method:

Limit of Detection:

P&amp;CAM 127

0.014 mg

P&amp;CAM 127

0.002 mg

AR100299

R.N. #AR100299

ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.

Page 6 of 8

Results of Analyses  
for

I. T. Corporation  
CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume		Xylenes		Trichloroethylene	
		Liters	(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> ) (ppm)
16298	864/28	360.0	<0.002	<0.006	<0.001	<0.014	<0.039
16299	892/29	360.0	0.276	0.767	0.018	0.153	0.425
16300	858/27	360.0	0.006	0.017	<del>0.018</del>	<0.014	<0.039
16301	893/47	344.6	<0.002	<0.006	<0.001	<0.014	<0.041
16302	864/48	318.4	<0.002	<0.006	<0.001	<0.014	<0.044
16303	893/26 marked 897/33	360.0	<0.002	<0.006	<0.001	<0.014	<0.039

Analytical Method:

P&CAM 127

P&CAM 127

Limit of Detection:

0.002 mg

0.014 mg

AR100300

12.2.85 18.5

Results of Analyses  
for

I. T. Corporation  
CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume Liters	(mg)	Styrene (mg/m <sup>3</sup> )	(ppm)	1,1,2-Trichloroethane (mg)	(mg/m <sup>3</sup> )	(ppm)
16298	864/28	360.0	<0.018	<0.050	<0.01	<0.014	<0.039	<0.01
16299	892/29	360.0	0.051	0.142	<del>0.033</del>	0.073	0.203	<del>0.044</del>
16300	858/27	360.0	<0.018	<0.050	<0.01	<0.014	<0.039	<0.01
16301	893/47	344.6	<0.018	<0.052	<0.01	<0.014	<0.041	<0.01
16302	864/48	318.4	<0.018	<0.057	<0.01	<0.014	<0.044	<0.01
16303	893/26 marked 897/33	360.0	<0.018	<0.050	<0.01	<0.014	<0.039	<0.01

Analytical Method:

P&CAM 127

P&CAM 127

Limit of Detection:

AR100301

R.N. #5, AR1003019 21

ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.

Page 8 of 8

Results of Analyses  
for  
I. T. Corporation  
CEC Job No. 8695-47

Lab Number	Sample Description	Air Volume		Total Hydrocarbons		
		Liters	(mg)	(mg/m <sup>3</sup> )	(ppm)	
16298	864/28	360.0	<0.002	<0.006	<0.001	
16299	892/29	360.0	1.197	3.325	<del>0.88</del>	
16300	858/27	360.0	0.016	0.044	<del>0.01</del>	
16301	893/47	344.6	<0.002	<0.006	<0.001	
16302	864/48	318.4	<0.002	<0.006	<0.002	
16303	893/26 marked 897/33	360.0	0.011	0.031	<0.01	

Analytical Method:

Limit of Detection:

P&CAM 127

0.002 mg

AR100302

H.N. #5 27 7 of 2  
AR100302

Clayton Environmental Consultants, Inc.  
Results of Analysesfor  
I.T. CorporationCEC Job No. 8768-47  
600 mg Charcoal Tubes

Page 2 of 3

Lab Number	Sample Description	Air Volume (liters)	Methylene Chloride		Methyl Ethyl Ketone	
			(mg)	(mg/m <sup>3</sup> )	(mg)	(mg/m <sup>3</sup> )
16939	#883/0	177.4	0.060	0.338	0.031	0.175
16940	#254/0	177.6	<0.014	<0.079	<0.016	<0.090
16941	#251/0	157.4	<0.014	<0.089	<0.016	<0.103
16946	#253/0	171.2	<0.014	<0.082	<0.016	<0.093
16944	#885/0	88.5	0.050	0.565	0.024	0.271

Analytical Method (NIOSH):  
Limit of Detection:P&CAM 127  
0.014 mgP&CAM 127  
0.016 mg

Lab Number	Sample Description	Air Volume (liters)	Chloroform		Ethylene Dichloride	
			(mg)	(mg/m <sup>3</sup> )	(mg)	(mg/m <sup>3</sup> )
16939	#883/0	177.4	0.120	0.676	0.037	0.209
16940	#254/0	177.6	<0.030	<0.169	<0.012	<0.068
16941	#251/0	157.4	<0.030	<0.381	<0.012	<0.076
16946	#253/0	171.2	<0.030	<0.175	<0.012	<0.070
16944	#885/0	88.5	0.096	1.085	0.028	0.316

Analytical Method (NIOSH):  
Limit of Detection:P&CAM 127  
0.030 mgP&CAM 127  
0.012 mg

AR100303

AR#00303 892  
H.N. 3/1/89

Clayton Environmental Consultants, Inc.  
Results of Analyses

Pg. 2 of 3

for  
I.T. CorporationCEC Job No. 8768-47  
600 mg Charcoal Tubes

Lab Number	Sample Description	Air Volume (liters)	Benzene			Trichloroethylene		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16939	#883/0	177.4	0.353	1.990	<del>0.02</del>	0.085	0.479	<del>0.09</del>
16940	#254/0	177.6	<0.008	<0.045	<0.01	<0.014	<0.079	<0.01
16941	#251/0	157.4	<0.008	<0.051	<0.02	<0.014	<0.089	<0.02
16946	#253/0	171.2	<0.008	<0.047	<0.01	<0.014	<0.082	<0.02
16944	#885/0	88.5	0.194	2.192	<del>0.69</del>	0.056	0.633	<del>0.12</del>

Analytical Method (NIOSH):  
Limit of Detection:PeCAM 127  
0.008 mgPeCAM 127  
0.014 mg

Lab Number	Sample Description	Air Volume (liters)	Toluene			Xylenes		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16939	#883/0	177.4	0.228	1.285	0.34	0.216	1.218	0.28
16940	#254/0	177.6	0.002	0.011	0.002	<0.002	<0.011	<0.003
16941	#251/0	157.4	<0.002	<0.013	<0.003	<0.002	<0.013	<0.003
16946	#253/0	171.2	<0.002	<0.012	<0.003	<0.002	<0.012	<0.003
16944	#885/0	88.5	0.124	1.401	0.33	0.116	1.311	0.30

Analytical Method (NIOSH):  
Limit of Detection:PeCAM 127  
0.002 mgPeCAM 127  
0.002 mgAB100304  
P.N. 5, 07 2 9 21



ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.  
Results of Analyses

for  
I.T. Corporation

CEC Job No. 8768-47  
600 mg Charcoal Tubes

Lab Number	Sample Description	Air Volume (liters)	1,1,2-Trichloroethane			Mineral Spirits		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16939	#883/0	177.4	0.056	0.316	<del>0.006</del>	0.589	3.320	<del>0.008</del>
16940	#254/0	177.6	<0.014	<0.079	<0.01	<0.080	<0.450	<0.07
16941	#251/0	157.4	<0.014	<0.089	<0.02	<0.080	<0.508	<0.08
16946	#253/0	171.2	<0.014	<0.082	<0.01	<0.080	<0.467	<0.08
16944	#885/0	88.5	0.036	0.407	<del>0.007</del>	0.317	3.582	<del>0.005</del>

Analytical Method (NIOSH):  
Limit of Detection:

PeCAM 127  
0.014 mg

PeCAM 127  
0.080 mg

AR100305  
D.N. 15, 10 g 21

Clayton Environmental Consultants, Inc.  
Results of Analyses  
for

Pg. 1 of 2

I.T. Corporation

CEC Job No. 8768-47

150 mg Charcoal Tubes

Lab Number	Sample Description	Air Volume (liters)	Methylene Chloride			Methyl Ethyl Ketone		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16942	#874/0	44.25	0.015	0.339	<del>0.010</del>	0.012	0.271	<del>0.009</del>
16943	#867/0	88.5	0.018	0.203	<del>0.010</del>	0.010	0.113	<del>0.004</del>
16945	#225/0	85.5	<0.007	<0.082	<0.02	<0.008	<0.094	<0.03
16947	#252/0	88.7	<0.007	<0.079	<0.02	<0.008	<0.090	<0.03
16948	#856/0	78.4	<0.007	<0.089	<0.03	<0.008	<0.102	<0.03

Analytical Method (NIOSH):

Limit of Detection:

P&CAM 127  
0.007 mgP&CAM 127  
0.008 mg

Lab Number	Sample Description	Air Volume (liters)	Chloroform			Ethylene Dichloride		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16942	#874/0	44.25	0.048	1.085	<del>0.042</del>	0.014	0.316	<del>0.008</del>
16943	#867/0	88.5	0.041	0.463	<del>0.030</del>	0.013	0.147	<del>0.004</del>
16945	#225/0	85.5	<0.030	<0.351	<0.15	<0.006	<0.070	<0.02
16947	#252/0	88.7	<0.030	<0.338	<0.15	<0.006	<0.068	<0.02
16948	#856/0	78.4	<0.030	<0.383	<0.17	<0.006	<0.077	<0.02

Analytical Method (NIOSH):

Limit of Detection:

AP 100306/21  
AN. 85, 18/11/21

ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.  
Results of Analyses

Pg. 2

for  
I.T. Corporation  
CEC Job No. 8768-47  
150 mg Charcoal Tubes

Lab Number	Sample Description	Air Volume (liters)	Benzene		Trichloroethylene	
			(mg)	(mg/m <sup>3</sup> )	(mg)	(mg/m <sup>3</sup> )
16942	#874/0	44.25	0.093	2.102	0.027	0.610
16943	#867/0	88.5	0.140	1.582	0.078	0.881
16945	#225/0	85.5	<0.004	<0.047	<0.007	<0.082
16947	#252/0	88.7	<0.004	<0.045	<0.007	<0.079
16948	#856/0	78.4	<0.004	<0.051	<0.007	<0.089

Analytical Method (NIOSH):  
Limit of Detection: 0.004 mg

PeCAM 127  
0.007 mg

Lab Number	Sample Description	Air Volume (liters)	Toluene		Xylenes	
			(mg)	(mg/m <sup>3</sup> )	(mg)	(mg/m <sup>3</sup> )
16942	#874/0	44.25	0.062	1.401	0.063	1.424
16943	#867/0	88.5	0.110	1.243	0.103	1.164
16945	#225/0	85.5	<0.001	<0.012	<0.001	<0.012
16947	#252/0	88.7	0.001	0.011	<0.001	<0.011
16948	#856/0	78.4	<0.001	<0.013	<0.001	<0.013

Analytical Method (NIOSH):  
Limit of Detection: 0.001 mg

PeCAM 127  
0.001 mg

AR100307  
R.N. #5, pg 12g

ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.

Pg. 3 of 3

Results of Analyses

for  
I.T. Corporation

CEC Job No. 8768-47

150 mg Charcoal Tubes

Lab Number	Sample Description	Air Volume (liters)	1,1,2-Trichloroethane			Mineral Spirits		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16942	#874/0	44.25	0.024	0.542	<del>0.10</del>	0.175	3.955	<del>0.65</del>
16943	#867/0	88.5	0.033	0.373	0.07	0.268	3.028	0.50
16945	#225/0	85.5	<0.007	<0.082	<0.02	<0.040	<0.468	<0.08
16947	#252/0	88.7	<0.007	<0.079	<0.01	<0.040	<0.451	<0.07
16948	#856/0	78.4	<0.007	<0.089	<0.02	<0.040	<0.510	<0.08
Analytical Method (NIOSH):			P&CAM 127			P&CAM 127		
Limit of Detection:			0.007 mg			0.040 mg		

AR100308

A.N. #5. Pp. 13 g

ORIGINAL  
(Red)

Clayton Environmental Consultants, Inc.  
Results Analyses

Page 1 of 8

for  
I. T. Corporation  
CEC Job No. 8747-47

Lab Number	Sample Description	Air Volume Liters	Acetone		Methylene Chloride	
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg/m <sup>3</sup> ) (ppm)
16702 1 <sup>st</sup>	#887/7	360	<0.060	<0.167	<0.07	0.064 0.178 0.05
16703 3 <sup>rd</sup>	#888/8	360	<0.060	<0.167	<0.07	<0.014 <0.039 <0.01
16704 1 <sup>st</sup>	#888/17	360	0.073	0.203	0.09	0.149 0.414 0.12
16705 3 <sup>rd</sup>	#887/22	360	<0.060	<0.167	<0.07	<0.014 <0.039 <0.01
16706	Blank	-	<0.060	-	-	<0.014 - -

Analytical Method:

Limit of Detection:

P&CAM 127

0.060 mg

P&CAM 127

0.014 mg

AR100309

AR100309  
H.N. #5, PA

ORIGINAL  
(R-1)

Results of Analyses

for

I. T. Corporation

CEC Job No. 8747-47

Lab Number	Sample Description	Air Volume Liters	Methyl Ethyl Ketone			Ethylene dichloride		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16702	#887/7	360	<0.016	<0.044	<0.02	0.014	0.039	0.01
16703	#888/8	360	<0.016	<0.044	<0.02	<0.012	<0.033	<0.01
16704	#888/17	360	0.024	0.067	0.02	0.030	0.083	0.02
16705	#887/22	360	<0.016	<0.044	<0.02	<0.012	<0.033	<0.01
16706	Blank	-	<0.016	-	-	<0.012	-	-

Analytical Method:

Limit of Detection:

P&CAM 127

0.016 mg

P&CAM 127

0.012 mg

AR100310  
R.N. #5, 150/c

ORIGINAL  
(Red)

Result for Analyses

I. T. Corporation

CEC Job No. 8747-47

Page 3 of 8

Lab Number	Sample Description	Air Volume Liters	Benzene		P-dioxane	
			(mg)	(mg/m <sup>3</sup> )	(mg)	(mg/m <sup>3</sup> )
16702	#887/7	360	0.464	1.289	0.40	<0.01
16703	#888/8	360	<0.008	<0.022	<0.01	<0.01
16704	#888/17	360	0.565	1.569	<del>0.49</del>	<0.01
16705	#887/22	360	<0.008	<0.022	<0.01	<0.01
16706	Blank	-	<0.008	-	<0.010	-

Analytical Method:

P&CAM 127

P&CAM 127

Limit of Detection:

0.008 mg

0.010 mg

AR100311

AR100311  
K.O. 5, 18 14 9 2

ORIGINAL  
(Red)

Results of Analyses

for

I. T. Corporation

CEC Job No. 8747-47

Lab Number	Sample Description	Air Volume Liters	1,1,2-Trichloroethane			Tetrachloroethylene		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16702	#887/7	360	0.024	0.067	<del>0.01</del>	<0.016	<0.052	<0.01
16703	#888/8	360	<0.014	<0.039	<0.01	<0.016	<0.052	<0.01
16704	#888/17	360	0.078	0.217	<del>0.04</del>	<0.016	<0.052	<0.01
16705	#887/22	360	<0.014	<0.039	<0.01	<0.016	<0.052	<0.01
16706	Blank	-	<0.014	-	-	<0.016	-	-

Analytical Method:

Limit of Detection:

P&CAM 127

0.014 mg

P&CAM 127

0.016 mg

AR100312  
D.N. #5, 88 17921



ORIGINAL  
(Red)

Results of Analyses

I. T. Corporation

CEC Job No. 8747-47

Lab Number	Sample Description	Air Volume Liters	Xylenes		Chloroform	
			(mg)	(mg/m <sup>3</sup> )	(mg)	(ppm)
16702	#887/7	360	0.165	0.458	0.033	0.092
16703	#888/8	360	<0.002	<0.006	<0.030	<0.083
16704	#888/17	360	0.306	0.850	0.095	0.264
16705	#887/22	360	<0.002	<0.006	<0.030	<0.083
16706	Blank	-	<0.002	-	<0.030	-

Analytical Method:

P&CAM 127

P&CAM 127

Limit of Detection:

0.002 mg

0.030 mg

AR100313

AR100313  
H.N. 5/24/89

ORIGINAL  
(Red)

Results of Analyses  
for  
I. T. Corporation  
CEC Job No. 8747-47

Lab Number	Sample Description	Air Volume Liters	1,1,1-Trichloroethane (mg)	(mg/m <sup>3</sup> )	(ppm)	Carbon Tetrachloride (mg)	(mg/m <sup>3</sup> )	(ppm)
16702	#887/7	360	<0.014	<0.039	<0.01	<0.016	<0.044	<0.01
16703	#888/8	360	<0.014	<0.039	<0.01	<0.016	<0.044	<0.01
16704	#888/17	360	<0.014	<0.039	<0.01	<0.016	<0.044	<0.01
16705	#887/22	360	<0.014	<0.039	<0.01	<0.016	<0.044	<0.01
16706	Blank	-	<0.014	-	-	<0.016	-	-

Analytical Method:

Limit of Detection:

P&CAM 127

0.014 mg

P&CAM 127

0.016 mg

AR100314

AR100344/2  
P.N. 5, 98

ORIGINAL  
(Red)

Results for Analyses

I. T. Corporation  
CEC Job No. 8747-47

Lab Number	Sample Description	Air Volume Liters	Trichloroethylene			Toluene		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16702	#887/7	360	0.052	0.144	0.03	0.248	0.689	0.18
16703	#888/8	360	<0.014	<0.039	<0.01	<0.002	<0.006	<0.001
16704	#888/17	360	0.114	0.317	0.06	0.397	1.103	0.29
16705	#887/22	360	<0.014	<0.039	<0.01	<0.002	<0.006	<0.001
16706	Blank	-	<0.014	-	-	<0.002	-	-

Analytical Method:

P&CAM 127

P&CAM 127

Limit of Detection:

0.014 mg

0.002 mg

AR100315  
DN #5. x 20 92

## Results of Analyses

for

I. T. Corporation

CEC Job No. 8747-47

Lab Number	Sample Description	Air Volume Liters	Styrene			Mineral Spirits		
			(mg)	(mg/m <sup>3</sup> )	(ppm)	(mg)	(mg/m <sup>3</sup> )	(ppm)
16702	#887/7	360	<0.018			0.217	0.603	0.10
16703	#888/8	360	<0.018			<0.080	<0.222	<0.04
16704	#888/17	360	<0.018			0.668	1.856	0.31
16705	#887/22	360	<0.018			<0.080	<0.222	<0.04
16706	Blank	-	<0.018			<0.080		

Analytical Method:

Limit of Detection:

P&amp;CAM 127

0.018 mg

P&amp;CAM 127

0.080 mg

AR100316

AN #5, 07/21/90

~~EDISON ENVIRONMENTAL CONSULTANTS, INC.~~

25711 Southfield Road, Southfield, Michigan 48075. Telephone 313 424-8860

November 16, 1983

Mr. Phil Staats  
IT CORPORATION  
GSA Raritan Center  
Building 209; Bay F  
Edison NJ 08837

CEC Job No. 8695-47

Dear Mr. Staats:

The samples which you submitted to us on November 7, 1983, have been analyzed by gas chromatography/mass spectrometry (GC/MS) as requested. I have enclosed copies of the total ion current chromatograms (TIC) and mass spectra for the compounds identified.

Quantitation was performed using an external mixture of chloroform, toluene, 1,2,3-trimethylbenzene, and dodecane. This mixture gives a good combination of retention times and response factors for external standard quantification.

The results have been blank corrected to eliminate compounds not actually present in the field samples.

It is a pleasure to be of assistance to you. Please contact us if you have any questions concerning this report.

Sincerely,

Robert Lieckfield Jr., C.I.H.  
Manager, Laboratory Services

RL:li

cc: Mark Fenner

AR100317

Lab Number: 293588

Sample Description: J/1 Station #1, Front section: Tenax

Air volume: 6.16 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
18	Sulfue dioxide			
101	Benzene	0.3	0.02	50
182	Toluene	2.	0.1	400
254	Ethylbenzene	3.	0.2	600
261	Xylene	1.	0.04	200
277	Styrene	2.	0.06	300
280	Xylene	2.	0.07	300
302	Methyl ethyl benzene	< 0.2	< 0.007	< 40
324	Phenyl acetaldehyde	< 0.2	< 0.007	< 40
332	Methyl ethyl benzene	1.	0.03	200
351	Benzonitrile	2.	0.06	300
355	C <sub>9</sub> H <sub>12</sub> Alkylbenzene	1.	0.04	200
376	Methyl styrene			
388	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	1.	0.03	200
416	Indene	< 0.2	< 0.007	< 40
457	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	0.4	0.01	60
477	Dimethyl or Ethylstyrene			
542	Methylindene	0.4	0.01	60
550	Naphthalene	2.	0.08	400
583	Methylnaphthalene	0.6	0.02	100
593	Methylnaphthalene	0.4	0.01	70
603	Acenaphthene or Biphenyl	0.4	0.01	70
616	Dimethyl naphthalene	0.2	0.006	40
631	Dimethyl naphthalene	0.5	0.01	80
635	Acenaphthylene	0.4	0.01	70
644	C <sub>13</sub> H <sub>12</sub> (allyl naphthalene and/or methyl biphenyl)	< 0.2	< 0.005	< 30
651	C <sub>13</sub> H <sub>12</sub> (Allyl naphthalene and/or Methyl biphenyl)	< 0.2	< 0.005	< 20
675	Butylated hydroxy toluene	0.3	0.005	40
723	C <sub>13</sub> H <sub>14</sub> Alkyl naphthalene	< 0.2	< 0.005	< 40
736	Fluorene	< 0.2	< 0.005	< 40
762	C <sub>14</sub> H <sub>28</sub> Hydrocarbon	0.3	0.006	50
872	Trimethyl phenyl indane	0.3	0.005	50
894	Anthracene and/or phenanthrene	0.5	0.01	90
1001	Fluoranthene	< 0.2	< 0.004	< 40
	Pyrene	< 0.2	< 0.004	< 40
	Chrysene and/or benz(a)anthracene	< 0.2	< 0.003	< 40

Results have been blank corrected.

AR100318

Att. No. 6

ORIGINAL  
(Red)

IT CORPORATION  
CEC Job No. 8695-47

Lab Number: 293588

Sample Description: J/1 Station #1, Back section: Chromosorb 102

Air volume: 6.16 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
105	Benzene	2.	0.08	200

Results have been blank corrected.

$E = .67 \text{ ppm}$   
 $d_f = .56 \text{ ppm}$

AR100319

A.N. #6

Lab Number: 293589

Sample Description: A/5 Station #1, Front Section: Tenax

Air Volume: 11.66 liters

Spectrum Number	Compound	(micrograms)	(ppm)	(micrograms/m <sup>3</sup> )
103	Benzene	3.	0.08	300
180	Toluene	5.	0.1	400
250	Ethylbenzene	3.	0.06	200
254	Xylene	3.	0.06	200
272	{ Styrene	3.	0.07	300
	{ Xylene			
296	Methyl ethyl benzene	0.5	0.008	40
316	Phenyl acetaldehyde	0.4	0.006	30
324	C <sub>9</sub> H <sub>12</sub> alkylbenzene	3.	0.05	200
337	Methyl styrene	0.6	0.01	50
	{ Benzonitrile			
344	{ Phenol	5.	0.1	400
	{ C <sub>9</sub> H <sub>12</sub> alkylbenzene			
348	Methyl styrene	0.9	0.02	80
368	C <sub>10</sub> H <sub>14</sub> alkylbenzene	4.	0.06	400
380	Indene	0.5	0.009	40
388	C <sub>10</sub> H <sub>14</sub> alkylbenzene	0.3	0.004	20
407	{ Dimethyl or Ethylstyrene	1.	0.02	90
	{ C <sub>10</sub> H <sub>14</sub> alkylbenzene			
448	{ Methyl indene	0.5	0.007	40
453	{ Methyl indene	0.6	0.008	50
	{ C <sub>11</sub> H <sub>16</sub> alkylbenzene			
475	Naphthalene	5.	0.08	400
537	Methylnaphthalene	2.	0.03	200
548	Methylnaphthalene	1.	0.01	80
583	Acenaphthene or Biphenyl	1.	0.02	100
595	Dimethylnaphthalene	0.5	0.006	40
605	Dimethylnaphthalene	1.	0.01	90
618	Acenaphthylene	1.	0.01	80
633	{ C <sub>13</sub> H <sub>12</sub> (allylnaphthalene or	0.3	0.004	30
	{ methyl biphenyl)			
638	{ C <sub>13</sub> H <sub>12</sub> (allylnaphthalene or	0.2	0.003	20
	{ methyl biphenyl)			
655	C <sub>13</sub> H <sub>14</sub> alkyl naphthalene	< 0.2	< 0.003	< 20
670	C <sub>13</sub> H <sub>14</sub> alkyl naphthalene	< 0.2	< 0.003	< 20
681	Fluorene	0.2	0.003	20
699	C <sub>14</sub> H <sub>14</sub> alkyl naphthalene	0.2	0.002	20
725	Hydrocarbon	< 0.2	< 0.002	< 20
767	{ Anthracene and/or	0.9	0.01	80
	{ Phenanthrene			
815	{ Methyl anthracene and/or	0.2	0.002	20
	{ methyl phenanthrene			
839	Palmitic acid	1.0	0.008	80
876	Fluoranthene	0.2	0.002	20
894	Pyrene	< 0.2	< 0.002	< 20
929	Methyl fluoranthene and/or	< 0.2	< 0.002	< 20
	methyl pyrene			

Results have been blank corrected.

AR100320

D.N. #6



ORIGINAL  
(Red)

IF CORPORATION

Job No. 3695-47

Lab Number: 293589

Sample Description: A/5 Station #1, Back Section: Chromosorb 102

Air Volume: 11.66 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
37	C <sub>5</sub> H <sub>8</sub> hydrocarbon	0.3	0.009	20
103	Benzene	2.	0.06	200
178	Toluene	0.9	0.02	80

Results have been blank corrected.

$\Sigma = 1.012$

AR100321

ZAC

ORIGINAL  
(Red)

IT CORPORATION  
Job No. 8695-47

Lab Number: 293590

Sample Description: F/4 Station #3, Front section: Tenax

Air Volume: 4.36 liters

← Background

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
95	Benzene	< 0.2	< 0.02	< 50
684	Possible hydrocarbon	< 0.2	< 0.03	< 50
701	Unknown	< 0.2	< 0.03	< 50
723	Hydrocarbon	< 0.2	< 0.03	< 50

Results have been blank corrected.

AR100322  
A.#6

IF CORPORATION  
Job No. 8695-47

Lab Number: 293590

Sample Description: F/4 Station #3, Back section: Chromosorb 102

Air Volume: 4.36 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
127	C <sub>8</sub> H <sub>18</sub> hydrocarbon	< 0.2	< 0.01	< 50
183	Toluene	0.3	0.02	70

Results have been blank corrected.

AR100323  
#2

ORIGINAL  
(Red)

IT CORPORATION  
CEC Job No. 8695-47

Lab Number: 293591

Sample Description: C/7 Station #3, Front section: Tenax

Air Volume: 10.71 liters

← BACKGROUND →

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
103	Benzene	< 0.2	< 0.006	< 20
400	C <sub>9</sub> H <sub>12</sub> alkylbenzene	< 0.2	< 0.004	< 20
718	Unknown	0.3	0.003	30
740	Hydrocarbon	< 0.2	< 0.002	< 20
749	Unknown	< 0.2	< 0.002	< 20

Results have been blank corrected.

AR100324 #6

ORIGINAL  
(Red)

IT CORPORATION  
CEC Job No. 8695-47

Lab Number: 293591

← BACKGROUND

Sample Description: C/7 Station #3, Back section: Chromosorb 102

Air Volume: 10.71 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
34	Trichlorofluoromethane	0.2	0.004	20
112	C <sub>7</sub> H <sub>16</sub> hydrocarbon	<0.2	<0.005	<20
118	C <sub>7</sub> H <sub>16</sub> hydrocarbon	<0.2	<0.005	<20
125	C <sub>8</sub> H <sub>18</sub> hydrocarbon	<0.2	<0.004	<20
135	C <sub>7</sub> H <sub>16</sub> hydrocarbon	<0.2	<0.005	<20
260	Xylene	0.2	0.005	20

Results have been blank corrected.

AR100325

#6

ORIGINAL  
(Red)

Lab Number: 293592

Sample Description: R/8-1 Station #4, Front section: Tenax

Air Volume: Unknown

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
735	Trimethylphenyl indane	0.2	*	*

\* No concentrations in ppm or micrograms/m<sup>3</sup> were calculated due to questionable air volumes; a sample mislabeling occurred in the field.

Results have been blank corrected.

AR100326

#6

ORIGINAL  
(Red)

IT CORPORATION  
CEC Job No. 8695-47

Lab Number: 293592

Sample Description: R/8-1 Station #4, Back section: Chromosorb 102

Air Volume: Unknown

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
180	Toluene	0.2	*	*

\* No concentrations in ppm or micrograms/m<sup>3</sup> were calculated due to questionable air volumes; a sample mislabeling occurred in the field.

Results have been blank corrected.

AR100327

#6

ORIGINAL  
(Red)

Lab Number: 293593

Sample Description: R/8-2 Station #4, Front section: Tenax

Air Volume: Unknown

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
665	Butylated hydroxy toluene	< 0.2	*	*
747	Hydrocarbon	< 0.2	*	*
762	Trimethyl phenyl indane	0.3	*	*

\* No concentrations in ppm or micrograms/m<sup>3</sup> were calculated due to questionable air volumes; a sample mislabeling occurred in the field.

Results have been blank corrected.

AR100328

#6



ORIGINAL  
(Red)

Lab Number: 293593

Sample Description: R/8-2 Station #4, Back section: Chromosorb 102

Air Volume: Unknown

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
178	Toluene	< 0.2	*	*

\*No concentration in ppm or micrograms/m<sup>3</sup> were calculated due to questionable air volumes; a sample mislabeling occurred in the field.

Results have been blank corrected.

AR 10032 BA

Lab Number: 293594

Sample Description: K/18, Front section: Tenax

Air volume: 10.33 liters

Spectrum Number	Compound	(micrograms)	(ppm)	(micrograms/m <sup>3</sup> )
110	benzene	6.	0.2	600
137	C <sub>7</sub> H <sub>16</sub> hydrocarbon	0.4	0.01	40
185	Toluene	6.	0.2	600
209	C <sub>8</sub> H <sub>18</sub> hydrocarbon	0.4	0.009	40
254	Ethylbenzene	4.	0.08	300
260	Xylene	4.	0.08	400
277	{ Styrene	4.	0.08	300
	{ Xylene			
299	Methyl ethyl benzene	0.7	0.01	70
320	Phenylacetaldehyde	0.6	0.01	60
328	Acetophenone	3.	0.05	300
341	Methyl Styrene	0.3	0.005	30
	{ Benzonitrile			
349	{ Phenol	6.	0.1	600
	{ C <sub>9</sub> H <sub>12</sub> Alkylbenzene			
373	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	3.	0.06	300
384	Indene	0.9	0.02	80
394	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	<0.2	<0.004	<20
415	Dimethylstyrene	1.	0.02	100
453	{ Methyl indene	1.	0.02	100
	{ Ethyl styrene			
457	{ Methyl Indene	1.	0.02	100
	{ C <sub>11</sub> H <sub>16</sub> Alkylbenzene			
477	Naphthalene	5.	0.09	400
498	{ C <sub>11</sub> H <sub>14</sub> Hydrocarbon	0.6	0.01	60
	{ C <sub>12</sub> H <sub>18</sub> Alkylbenzene			
500	Benzothiazole	0.5	0.009	50
543	Methyl naphthalene	3.	0.01	300
552	Methyl naphthalene	2.	0.04	200
588	Biphenyl	2.	0.03	200
602	Dimethylnaphthalene	1.	0.01	100
612	Dimethylnaphthalene	2.	0.03	200
614	Acenaphthene	0.6	0.009	60
624	Acenaphthylene	1.	0.02	100
642	C <sub>13</sub> H <sub>12</sub> (Allylnaphthalene or methylbiphenyl)	1.	0.01	90
647	C <sub>13</sub> H <sub>12</sub> (Allylnaphthalene or methylbiphenyl)	0.8	0.01	80
666	C <sub>13</sub> H <sub>14</sub> Alkyl naphthalene	0.8	0.01	80
674	C <sub>13</sub> H <sub>14</sub> Alkyl naphthalene	0.5	0.006	40
683	C <sub>13</sub> H <sub>14</sub> Alkyl naphthalene	0.6	0.008	50
692	Fluorene	0.7	0.01	70
712	Dimethylbiphenyl	0.7	0.009	70
722	Unknown	0.3	0.004	30
740	Possible Hydrocarbon	0.4	0.005	40
743	Possible C <sub>17</sub> H <sub>18</sub>	0.5	0.005	40
764	Fluorenone	0.4	0.005	30
770	Dibenzothiophene	0.4	0.006	40
784	Anthracene and/or Phenanthrene	1.	0.02	100

Results have been blank corrected.

AR100329

ORIGINAL  
(Red)

IF CORPORATION  
CEC Job No. 8695-47

Lab Number: 293594  
Sample Description: K/18, Back section: Chromosorb 102  
Air volume: 10.33 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
28	Pentane	0.6	0.02	60
34	C <sub>5</sub> H <sub>8</sub> Hydrocarbon	8.	0.3	700
83	Cyclohexane	2.	0.07	200
<del>104</del>	<del>Benzene</del>	40	<del>0.07</del>	4000
123	Hydrocarbon (possible C <sub>8</sub> H <sub>18</sub> )	2.	0.03	200
140	C <sub>8</sub> H <sub>16</sub> Hydrocarbon	1.	0.02	90
146	C <sub>7</sub> H <sub>14</sub> Hydrocarbon	0.9	0.02	90
181	Toluene	3.	0.07	300
188	C <sub>8</sub> H <sub>16</sub> Hydrocarbon	1.	0.02	90

Results have been blank corrected.

ARI00330

ORIGINAL  
(Red)

IT CORPORATION  
CEC Job No. 8695-47

Lab Number: 293598

Sample Description: J/22, Front section: Tenax

Air volume: 4.99 liters

Spectrum Number	Compound	(micrograms)	(ppm)	(micrograms/m <sup>3</sup> )
103	Benzene	6.	0.4	1,000
182	Toluene	5.	0.3	1,000
253	Ethyl benzene	2.	0.09	400
261	Xylene	3.	0.1	500
276	( Styrene	2.	0.1	400
	( Xylene			
326	Acetophenone	1.	0.06	300
345	Benzonitrile	2.	0.08	300
349	C <sub>9</sub> H <sub>12</sub> alkylbenzene	1.	0.07	300
352	Methyl styrene	0.8	0.03	200
368	C <sub>9</sub> H <sub>12</sub> alkylbenzene	0.6	0.03	100
370	C <sub>10</sub> H <sub>14</sub> alkylbenzene	1.	0.04	200
377	Methyl styrene	0.7	0.03	100
	Hydrocarbon			
390	C <sub>10</sub> H <sub>14</sub> alkylbenzene	0.9	0.03	200
413	Ethyl styrene	0.6	0.02	100
451	Methylindene	0.4	0.02	80
455	Methylindene	0.6	0.02	100
476	Naphthalene	3.	0.1	600
540	Methyl naphthalene	1.	0.05	300
549	Methyl naphthalene	0.8	0.03	200
586	Biphenyl	0.9	0.03	200
599	Dimethyl naphthalene	0.4	0.01	80
610	Dimethyl naphthalene	0.9	0.03	200
623	Acenaphthylene	0.3	0.01	60
641	C <sub>13</sub> H <sub>12</sub> (allylnaphthalene or methyl biphenyl)	0.4	0.01	80
645	C <sub>13</sub> H <sub>12</sub> (allylnaphthalene or methyl biphenyl)	0.4	0.01	80
664	C <sub>13</sub> H <sub>14</sub> alkylnaphthalene	0.3	0.01	60
781	Anthracene and/or phenanthrene	0.8	0.02	200
859	C <sub>16</sub> H <sub>12</sub>	0.2	0.006	50
996	Unknown	0.5	0.009	90
1017	Benz(a)anthracene and/or chrysene	< 0.2	< 0.004	< 40

Results have been blank corrected.

AR10033#6

ORIGINAL  
(Red)

IF CORPORATION  
CEC Job No. 8695-47

Lab Number: 293598

Sample Description: J/22, Back section: Chromosorb 102

Air volume: 4.99 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
37	C <sub>5</sub> H <sub>8</sub> hydrocarbon	5.	0.4	1,000
106	Benzene	8.	0.5	2,000
122	C <sub>8</sub> H <sub>18</sub> hydrocarbon	0.6	0.3	100
185	Acetic Acid	8.	0.6	2,000
373	Hydrocarbon (possible C <sub>16</sub> H <sub>22</sub> )	0.5	0.02	100
386	Hydrocarbon (possible C <sub>10</sub> H <sub>22</sub> )	0.5	0.02	100

Results have been blank corrected.

AR100332#6

ORIGINAL  
(Red)

AT CORPORATION  
REC Job No. 8695-47

Lab Number: 293595

← Background

Sample Description: C-19, Front section: Tenax

Air volume: 9.16 liters

No significant compounds after blank correcting.

AR100333

#6

ORIGINAL  
(Red)

IT CORPORATION  
CIC Job No. 8695-47

Lab Number: 293595  
Sample Description: C-19, Back section: Chromosorb 102  
Air Volume: 9.16 liters

No significant compounds after blank correcting.

AR100334 #6

IT CORPORATION  
CEC Job No. 8695-47

ORIGINAL  
(Red)

Lab Number: 293599 ← *background*  
Sample Description: F/23, Front section: Tenax  
Air volume: 3.59 liters

No significant compounds after blank correcting.

AR100335 *HL*



ORIGINAL  
(Red)

IT CORPORATION  
CEC Job No. 8695-47

Lab Number: 293599

Sample Description: F/23, Back section: Chromosorb 102

Air volume: 3.59 liters

No significant compounds after blank correcting.

AR100336  
#6

Lab Number: 293596

Sample Description: R/20, Front section: Tenax

Air volume: 9.38 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
104	Benzene	2.	0.06	200
179	Toluene	1.	0.03	100
247	Ethylbenzene	0.5	0.01	50
253	Xylene	0.4	0.01	40
271	Styrene	3.	0.06	300
319	Acetopnenone	1.	0.03	100
340	Phenol	1.	0.03	100
342	Methylstyrene	2.	0.04	200
403	Ethylstyrene	3.	0.06	300
407	Ethylstyrene	1.	0.03	100
421	Methylindene	2.	0.04	200
427	Methylindene	0.8	0.02	80
451	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	0.6	0.01	60
465	C <sub>9</sub> H <sub>8</sub> O(Benzofuran or Vinyl benzaldehyde)	2.	0.03	200
473	Dimethylindene	0.7	0.01	80
526	Possible Phenylbutenone	0.9	0.02	100
739	Trimethyl phenyl indane	0.4	0.004	40

Results have been blank corrected.

AR1003376

IT CORPORATION  
EC Job No. 8695-47

ORIGINAL  
(Red)

id Number: 293596  
Sample Description: R/20, Back section: Chromosorb 102  
Air volume: 9.38 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
102	Benzene	5.	0.2	600
184	Acetic Acid	5.	0.2	500

Results have been blank corrected.

AR100338

ORIGINAL  
(Red)

IF CORPORATION  
CEC Job No. 8695-47

Lad Number: 293600  
Sample Description: E/24, Front section: Tenax  
Air volume: 13.55 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
101	Benzene	< 0.2	<0.005	<10

Results have been blank corrected.

AR100339 #6

ORIGINAL  
(Red)

IT CORPORATION  
CEC Job No. 8695-47

Lab Number: 293600

Sample Description: E/24, Back section: Chromosorb 102

Air volume: 13.55 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
41	Methylene Chloride	4.	0.08	300

Results have been blank corrected.

AR100340

Sample Description: Field Blank, Front section: Tenax

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>
40	Methylene Chloride	0.2
64	Hexane	< 0.2
143	Acetic Acid	< 0.2
178	Toluene	< 0.2
321	C <sub>9</sub> H <sub>12</sub> alkylbenzene	< 0.2
344	Trimethyl Benzene	0.2
365	Hydrocarbon	< 0.2
372	Hydrocarbon	0.2
384	Hydrocarbon	0.2
391	Hydrocarbon	< 0.2
652	Butylated hydroxy toluene	0.6
676	Di-tert butyl ethyl phenol	< 0.2
738	possible C <sub>17</sub> H <sub>18</sub>	0.2
748	Trimethyl phenyl indane	0.5

Results have been blank corrected.

AR100341#6

Sample Description: Field Blank, Back section, Chromosorb 102

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>
47	Methylene chloride	1.
71	Hexane	2.
104	( Benzene	0.2
	( Carbon tetrachloride	
178	Toluene	0.3
187	Acetic acid	0.9
256	Xylene	<0.2
272	Styrene	0.2
323	Benzaldehyde	0.5
346	Trimethyl benzene	0.2
408	Ethyl styrene	0.3
415	Methyl benzoate	0.4
459	C <sub>10</sub> H <sub>14</sub> alkylbenzene	0.3
999	Unknown	2.

Results have been blank corrected.

IF CORPORATION  
EC Job No. 8695-47

ORIGINAL  
(Red)

Sample Number: 293597

Sample Description: A/21, Front section: Tenax

Air volume: 41.49 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
100	Benzene	0.3	0.003	8.
177	Toluene	0.5	0.003	10.
250	Ethylbenzene	< 0.2	< 0.001	< 5.
255	Xylene	< 0.2	< 0.001	< 5.
271	Styrene	< 0.2	< 0.001	< 5.
467	Naphthalene	< 0.2	< 0.0009	< 5.

Results have been blank corrected.

AR100343

A-6



ORIGINAL  
(Red)

IT CORPORATION  
SEC Job No. 8695-47

Lab Number: 293597  
Sample Description: A/21, Back section: Chromosorb 102  
Air volume: 41.49 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
168	Toluene	0.9	0.006	20
302	Hydrocarbon (possible C <sub>8</sub> H <sub>18</sub> )	0.5	0.003	10
361	Hydrocarbon (possible C <sub>9</sub> H <sub>20</sub> )	0.9	0.004	20

Results have been blank corrected.

AR100344

#6

IT CORPORATION  
CEC Job No. 8695-47

Lab Number: 293601

Sample Description: I/25, Front section: Tenax

Air volume: 4.11 liters

<u>Spectrum Number</u>	<u>Compound</u>	<u>(micrograms)</u>	<u>(ppm)</u>	<u>(micrograms/m<sup>3</sup>)</u>
29	Trichlorofluoromethane	<0.2	<0.009	<50
103	Benzene	0.4	0.03	90
130	Toluene	0.3	0.02	70
253	Ethyl benzene	<0.2	<0.01	<50
259	Xylene	<0.2	<0.01	<50

Results have been blank corrected.

AR100345

#6

ORIGINAL  
(Red)

IT CORPORATION  
CEC Job No. 8695-47

Lab Number: 293601  
Sample Description: 1/25, Back section: Chromosorb 102  
Air volume: 4.11 liters

No significant compounds after blank correcting.

ARI00346

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGINAL  
(Red)

Results of Analyses  
for  
IT Corporation

Job No. 19859-17

Lab Number: 296310

Sample Description: R/11 Tenax Front Section

SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M <sup>3</sup>	PPM
--------------------	----------	------------	---------------------------	-----

No data for front section

Lab Number: 296310

Sample Description: R/11 Chromosorb 102 Back Section

SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M <sup>3</sup>	PPM
128	Benzene	<0.2	<20	<0.0

AR100347

#6

## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGINAL  
(Red)Results of Analyses  
for  
IT Corporation

Job No. 19859-17

Lab Number: 296311

Sample Description: J/12 Tenax Front Section


SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M <sup>3</sup>	PPM
130	Benzene	<0.2	<40	<0.01
221	Acetic Acid	0.2	30	0.01
430	Unknown	0.2	40	0.00
528	Nonanal	0.3	50	0.00
792	Unsaturated Hydrocarbons	0.3	50	0.00
961	Fatty Acid	0.3	50	0.01
984	Unknown	0.5	90	0.00
1064	Fatty Acid	0.3	60	0.00
1087	Unknown	0.2	40	0.00

Results have been blank corrected.

J/12 TENAX(2580)/IT CORP /11-28-83  
SEM DE54 10(2)-220 85/MIN

1550 SCANS (1200 SCANS, 39.62 MINS)

MASS RANGE: 29.0, 321.3 TOTAL ABUND= 2756286.



AR100348 #6

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGINAL  
(Red)

Results of Analyses  
for

IT Corporation

Job No. 19859-17

Lab Number: 296311

Sample Description: J/12 Chromosorb 102 Back Section

SPECTRUM  
NUMBER

COMPOUND

MICROGRAMS

MICROGRAMS/M<sup>3</sup>

PPI

No significant compounds detected

AR100349 #6

## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGINAL  
(Red)Results of Analyses  
for

IT Corporation

Job No. 19859-17

Lab Number: 296312

Sample Description: F/13 Tenax Front Section

<u>SPECTRUM NUMBER</u>	<u>COMPOUND</u>	<u>MICROGRAMS</u>	<u>MICROGRAMS/M<sup>3</sup></u>	<u>PPM</u>
128	Benzene	20	4,000	1
226	Toluene	20	4,000	1
313	Ethylbenzene	4	900	0.2
321	Xylene	5	1,000	0.2
341	{ Styrene Xylene	5	1,000	0.2
368	C <sub>9</sub> H <sub>12</sub> Alkylbenzene	0.7	100	0.03
393	Phenylacetaldehyde	0.7	200	0.03
403	C <sub>9</sub> H <sub>12</sub> Alkylbenzene	2	500	0.1
426	Benzonitrile	8	2,000	0.1
430	C <sub>9</sub> H <sub>12</sub> Alkylbenzene			
458	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	4	800	0.1
473	Indene	1	300	0.06
510	Dimethylstyrene	0.7	100	0.03
523	Tolunitrile	0.6	100	0.03
564	{ Methylindene C <sub>11</sub> H <sub>16</sub> Alkylbenzene	3	600	0.1
589	Naphthalene	7	1,000	0.3
593	Benzothiophene	0.9	200	0.03
670	Methylnaphthalene	3	700	0.1
681	Methylnaphthalene	3	600	0.09
728	Biphenyl	2	300	0.05
745	Dimethylnaphthalene	0.8	200	0.03
757	Dimethylnaphthalene	2	300	0.05
775	Acenaphthylene	0.7	100	0.02
797	Methylbiphenyl	0.8	200	0.02
802	Methylbiphenyl	0.6	100	0.02
826	C <sub>13</sub> H <sub>14</sub> Alkylnaphthalene	0.5	100	0.02
858	Fluorene	0.7	100	0.02

AR100350

#6

Results of Analyses  
for  
IT Corporation

Job No. 19859-17

Lab Number: 296312

Sample Description:  $\text{C}_{10}\text{H}_8$  Tenax Front Section (cont.)


SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M <sup>3</sup>	PPM
974	Anthracene &/or Phen- anthrene	1	300	0.04
1072	C <sub>16</sub> H <sub>12</sub> (probable Dibenzo- heptafulvene)	0.6	100	0.02
1115	Fluoranthene	0.3	60	0.007
1140	Pyrene	0.3	70	0.008

Results have been blank corrected.

F/13 TENAX(255C)/IT CORP/11-22-83  
255 CEE4-10(2)-200.95/MIN

1550 SCANS (1200 SCANS, 30.70 MIN)

MASS RANGE: 29.0, 321.2 TOTAL ABUND= 7385624.



AR100351

#6



CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGINAL  
(Red)

Results of Analyses  
for  
IT Corporation

Job No. 19859-17

Lab Number: 296312

Sample Description: F/13 Chromosorb 102 Back Section


RETENTION TIME	COMPOUND	MICROGRAMS	MICROGRAMS/M <sup>3</sup>	PP
4.6	{ C <sub>5</sub> H <sub>8</sub> Hydrocarbon C <sub>5</sub> H <sub>10</sub> Hydrocarbon	0.3	60	0.
1.1	Benzene	4	800	0.

Results have been blank corrected.

F/13 CHROMO 102(150C)/IT/11-23-83  
SEM DATA 10(29-298 06 MIN)

1236 SCANS (1236 SCANS, 29.92 MINS)

MASS RANGE: 29.8, 207.1 TOTAL ABUND= 2696540.



AR100352

#6

## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGINAL  
(Red)Results of Analyses  
for  
IT Corporation


Job No. 19859-17

Lab Number: 296313

Sample Description: B/14 Chromosorb 102 Back Section

SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M <sup>3</sup>	PPM
31	Benzene	20	2,000	0.6
22	Toluene	0.8	90	0.02

Results have been blank corrected.

B/14 CHROMO 102(1150C)/IT/11-20-83  
25M SES4 10121-230 05/MINSCAN 10300, TIME 7  
1243 SCAND (1242 SCAND, 35.92 MIN)  
MASS RANGE: 25.0, 201.2 TOTAL ABUND= 3870230.

AR100353

#6

Results of Analyses  
for  
IT Corporation

Job No. 19859-17

Lab Number: 296313 continued

Sample Description: B/14 Tenax Front Section


SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M <sup>3</sup>	PPM
668	Methyl Naphthalene	7	800	0.1
690	Methyl Naphthalene	3	400	0.06
725	Biphenyl	3	400	0.06
734	Ethyl naphthalene	1	200	0.03
742	Dimethylnaphthalene	1	200	0.03
755	Dimethylnaphthalene	3	300	0.05
772	Acenaphthylene	1	100	0.02
794	Methyl Biphenyl	1	200	0.02
799	Methyl Biphenyl	1	100	0.02
823	C <sub>13</sub> H <sub>14</sub> Alkyl naphthalene	1	100	
855	Fluorene	2	200	0.03
871	Anthracene and/or Fluoranthene	2	300	0.04
869	C <sub>16</sub> H <sub>12</sub> (probable Dibenzoheptafulene)	0.9	100	0.01

Results have been blank corrected.

B/14 TENAX(2580)/IT CORP/11-26-82  
25M CE54 10(2)-300 95/MIN

1550 SCANS (1200 SCANS, 30.77 MIN)

MASS RANGE: 29.0, 231.2 TOTAL ABUND= 10115950.



ARI00354

H6

## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGINAL  
(Red)Results of Analyses  
for

IT Corporation

Job No. 19859-17

Lab Number: 296314


Sample Description: A/19 Tenax Front Section

SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M <sup>3</sup>	PPM
274	Acetic Acid	0.3	20	0.008
523	Nonanal	<0.2	<20	<0.003
789	Probable Hydrocarbon	<0.2	<20	<0.002

Results have been blank corrected.

A/19 TENAX(2500)/IT CORP/11-22-83  
250 CE54 10(2)-200 06/MIN

P: 1.0

1551 SCANS (1200 SCANS, 30.70 MIN)  
MASS RANGE: 29.0, 299.3 TOTAL ABUND= 2304183.

AR100355 #6

Results of Analyses  
for

IT Corporation

Job No. 19859-17

Lab Number: 296314

Sample Description: A/19 Chromosorb 102 Back Section

SPECTRUM  
NUMBERCOMPOUNDMICROGRAMSMICROGRAMS/M<sup>3</sup>PPM

227

Acetic Acid

0.3

20


0.008

Results have been blank corrected.

A/19 CHROMO 102(1130)/IT/11-29-83  
25M SE54 10(21-232 35/MINERN 10001, 7  
1242 SCANS (1242 SCANS, 33.33 MIN)

1.0

MASS RANGE: 29.0, 281.2 TOTAL AREA= 2491054.



AR100356

#6

## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGINAL  
(Red)Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296140

Sample Description: A/1 Front, Tenax

SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M3	P
27	Sulfur Dioxide	0.2	20	0.
134	Benzene	4.	400	0.
234	Toluene	6.	700	0.
320	Ethylbenzene	1.	100	0.
329	Xylene	2.	200	0.
349	Styrene }	1.	200	0.
	Xylene			
377	C <sub>9</sub> H <sub>12</sub> Alkylbenzene	0.2	20	0.
404	Phenylacetaldehyde	0.2	20	0.
413	C <sub>9</sub> H <sub>12</sub> Alkylbenzene	0.6	70	0.
417	C <sub>9</sub> H <sub>12</sub> Alkylbenzene	0.2	20	0.
438	Benzonitrile }	1.	100	0.
	Phenol			
441	C <sub>9</sub> H <sub>12</sub> Alkylbenzene }	0.6	70	0.
	Methylstyrene			
444	Methylstyrene	0.3	30	0.0
465	C <sub>9</sub> H <sub>12</sub> Alkylbenzene }	0.4	40	0.0
	C <sub>10</sub> H <sub>14</sub> Alkylbenzene			
468	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	0.6	60	0.0
483	Indene	0.3	30	0.0
536	C <sub>8</sub> H <sub>7</sub> N	0.2	30	0.0
	(probable Tolunitrile)			
569	Methylindene }	0.3	30	0.0
	Dimethylstyrene			
575	Methylindene }	0.3	30	0.0
	C <sub>11</sub> H <sub>16</sub> Alkylbenzene			
603	Naphthalene	3.	300	0.0
606	Probable Benzothiophene	0.4	40	0.0

AR100357 #6

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGINAL  
(Red)

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296140 continued


Sample Description: A/1 Front, Tenax

SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M3	P
680	Methylnaphthalene	1.	100	0
692	Methylnaphthalene	0.7	80	0
737	Biphenyl	0.6	60	0
754	Dimethylnaphthalene	0.2	30	0
766	Dimethylnaphthalene	0.5	50	0
781	Acenaphthylene	0.3	30	0
803	Methylbiphenyl	0.2	30	0
809	Methylbiphenyl	0.2	20	0
833	C <sub>13</sub> H <sub>14</sub> Alkylnaphthalene	0.2	20	0
865	Fluorene	0.2	20	0
975	Anthracene and or Phenanthrene	0.5	50	0
1072	C <sub>16</sub> H <sub>12</sub> (possible Dibenzoheptafulrene)	0.2	30	0

A/1 TENAX THERMAL (2500)/IT CORP/11-23-83  
25M CE54 10(21)-239 810/MIN

1551 SCANS (1200 SCANS, 36.65 MIN)

MASS RANGE: 29.0, 293.3 TOTAL COUNT= 6729766.



AR100358

#6

ORIGINAL  
(Red)

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296140

Sample Description: A/1 Back, Chromosorb 102

<u>SPECTRUM NUMBER</u>	<u>COMPOUND</u>	<u>MICROGRAMS</u>	<u>MICROGRAMS/M3</u>	<u>PP</u>
101	Cyclohexane	<0.1	<10	<0.
133	Benzene	10	1000	0.
137	Thiophene	0.1	20	0.
227	Toluene	0.2	20	0.
251	Acetic Acid	0.1	10	0.
410	Benzaldehyde	<0.1	<10	<0.

A/1 CHROMO 102 T-EPHML:1520/IT CORP/11-23-83


1241 SCAND 11222 SCAND. 33.58 MIN-1

25M 2554 10(2)-252 35 MIN

1241 SCAND 11222 SCAND. 33.58 MIN-1

1.2

MASS RANGE: 29.0, 291.2 TOTAL FOUND= 3332222.



ARI00359

#6



ORIGINAL  
(Red)

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296141

Sample Description: E/4 Front, Tenax

<u>SPECTRUM NUMBER</u>	<u>COMPOUND</u>	<u>MICROGRAMS</u>	<u>MICROGRAMS/M3</u>	<u>PPM</u>
32	Sulfur Dioxide	0.2		
139	Benzene	5.	40	0.
232	Toluene	4.	1000	0.
317	Ethylbenzene	0.5	900	0.
325	Xylene	0.7	100	0.
345	Styrene	0.6	200	0.
375	C <sub>9</sub> H <sub>12</sub> Alkylbenzene	<0.1	200	0.
409	Acetophenone	0.3	<20	0.
431	Benzonitrile	0.5	80	0.
435	C <sub>9</sub> H <sub>12</sub> Alkylbenzene	0.3	100	0.
461	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	0.3	70	0.
477	Indene	0.3	70	0.
492	C <sub>9</sub> H <sub>12</sub> Alkylbenzene	0.1	30	0.
512	Ethylstyrene	0.2	50	0.00
528	C <sub>8</sub> H <sub>7</sub> N (probable Tolunitrile)	0.1 <0.1	30 <20	0.00 0.00
564	Dimethylstyrene }	0.1	30	0.00
569	Methylindene			
	Methylindene }	0.1	40	0.00
594	C <sub>11</sub> H <sub>16</sub> Alkylbenzene }			
599	Naphthalene	2.	400	0.07
602	Probable Benzothiophene	0.3	70	0.01
	C <sub>11</sub> H <sub>14</sub> (possible Dimethylindan	0.3	80	0.01
687	Methylnaphthalene Hydrocarbon			
703	Benzoic Acid Hydrocarbon			
762	Dimethylnaphthalene Methylbenzoic Acid	20.	5000	0.9

AR100360

ORIGINAL

## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296141 continued

Sample Description: E/4 Front, Tenax


<u>SPECTRUM NUMBER</u>	<u>COMPOUND</u>	<u>MICROGRAMS</u>	<u>MICROGRAMS/M3</u>	<u>PI</u>
776	Benzamide	1.	300	0.
783	Possible Methyl- benzamide	0.7	200	0.
975	Anthracene and or Phenanthrene	0.5	100	0.
1036	Probable Methyl- phenanthrene	0.1	20	0.
1049	Probable Methyl- anthracene	0.1	20	0.
1072	C <sub>16</sub> H <sub>12</sub> (possible Dibenzoheptafuluene)	0.5	100	0.
1113	Fluoranthene	0.1	30	0.0
1138	Pyrene	0.1	30	0.0

E/4 TENAX THERMAL (2500)/IT CORP/11-23-83

25M SE54 10(21-200) 45/MIN

1533 SCANS (1500 SCANS, 40.88 MIN)

MASS RANGE: 29.0, 396.4 TOTAL ABUND= 8363354.



AR100361#6

ORIGINAL  
(Red)

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296141


Sample Description: E/4 Back, Chromosorb 102

<u>TRUM NUMBER</u>	<u>COMPOUND</u>	<u>MICROGRAMS</u>	<u>MICROGRAMS/M3</u>
36	C <sub>4</sub> H <sub>8</sub> Hydrocarbon Sulfur Dioxide }	<0.1	<20
140	Benzene	2.	500
244	Acetic Acid	0.4	100
409	Benzaldehyde	0.1	20

E/4 CHROMO 102 THERMAL (150C)/IT CORP/11-23-83  
25M CE54 10(2)-200 06/MIN

1242 SCANS (1200 SCANS, 38.55 MIN)

MASS RANGE: 29.0, 200.1 TOTAL ABUND= 2481026.



AR100362 #6

ORIGINAL  
(Red)

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296142

Sample Description: R/2 Front, Tenax

← BACKGROUND

SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M3
523	Nonanal	0.1	10
602	Decanal	<0.1	<10
847	Possible Lauric Acid	0.1	10
957	Myristic Acid	0.2	20
1056	Possible Palmitic Acid	<0.1	<10


R/2 TENAX THERMAL (2500)/IT CORP/11-23-83  
25M CE54 10(2)-380 @6/MIN

1545 SCANS (1200 SCANS, 32.00 MIN)

ERN 9505, 6

1.0

MASS RANGE: 29.0, 293.3 TOTAL ABUND= 2139723.



AR100363

#6

ORIGINAL  
(Red)

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296142

Sample Description: R/2 Back, Chromosorb 102

<u>PEAK NUMBER</u>	<u>COMPOUND</u>	<u>MICROGRAMS</u>	<u>MICROGRAMS/M3</u>
401	Benzaldehyde	0.1	10
569	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	<0.1	<10

PE 10-1000 102 THERMAL/11-23-92


BY CEE4 12(2)-222 66/MIN

11-23-92 11-23-92

11-23-92 11-23-92 11-23-92

1.2

11-23-92 11-23-92 11-23-92



AR100364

46

ORIGINAL  
(red)

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296143

← BACKGROUND

Sample Description: J/3 Front, Tenax

<u>RETENTION NUMBER</u>	<u>COMPOUND</u>	<u>MICROGRAMS</u>	<u>MICROGRAMS/M3</u>
341	Styrene	<0.1	<20
403	Benzaldehyde	<0.1	<20
492	Acetophenone	<0.1	<20
508	Ethylstyrene	<0.1	<20
523	Nonanal	<0.1	<20
785	Unsaturated Hydrocarbon	<0.1	<20
914	Hydrocarbon	<0.1	<20
977	Hydrocarbon and Unknown	<0.1	<20
1385	Unknown	0.6	120
1402	Unknown	1.	200
1425	Unknown	3.	600


J/3 TENAX THERMAL (25001)/IT CORP/11-23-83

25M CE54 10(21)-200 06/MIN

1534 SCANS (1500 SCANS, 48.78 MIN)

1.0

MASS RANGE: 29.0, 397.3 TOTAL ABUND= 3019279.



AR100365

ORIGINAL  
(Red)

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17

Lab Number: 296143

Sample Description: J/3 Back, Chromosorb 102

<u>PEAK NUMBER</u>	<u>COMPOUND</u>	<u>MICROGRAMS</u>	<u>MICROGRAMS/M3</u>	<u>F</u>
408	Benzaldehyde	0.1	30	0
575	C <sub>10</sub> H <sub>14</sub> Alkylbenzene	<0.1	<20	<0

J/3 CHROMO 102 THERMAL (150C)/IT CORP/11-23-83


25M CEE4 10/21-200 65/MIN

DATE 9507, PAGE 6

1243 SCANS (1200 SCANS, 33.53 MIN)

1.0

MASS RANGE: 29.0, 207.1 TOTAL REUND= 2119146.



ARI00366

# CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGIN  
(Red)

Results of Analyses  
for  
IT Corporation

Job No. 19859-17

Lab Number: 296315


Sample Description: Blank Chromosorb 102 Back Section

SPECTRUM NUMBER	COMPOUND	MICROGRAMS	MICROGRAMS/M <sup>3</sup>
150	C <sub>8</sub> H <sub>18</sub> Hydrocarbon	0.2	--
225	Toluene	<0.2	--

CLIENT BLANK CHROMO 102 (1500) / IT/11-20-83  
25N CES4 10(2)-200 06/RIN

1.0

1246 SCANS (1246 SCANS, 39.32 MIN)  
NACC RANGE: 29.0, 207.1 TOTAL ABUND= 1967001.



AR100367



# CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIG  
(R)

Results of Analyses  
for

IT Corporation

Job No. 19859-17

Lab Number: 296315

Sample Description: Blank Tenax Front Section

SPECTRUM  
NUMBER

COMPOUND


MICROGRAMS

MICROGRAMS/M<sup>3</sup>

90	Hexane	0.2	--
104	Chloroform	0.6	--
156	C <sub>8</sub> H <sub>18</sub> Hydrocarbon	1.	--
229	Toluene	0.3	--
269	Tetrachloroethylene	0.6	--

BLANK/IT CORP.-TENAX/THERMAL (250°C) 11/28/83  
254,25K 10(21)-222 16/MIN.

1553 SCANS (1500 SCANS, 40.25 MIN)  
MASS RANGE: 29.0, 281.2 TOTAL ABUND= 2269729.



AR100368

H/6

# CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

ORIGI  
(Rec)

Results of Analyses  
for

IT Corporation

CEC Job No. 19842-17


Lab Number: 296144

Sample Description: Blank, Front, Tenax

SPECTRUM NUMBER	COMPOUND	MICROGRAMS
260	Acetic Acid	
520	Cresol	0.4
576	Dimethylphenol	1.
593	Ethylphenol	0.5
802	Alkylbenzene	0.6
	Unsaturated Hydrocarbon	<0.1
805	Hydrocarbon	
	Unsaturated Hydrocarbon	
840	Unsaturated Hydrocarbon	0.1
929	Unsaturated Hydrocarbon	0.1
940	Hydrocarbon	0.1
1004	Hydrocarbon and Unknown	0.1
	Unknown	0.2
1149	Unknown	
1267	Unknown	5.
1378	Unknown	7.
		6.

143 TENAX BLANK/THERMAL 92580/11-23-83  
25M CEE4 10121-288 95/MIN

1556 SCANS (1500 SCANS, 49.13 MIN)  
MASS RANGE: 29.0, 396.4 TOTAL ABUND= 6184695.



Blank was broken in transit; chromosorb 102 section was lost.

AR100369

**WESTON • SPER**ERT - Edison  
300 McGaw Drive - 2nd Floor, Raritan Center  
Edison, NJ 08837 • (201) 225-6266TECHNICAL ASSISTANCE TEAM FOR EMERGENCY RESPONSE REMOVAL AND PREVENTION  
EPA CONTRACT 68-01-6669MEMORANDUM

TO: Rodney Turpin, ERT

FROM: Philip R. Campagna, ERT/TAT


SUBJECT: Air Sampling and Monitoring At Rhinehart Tire Fire  
in Winchester, VA. (TDD# 12-8311-02)

DATE: November 29, 1983

11/08/83

897/14 Station #1. Volume of air sampled (0.55 l/min for 117 min) = 64.35 l. TWA  
methane =  $(120)(0.3)/(64.35) = 0.56$  ppm. GC: 12 peaks observed Rt. = 0.1, 0.3, 0.6, 1.0, 1.4, 2.7, 3.4, 4.2, 7.2, 11.4 and 14.3 cms.

RUSTRAK




Roy F. Weston, Inc.

SPILL PREVENTION &amp; EMERGENCY RESPONSE DIVISION


In Association with Jacobs Engineering Group Inc., Tetra Tech, Inc., and ICF Incorporated

AP-00370

894/15 Station #3 (Background). Volume of air sampled (0.5 l/min for 160 min) = 83  
TWA as methane =  $(1.0)(0.3)/(83) = 0.003$  ppm. GC one peaked observed Rt = 0.3 cms.



865/16 Station #4. Volume of air sampled (0.5 l/min for 135.4 min) = 67.7 l. TWA  
methane =  $(0.7)(0.3)/67.7 = 0.003$  ppm. GC 2 peaks observed Rt = 0.1 and 0.3 cms.




AR100371

DTT # 2


-3-

11/04/83

866/42 Station #1. Volume of air sampled (54.4 min at 0.4 l/min) = 22.96 l. TWA methane  $(70)(0.3)/(22.96) = 0.914$  ppm. GC 10 peaks observed Rt = 0.05, 0.1, 0.3, 0.85, 1.3, 3.7, 9.5, 10.0 and 12.1 cms.



886/41 Station #4. Volume of air sampled (180 min at 0.4 l/min) = 72 l. TWA as methane =  $(4.8)(0.3)/(72) = 0.02$  ppm. GC 4 peaks observed Rt = 0.1, 0.3, 1.2, and cms.



STYLE A

R 2279

AR100372

72 #5

865/43 Station #5. Volume of air sampled (180 min at 0.5 l/min) = 90 l. TWA as methane =  $(10)(0.3)/(90) = 0.033$  ppm. GC 5 peaks observed Rt = 0.1, 0.2, 0.3, 1.2, 3.1 cms.

RUSTRAK

PRINTED IN U.S.A.

STYLE A

RUSTRAK

ARI00373

H. #7

ORIGIN  
(Red)

RHINEHART TIRE FIRE 11/03/83 And 11/04/83

Station #	ERT 2-Stage Sample# (Volume in liter)	MCEF 0.45 u Sample# (Volume in Liter)	600 mg Carbon Sample# (Volume Liter)	3 Stage Mill Sample# (Vo in liter)
11/03/83				
1	J/1 (6.16) A/5 (11.66)	848/11 (552)		
3	F/4 (4.36) C/7 (10.71)	888/13 (588.8)		
4	E/3 (2.69) R/8 (7.14)	889/10 (307.5)		
11/04/83				
1	K/18 (10.33) J/22 (4.99)	889/31 (414)	892/29 (360)	882/38 (163.
3	C/19 (9.16) F/23 (3.59)	890/35 (414)	864/28 (360)	857/37 (360)
4	R/20 (9.38) E/24 (13.55)	887/30 (414)	893/26 (360)	881/40 (360)
5	A/21 (41.49) I/25 (4.11)	888/36 (414)	858/27 (360)	878/39 ( )
1 off		848/32 (395.4)	893/47 (344.6)	857/52 (347)
2 off		890/44 (319.6)	864/48 (318.4)	878/51 9320)

AR100374

The sediment samples were also all in the pH range of 6.0 to 7.0. The 2:1 dilution scheme compounded by the 5:1 extraction scheme resulted in the following test sample concentrations; 1.2%, 2.3%, 4.5%, and 9.0%. Samples were also rated under the same guidelines established in the aqueous samples. It should be noted that not every aqueous sample had a corresponding sediment sample.

<u>Sample</u>	<u>Rating</u>	<u>Response</u>
1832	Clean	Responses up to 11.3%
1837	Clean	Responses up to 10.2%
1836	Clean	Responses up to 11.6%
1830	Moderate	Responses up to 16.1%
1833	Moderate	Responses up to 17.7%
1831	Moderate	Responses up to 20.3%
1835	Significant	Responses up to 32.0%
1834	Significant	Responses up to 70.8%

Comparison of the sediment and soil samples displayed some significant trends. Both sediment and aqueous samples 1834 and 1835 displayed, respectively, the highest and second highest microtox NPLD responses. Aqueous sample 1833 displayed a significant Microtox response with the corresponding 1833 sediment sample displaying a decreased moderate response; owing to a greater dilution test scheme in the sediment sample. This similar trend was also evident in sample 1832 which displayed a moderate response for the aqueous sample and a clean response for the sediment sample. Samples 1836, 1837 displayed clean responses in both sample categories. Sample 1831 gave somewhat inconsistent results in that the aqueous sample displayed a clean response while the corresponding sediment sample displayed a moderate response. It may be possible that the higher response of the sediment sample might be owing to the extraction/washing any contaminants from the granular sediment sample.

AR100375



APPENDIX D

GROUNDWATER STUDY PLAN

RHINEHART TIRE FIRE  
Winchester, Virginia

JANUARY, 1983



ENVIRONMENTAL RESPONSE TEAM  
WOODBIDGE AVENUE, EDISON, NEW JERSEY

AR100376

IT ENVIROSCIENCE, INC. Ground Water Monitoring Program

**IT ENVIRONMENT, INC.**


DESCRIPTION OF WORK	January												February												PROJECT SCHEDULE												ORIGINAL (Red)	
	23	24	25	26	27	28	29	30	31	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25				
well drilling	A																																					
sampling - Water	B																																					
surveying (optional)	C																																					
analysis - Water	D																																					
job report																																						
final report																																						
travel																																						
REMARKS: A - Drilling commenced on Jan 3, 1984 B - Virginia Water Control Board 4-6 weeks for results C - same as above D - All data to date compiled and draft report prepared while awaiting water results																																						
MADE BY: T. Stone DATE: 2/8/84 LAST REV. DATE: 12/16/83 1st revision																																						
FOR: Rhinehart Tire Fire Winchester Virginia 0117 FD																																						

DRAFT

Site Name: \_\_\_\_\_

Location: \_\_\_\_\_

Date: \_\_\_\_\_



REQUIREMENTS:

1. The contractor is responsible for obtaining all permits or licenses required by state or local governing authorities.

AR100378

2. Oversize borehole, minimum four (4) inches greater than casing diameter drilled through overburden and casing sealed ten (10) feet into competent rock unless shown otherwise above.
3. Approved high grade sodium base, well sealant type, granular bentonite must be used to seal casing. Casing sealant and drilling fluids must be mixed with potable water.
4. Well must be developed upon completion for a minimum of one (1) hour or to yield a turbid-free discharge.
5. The driller must maintain an accurate written log of all materials encountered in each hole, record all construction details for each well, and record the depth of major water bearing fracture zones. This information must be submitted to the IT project manager within one week of the job completion.
6. Cement collar must be installed a minimum of one (1) hour after casing seal has been emplaced.
7. Locking caps must be provided to secure each well.

ADDITIONAL REQUIREMENTS (IF CHECKED):

- ☐ 1. Split Spoon Samples (In Overburden) \_\_\_\_\_
- ☐ 2. Rock Core Samples \_\_\_\_\_
- ☐ 3. Dedicated Bailer (Sampler) in Well(s) \_\_\_\_\_
- ☐ 4. Borehole Geophysical Log(s) \_\_\_\_\_
- ☐ 5. Other \_\_\_\_\_

\* MODIFICATION OF THIS SPECIFICATION MUST BE APPROVED BY THE IT PROJECT MANAGER PRIOR TO IMPLEMENTATION.

Rev 12/83 TS (Modified from NJDEP)

dlg/0349D

AR100379

RHINEHART TIRE FIRE 11/22/83

Station #	ERT 2-Stage Sample# (Volume in liter)	MCEF 0.45 u Sample# (Volume in Liter)	600 mg Carbon Sample# (Volume Liter)	3 Stage Sample# in liter)
1 am	A/1 (9.02) E/4 (4.04)	865/6 (348)	887/7 (360)	868/9 (270)
pm	F/13 (4.8) B/14 (8.79)	889/5 (360)	888/17 (360)	889/16 (270)
3 am (Bckgrnd)	R/2 (10.14) J/3 (5.00)	889/5 (360)	888/8 (360)	886/10 (303.8)
pm	A/19 (14.92)	865/21 (360)	887/22 (360)	868/10 (270)
6 pm (Decon)	R/11 (11.02) J/12 (5.52)	861/18 (421.2)		

AR100380

17

ORIGINAL  
(Red)

APPENDIX B

WATER QUALITY DATA

RHINEHART TIRE FIRE  
Winchester, Virginia

NOVEMBER 3 to DECEMBER 19, 1983

VIRGINIA WATER QUALITY BOARD  
RICHMOND, VIRGINIA

AR100381

ORIGINAL  
(Red)



# COMMONWEALTH of VIRGINIA

## STATE WATER CONTROL BOARD

Richard N. Burton  
Executive Director

Post Office Box 11143  
Richmond, Virginia 23230  
(804) 257 0056

Valley Regional Office  
116 North Main Street  
P.O. Box 268  
Bridgewater, Virginia 22812  
(703) 828-2595

17 January 1984

BOARD MEM:  
John H. Arai  
Chairman  
Patrick L. Star  
Vice Chair

Watkins M. Abt  
Joseph S. Cragg  
David H. Mi  
Millard B. Ric  
Robert C. Win

Mr. Darius C. Ostrauskos  
Environmental Scientist -  
Super Fund Branch  
U.S. Environmental Protection Agency  
Region III  
6th and Walnut Streets  
Philadelphia, Pennsylvania 19106

Dear Mr. Ostrauskos:

Attached are copies of lab data on water samples taken at the Tire Fire site in Frederick County. The data was performed by the State Lab. Please note that the date which the lab received the samples is the next day following the sampling.

These are all of the data which I have. As more is received, a copy will be forwarded.

Very truly yours,

R. F. Tesh, Director  
Division of Surveillance  
and Field Studies

Jes

Attachment

cc: VRO File

Harry Allen  
EPA-ERT

Raritan Depot, Bldg. 10, Woodbridge Ave.  
Edison, NJ 08837

An Affirmative Action/Equal Opportunity Employer

AR100382

ORIGINAL  
(Red)

## CERTIFICATE OF ANALYSIS

November 28, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 22312

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-04-83

Identification No.:

Lab #: 10583-10587

11/3/93  
Q-2

Submitted By: Dave Chance

Analyst: James C. Peterson, Ph.D.

## Description:

- 10583--Unnamed tributary to Hogue Creek  
Upper portion unnamed tributary--pool of collected product  
10584--Unnamed tributary to Hogue Creek  
Free flowing stream upper portion, just above big pool of product ✓  
10585--X-tributary Hogue Creek  
Lower portion unnamed tributary from fire site  
10586--Hogue Creek Control  
Hogue Creek just above confluence with unnamed tributary from fire site  
10587--Hogue Creek  
Hogue Creek downstream from confluence with unnamed tributary from fire site

Results:	01?	04?	03	02
Priority Pollutants	10584	10585	10586	10587
Benzene	0.9ug/L	1.3ug/L	0.3ug/L	0.5ug/L
Toluene	1.7ug/L	2.3ug/L	<0.2ug/L	<0.2ug/L
Ethylbenzene	4.6ug/L	1.2ug/L	0.8ug/L	<0.2ug/L
Xylenes	2.4ug/L	0.6ug/L	<0.2ug/L	<0.2ug/L
Naphthalene	30 ug/L	10 ug/L	<1 ug/L	<1 ug/L
Fluorene	13 ug/L	4.6ug/L	<1 ug/L	<1 ug/L
Phenanthrene	4.1ug/L	2.0ug/L	<1 ug/L	<1 ug/L
Caprolactam	13 mg/L	4.8mg/L	140 ug/L	210 ug/L

## Other Components Identified in 10584, 10585, 10586, 10587:

Benzonitrile, Acetophenone, Tolunitrile, Phthalonitrile, Benzothiazole,  
Methyl benzothiazole, 1-methyl naphthalene, C<sub>3</sub> benzenes, C<sub>4</sub> benzenes

Sample 10583 was redundant with 10584 and was not analyzed.

STATE OF VIRGINIA  
CITY/COUNTY OF \_\_\_\_\_

to-wit:

THIS day personally appeared before me \_\_\_\_\_ a notary public, in and for said city/count

Commonwealth of Virginia, \_\_\_\_\_ who signed the foregoing Certificate of Analysis, before me, and after being duly sworn, made  
that he performed the analysis and/or examination the results of which are herein contained, (2) that said analysis and/or examination was performed in a laboratory of  
by the Division of Consolidated Laboratory Services of the Commonwealth or authorized by such Division to conduct such analysis and/or examination and (3) that if  
tificate of Analysis is true and correct.

Given under my hand this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_

My commission expires \_\_\_\_\_, 19\_\_\_\_

Notary

Page 1 of 1

AR100383





Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

November 28, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 22312

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-14-83

Identification No.:

Lab #: S83-695 through S83-700

Submitted By: Ray Miller

Analyst: James C. Peterson, Ph.D.

Description:

S83-695 -- Site 01, tributary  
S83-696 -- Site 02, downstream  
S83-697 -- Site 03, upstream  
S83-698 -- Site 03a, upstream  
S83-699 -- Site 04, confluence  
S83-700 -- VOA blank

Results:

Priority Pollutants

	01 695	02 696	03 697	03a 698	04 699	5 700
Benzene	1.5ug/L	0.3ug/L	no volatile sample	<0.2ug/L	no volatile sample	<0.2ug/L
Toluene	3.3ug/L	0.3ug/L		<0.2ug/L		<0.2ug/L
Ethylbenzene	9.1ug/L	0.2ug/L		<0.2ug/L		<0.2ug/L
Xylenes	7.6ug/L	0.3ug/L		<0.2ug/L		<0.2ug/L
Naphthalene	56 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	<1 ug/L	<1 ug/L
Acenaphthalene	22 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	1.0ug/L	<1 ug/L
Acenaphthene	26 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	1.6ug/L	<1 ug/L
Fluorene	13 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	<1 ug/L	<1 ug/L
Phenanthrene	6 ug/L	<1 ug/L	< 1ug/L	<1 ug/L	<1 ug/L	<1 ug/L
Caprolactam	8.5mg/L	1.6mg/L	140ug/L	<1 ug/L	9.0mg/L	<1 ug/L

Other Components Identified in 695, 696, 699:

Benzonitrile, Acetophenone, Tolunitrile, Benzothiazole, Methylbenzothiazole,  
1-methyl naphthalene, C<sub>3</sub> benzenes, C<sub>4</sub> benzenes

STATE OF VIRGINIA  
CITY/COUNTY OF \_\_\_\_\_

to-wit:

THIS day personally appeared before me \_\_\_\_\_

a notary public, in and for said city/county of \_\_\_\_\_

Commonwealth of Virginia, \_\_\_\_\_ who signed the foregoing Certificate of Analysis, before me, and after being duly sworn, made oath that he performed the analysis and/or examination the results of which are herein contained, (2) that said analysis and/or examination was performed in a laboratory operated by the Division of Consolidated Laboratory Services of the Commonwealth or authorized by such Division to conduct such analysis and/or examination and (3) that this Certificate of Analysis is true and correct.

Given under my hand this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_

My commission expires \_\_\_\_\_, 19\_\_\_\_

Page 1 of 1



Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

November 28, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 22312

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-17-83

Identification No.:

Lab #: S83-722-724

11/16/83  
Q=9.7 d

Submitted By: Ray Miller

Analyst: James C. Peterson, Ph.D.

Description: unnamed trib  
S83-722--Site 01, Masey Run  
S83-723--Site 02, Hogue Creek  
S83-724--Site 02a, Rt. 614 bridge

Results:  
Priority Pollutants (Volatiles Only)

	<u>722</u>	<u>723</u>	<u>724</u>
Benzene	1.1ug/L	<0.2ug/L	<0.2ug/L
Toluene	7.2ug/L	0.2ug/L	<0.2ug/L
Ethylbenzene	13.4ug/L	0.2ug/L	<0.2ug/L
Xylenes	26.9ug/L	0.5ug/L	<0.2ug/L

STATE OF VIRGINIA  
CITY/COUNTY OF \_\_\_\_\_ to-wit:

THIS day personally appeared before me \_\_\_\_\_ a notary public, in and for said city/county in

Commonwealth of Virginia, \_\_\_\_\_ who signed the foregoing Certificate of Analysis, before me, and after being duly sworn, made oath that he performed the analysis and/or examination the results of which are herein contained, (2) that said analysis and/or examination was performed in a laboratory operated by the Division of Consolidated Laboratory Services of the Commonwealth or authorized by such Division to conduct such analysis and/or examination and (3) that this Certificate of Analysis is true and correct.

Given under my hand this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_

My commission expires \_\_\_\_\_, 19\_\_\_\_

Notary Public



Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

December 5, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 23212

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-18-83

Identification No.:

RECEIVED

DEC 6 1983

Lab #: S83-770-772

Submitted By: Ray Miller, SWCB

BY

NORTHERN REGIONAL  
OFFICE

Analyst: M. E. Martin  
Mike Martin

Description:

S83-770: Site 01, water from pool on *unnamed trib* ~~Massey Run~~  
S83-771: Site 02, water, 100 yards downstream of confluence of *unnamed trib* ~~Massey Run~~  
and Hogue Creek  
S83-772: Site 02A, water at Rt. 614 bridge, Hogue Creek

Request: Volatile priority pollutants

Results:

Priority Pollutants	01 770	02 771	010 772
Benzene	2.0ug/L	<0.2	<0.2
Toluene	5.1	<0.2	<0.2
Ethyl benzene	6.0	0.8	<0.2
Xylenes	18.1	<0.2	<0.2

RECEIVED  
DEC 14 1983

VALLEY REGIONAL  
OFFICE



Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

December 5, 1983

TO: Ray Tesh  
State Water Control Board  
Northern Regional Office  
5515 Cherokee Avenue, Suite 404  
Alexandria, VA 23212

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-21-83

Identification No.:

RECEIVED

DEC 5 1983

Lab #: S83-767-769

Submitted By: Ray Miller, SWCB

BY  
NORTHERN REGIONAL  
OFFICE

Analyst:

M. E. Martin  
Mike Martin

Description:

S83-767: Site 01, water from pool on ~~Massey Run~~ *unnamed trib*

S83-768: Site 02, water, 100 yards downstream of confluence with ~~Massey Run~~ *unnamed trib*  
on Hogue Creek

S83-769: Site 02A, water at Rt. 614 bridge, Hogue Creek

Request: Volatile priority pollutants

Results:

Priority Pollutants	<sup>01</sup> 767	<sup>02</sup> 768	<sup>02A</sup> 769
Benzene	0.5ug/L	0.2	<0.2
Toluene	1.1	<0.2	<0.2
Ethyl benzene	3.5	<0.2	<0.2
Xylenes	3.3	<0.2	<0.2

RECEIVED

DEC 22 1983

NORTHERN REGIONAL  
OFFICE



Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

December 22, 1983

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 11-30-83

Identification No.:

Lab #:

Submitted By: REM

Analyst: J. C. Peterson, Ph.D.

Description:

11178, 11187: Station 01, approximately 1500 ft. upstream of confluence with Hogue  
11179, 11188: Station 02, 100 yds. downstream of confluence with Maxey Run  
11180, 11192: Station 02A, at Rt. 614 bridge (gauging station) *unmarked tr. D.*

Results:

Priority Pollutants

	01	02	02A
Benzene	5.1 ug/L	<0.2ug/L	0.2 ug/L
Toluene	10.9	0.3	<0.2
Ethyl benzene	1.9	1.0	1.7
Xylenes	5.9	<0.2	<0.2
Naphthalene	20.	<1.	<1.
Phenol	460.	6.8	1.0

No other priority pollutants were detected (Limit of Detection = 0.2 to 5ug/L)

Other Contaminants\*

2(2-n-butoxyethoxy)ethanol	9.7 mg/L	110. ug/L	23. ug/L
benzothiazole	380. ug/L	2.7ug/L	3.7 ug/L
caprolactam	12.9 mg/L	110. ug/L	84. ug/L
2-methylbenzothiazole	180. ug/L	1.2ug/L	2.3 ug/L
Benzoic Acid	10. mg/L	16.6ug/L	1.5 ug/L

\*Confirmed by GC/MS with authentic standards.

Other major contaminants identified by GC/MS, not yet confirmed with authentic standards: phenylisocyanate, hexanedinitrile, N,N dimethylbenzamide, 3-methylbenzoic acid, cyanobenzoic acid.

RECEIVED  
JAN 6 1984

VALLEY REGIONAL  
OFFICE



Department of General Services  
Division of Consolidated Laboratory Services

ORIGINAL  
(Red)

CERTIFICATE OF ANALYSIS

December 23, 1983

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: 12-07-83

Identification No.:

Lab #:

12/6/83  
Q-40

Submitted By: REM, D. Wright

Analyst: J. C. Peterson, Ph.D.

Description:

11400, 11404, 11408: Station 01, approximately 1500 ft. upstream of confluence with Hogue Creek  
11401, 11405, 11409: Station 02, 100 yds. downstream of confluence with Massey Run  
11402, 11406, 11410: Station 02A, at Rt. 614 bridge (gauging station)  
11399, 11403, 11407: Rhinehart's Pond (R.P.)

Results:

Priority Pollutants	R.P.	01	02	02A
Benzene	141 ug/L	4.7 ug/L	0.5 ug/L	1.1 ug/L
Toluene	171	9.4	0.7	<0.2
Ethylbenzene	112	7.6	0.5	<0.2
Xylenes	88	7.1	0.4	<0.2
Naphthalene	100	14	2.0	1.1
Acenaphthylene	350 ppb	51	3.2	<2
Phenol	2.7 mg/L	260	5.1	<2

No other priority pollutants were detected (Limit of Detection: 0.2 to 5ug/L)

Other Contaminants\*

2(2-n-butoxyethoxy)ethanol	9.7 mg/L	1.6 mg/L	190 ug/L	100 ug/L
benzothiazole	2.2 mg/L	320 ug/L	49 ug/L	30 ug/L
caprolactam	66 mg/L	11 mg/L	340 ug/L	210 ug/L
2-methylbenzothiazole	560 mg/L	230 ug/L	16 ug/L	11 ug/L
benzoic acid	27 mg/L	8.8 mg/L	200 ug/L	<2 ug/L

\*confirmed by GC/MS with authentic standards

Other contaminants identified by GC/MS, not yet confirmed with authentic standards:  
phenylisocyanate hexanedinitrile, N,N dimethylbenzamide, 3-methylbenzoic acid,  
cyanobenzoic acid.

RECEIVED



Department of General Services  
Division of Consolidated Laboratory Services

CERTIFICATE OF ANALYSIS

December 22, 1983

ORIGINAL  
(Red)  
taken

TO: Ray Tesh  
Valley Regional Office  
State Water Control Board  
P. O. Box 268  
Bridgewater, VA 22812

1 N. 14th Street  
Richmond, Virginia 23219  
Contact Tel. No. 786-4898

Date Received: December 13-14, 1983

Identification No.:

Lab #: 134-151, 152, 153, 148,  
150, 149

Submitted By:

Analyst: J. C. Peterson

Description:

11704, 11708 Donald Swaner well 134-151 ✓  
11705, 11709 Robinson well 134-152 ✓  
11706, 11710 W. T. Rhinehart well 134-153  
11628, 11629 Rhinehart spring 134-148  
11631-11632 Palmer well 134-150  
11634-11635 Pigeon well 134-149 PC84-196

RECEIVED  
DEC 29 1983

VALLEY REGIONAL  
OFFICE

Results:

Priority Pollutants	134-151	152	153	148	150	149
Benzene	<0.2ug/L	<0.2	<0.2	<0.2	<0.2	<0.2
Toluene	0.8	0.3	<0.2	<0.2	<0.2	<0.2
Ethyl benzene	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
Xylenes	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
Naphthalene	<1	<1	<1	<1	<1	<1

No other priority pollutants were detected (Limit of Detection = 0.2 to 5ug/L)

No non-priority pollutant tire fire constituents normally found in Hogue Creek and Massey Run were detected in these well waters. (Limit of Detection = 1 to 10ug/L)

STATE OF VIRGINIA  
CITY/COUNTY OF

Richmond to-wit:

J. C. Peterson

THIS day personally appeared before me Helen Sherris a notary public, in and for said city/court

Commonwealth of Virginia J. C. Peterson who signed the foregoing Certificate of Analysis, before me, and after being duly sworn, made that he performed the analysis and/or examination the results of which are herein contained, (2) that said analysis and/or examination was performed in a laboratory operated by the Division of Consolidated Laboratory Services of the Commonwealth or authorized by such Division to conduct such analysis and/or examination and (3) that the Certificate of Analysis is true and correct.

Given under my hand this 22 day of Dec, 1983

My commission expires May 18, 1987

Page 1 of 1

ORIGINAL  
(Red)

APPENDIX C

MICROTOX® ANALYSIS REPORT  
WATERS AND SEDIMENTS OF  
MASSEY RUN AND HOGUE CREEK

RHINEHART TIRE FIRE  
Winchester, Virginia

NOVEMBER 18, 1983



ENVIRONMENTAL RESPONSE TEAM  
WOODBIDGE AVENUE, EDISON, NEW JERSEY

AR100391



MICROTOX ANALYSIS REPORT ON  
THE SEDIMENT AND AQUEOUS  
SAMPLES FROM THE RHINEHART TIRE FIRE

On November 18, 1983, eleven aqueous samples and eight sediment samples were taken for Microtox analysis. The samples were taken from the site of the Rhinehart tire fire response in West Virginia. The site was located in a valley in which an estimated five million tires were stored and it was suspected that arson was responsible for starting the blaze. The Microtox samples taken were from the nearby stream into which some of the contaminants of the fire were flowing.

The samples were received on November 19, and had been kept cool during transport in an ice chest. The Microtox sediment samples were extracted using the method described in the microtox application notes M105, September 1, 1982. The recommended extraction procedure required mixing one part sediment samples to five parts distilled water (w/v). Approximately five grams of each sediment sample was added to twenty five milliliters of distilled water and placed in a fifty milliliter Wheaton bottle. A magnetic stir bar was added, the bottles were closed with teflon seals and extracted for twenty four hours. Samples were allowed to settle and were then filtered using a 0.45um disposable teflon filter. Light readings were taken at five and ten minute intervals. Operating conditions were as follows: Turret assembly 15.0 C, and incubator 2.5 C. All calculations were based upon the mean of duplicate  $I_5$  sample analyses.

AR100392

## A. Aqueous Samples

ORIGINAL  
(Red)

<u>Sample</u>	<u>pH</u>	<u>Concentration</u>	Io	15	NPLD
Blank	6.0	0.0%	77	72	—
		5.65%	74	71	+1.4
		11.3%	74	71	+1.4
		22.5%	75	70	+1.4
		45.0%	70	67	+1.5
01833	6.0	0.0%	79	65	—
		5.65%	76	46	26.0%
		11.3%	77	49	38.0%
		22.5%	74	28	54.0%
		45.0%	68	18	68.0%
01830	7.0	0.0%	82	69	—
		5.65%	79	67	+1.5
		11.3%	77	67	+3.1
		22.5%	77	65	0.0
		45.0%	72	65	+8.3
01831	6.0	0.0%	76	68	—
		5.65%	74	65	1.5
		11.3%	74	65	1.5
		22.5%	73	65	0.0
		45.0%	73	64	1.5

AR100393

## MICROTOX ANALYSIS DATA

ORIGINAL  
(Red)Aqueous Samples (Continued)

<u>Sample</u>	<u>pH</u>	<u>Concentration</u>	<u>Io</u>	<u>15</u>	<u>NPLD</u>
01834	6.0	0.0%	80	54	—
		5.65%	84	42	26.3
		11.3%	82	34	39.3
		22.5%	77	23	55.8
		45.0%	78	13	75.5
01835	5.5	0.0%	80	60	—
		5.65%	78	46	22.0
		11.3%	79	38	35.6
		22.5%	75	26	53.6
		45.5%	73	17	69.0
01836	6.0	0.0%	75	56	—
		5.65%	70	52	1.9
		11.3%	70	52	1.9
		22.5%	67	50	0.0
		45.0%	66	54	+8.0
01837	7.0	0.0%	80	60	—
		5.65%	81	58	4.9
		11.3%	78	58	1.7
		22.5%	75	53	5.4
		45.0%	74	53	5.4

AR100394

MICROTOX ANALYSIS DATAORIGINAL  
(Red)

## B. Sediment Samples

<u>Sample</u>	<u>pH</u>	<u>Concentration</u>	<u>Io</u>	<u>15</u>	<u>NPLD</u>
01838	6.0	0.0%	82	61	—
		5.65%	79	57	1.7
		11.3%	76	50	10.7
		22.5	79	47	19.0
		45.0	74	36	34.5
01839	6.0	0.0%	75	66	—
		5.65%	71	48	22.6
		11.3%	64	38	32.1
		22.5%	68	30	50.0
		45.0%	65	21	63.2
01832	6.0	0.0%	79	66	—
		5.65%	76	57	10.9
		11.3%	75	51	19.0
		22.5%	75	44	30.1
		45.0%	74	33	46.8

AR100395

MICROTOX ANALYSIS DATA

## B. Sediment Samples

<u>Sample</u>	<u>pH</u>	<u>Concentration</u>	<u>Io</u>	<u>15</u>	<u>NPLD</u>
01830	7.0	0.0%	79	68	—
		1.2%	70	58	3.3
		2.3%	68	55	5.1
		4.5%	64	54	1.8
		9.0%	65	47	16.1
01831	7.0	0.0%	83	74	—
		1.2%	88	76	2.6
		2.3%	84	75	0.01
		4.5%	80	64	9.9
		9.0%	78	55	20.7
01832	7.0	0.0%	82	72	—
		1.2%	77	67	1.5
		2.3%	76	64	4.5
		4.5%	70	60	3.3
		9.0%	70	55	11.3
01833	7.0	0.0%	89	75	—
		1.2%	86	70	2.8
		2.3%	81	63	7.4
		4.5%	77	58	10.8
		9.0%	74	51	17.7

AR100396

## MICROTOX ANALYSIS DATA

ORIGINAL  
(Red)Sediment Samples (Continued)

<u>Sample</u>	<u>pH</u>	<u>Concentration</u>	<u>Io</u>	<u>15</u>	<u>NPLD</u>
01834	7.0	0.0%	75	64	—
		1.2%	67	40	29.8
		2.3%	62	30	24.5
		4.5%	66	23	58.9
		9.0%	57	14	70.8
01835	7.0	0.0%	78	60	—
		1.2%	76	55	6.7
		2.3%	73	50	6.7
		4.5%	71	44	20.0
		9.0%	65	34	32.0
01836	6.0	0.0%	79	72	—
		1.2%	76	67	2.9
		2.3%	77	67	4.3
		4.5%	75	65	4.4
		9.0%	76	61	11.6
01837	7.0	0.0%	81	63	—
		1.2%	82	60	6.3
		2.3%	79	56	9.7
		4.5%	76	54	8.5
		9.0%	75	53	10.2

AR100397

## DISCUSSION OF RESULTS

ORIGINAL  
(Red)

Microtox samples were divided into two categories; sediment and aqueous sample. In aqueous samples were analyzed at a 2:1 dilution scheme resulting in the following sample concentrations: 5.65%, 11.3%, 22.5%, 45.0%. All samples were in the pH range of 6.0 to 7.0. Samples that displayed Microtox NPLD responses between +15.0% and 15% were rated as background clean, those with responses between 15.1% and 30% were rated as moderate, and those with responses above 30.1% were rated as significant. Since actual sampling locations were not provided, the samples were only examined in relation to their relative toxicity to one another. An overall view of sampling locations in relation to the source of contamination as well as controls would significantly aid evaluating the data.

The following data is the categorizing of the aqueous data in terms of increasing toxicity.

<u>Sample</u>	<u>Rating</u>	<u>Response</u>
Blank	Clean	Stimulatory responses up to +1.5%
1830	Clean	Stimulatory responses up to +8.3%
1831	Clean	Responses up to 1.5%
1836	Clean	Stimulatory responses up to +8.0%
1837	Clean	Responses up to 5.4%
1838	Moderate	Responses ranging from 1.7% to 34.5%
1832	Moderate	Responses ranging from 10.9% to 46.8%
1839	Significant	Responses ranging from 22.2% to 63.2%
1833*	Significant	Responses ranging from 26.0% to 68.0%
1835*	Significant	Responses ranging from 22.0% to 69.0%
1834	Significant	Responses ranging from 26.3% to 75.5%

\*These samples appear to share a similar concentration to response range and thus share the same order of toxicity.

AR100398